

# PIC18FXX2 Data Sheet

High Performance, Enhanced FLASH Microcontrollers with 10-Bit A/D

#### Note the following details of the code protection feature on PICmicro® MCUs.

- · The PICmicro family meets the specifications contained in the Microchip Data Sheet.
- Microchip believes that its family of PICmicro microcontrollers is one of the most secure products of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our knowledge, require using the PICmicro microcontroller in a manner outside the operating specifications contained in the data sheet.
   The person doing so may be engaged in theft of intellectual property.
- · Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable".
- Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our product.

If you have any further questions about this matter, please contact the local sales office nearest to you.

Information contained in this publication regarding device applications and the like is intended through suggestion only and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. No representation or warranty is given and no liability is assumed by Microchip Technology Incorporated with respect to the accuracy or use of such information, or infringement of patents or other intellectual property rights arising from such use or otherwise. Use of Microchip's products as critical components in life support systems is not authorized except with express written approval by Microchip. No licenses are conveyed, implicitly or otherwise, under any intellectual property rights.

#### Trademarks

The Microchip name and logo, the Microchip logo, KEELOQ, MPLAB, PIC, PICMicro, PICSTART and PRO MATE are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

FilterLab, microID, MXDEV, MXLAB, PICMASTER, SEEVAL and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

dsPIC, dsPICDEM.net, ECONOMONITOR, FanSense, FlexROM, fuzzyLAB, In-Circuit Serial Programming, ICSP, ICEPIC, microPort, Migratable Memory, MPASM, MPLIB, MPLINK, MPSIM, PICC, PICDEM, PICDEM.net, rfPIC, Select Mode and Total Endurance are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

Serialized Quick Turn Programming (SQTP) is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2002, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.





Microchip received QS-9000 quality system certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona in July 1999 and Mountain View, California in March 2002. The Company's quality system processes and procedures are QS-9000 compliant for its PICmicro® 8-bit MCUs, KEELOQ® code hopping devices, Serial EEPROMs, microperipherals, non-volatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001 certified.



# 28/40-pin High Performance, Enhanced FLASH Microcontrollers with 10-Bit A/D

### **High Performance RISC CPU:**

- · C compiler optimized architecture/instruction set
  - Source code compatible with the PIC16 and PIC17 instruction sets
- · Linear program memory addressing to 32 Kbytes
- · Linear data memory addressing to 1.5 Kbytes

Device		hip Program Memory	On-Chip	Data EEPROM	
Device	FLASH (bytes)	# Single Word Instructions	(bytes)	(bytes)	
PIC18F242	16K	8192	768	256	
PIC18F252	32K	16384	1536	256	
PIC18F442	16K	8192	768	256	
PIC18F452	32K	16384	1536	256	

- · Up to 10 MIPs operation:
  - DC 40 MHz osc./clock input
  - 4 MHz 10 MHz osc./clock input with PLL active
- · 16-bit wide instructions, 8-bit wide data path
- · Priority levels for interrupts
- 8 x 8 Single Cycle Hardware Multiplier

### **Peripheral Features:**

- · High current sink/source 25 mA/25 mA
- · Three external interrupt pins
- Timer0 module: 8-bit/16-bit timer/counter with 8-bit programmable prescaler
- · Timer1 module: 16-bit timer/counter
- Timer2 module: 8-bit timer/counter with 8-bit period register (time-base for PWM)
- · Timer3 module: 16-bit timer/counter
- · Secondary oscillator clock option Timer1/Timer3
- Two Capture/Compare/PWM (CCP) modules.
   CCP pins that can be configured as:
  - Capture input: capture is 16-bit, max. resolution 6.25 ns (Tcy/16)
  - Compare is 16-bit, max. resolution 100 ns (Tcy)
  - PWM output: PWM resolution is 1- to 10-bit, max. PWM freq. @: 8-bit resolution = 156 kHz 10-bit resolution = 39 kHz
- Master Synchronous Serial Port (MSSP) module, Two modes of operation:
  - 3-wire SPI™ (supports all 4 SPI modes)
  - I<sup>2</sup>C™ Master and Slave mode

### Peripheral Features (Continued):

- · Addressable USART module:
  - Supports RS-485 and RS-232
- Parallel Slave Port (PSP) module

### **Analog Features:**

- Compatible 10-bit Analog-to-Digital Converter module (A/D) with:
  - Fast sampling rate
  - Conversion available during SLEEP
  - Linearity ≤ 1 LSb
- · Programmable Low Voltage Detection (PLVD)
  - Supports interrupt on-Low Voltage Detection
- · Programmable Brown-out Reset (BOR)


### **Special Microcontroller Features:**

- 100,000 erase/write cycle Enhanced FLASH program memory typical
- 1,000,000 erase/write cycle Data EEPROM memory
- FLASH/Data EEPROM Retention: > 40 years
- · Self-reprogrammable under software control
- Power-on Reset (POR), Power-up Timer (PWRT) and Oscillator Start-up Timer (OST)
- Watchdog Timer (WDT) with its own On-Chip RC Oscillator for reliable operation
- · Programmable code protection
- · Power saving SLEEP mode
- · Selectable oscillator options including:
  - 4X Phase Lock Loop (of primary oscillator)
  - Secondary Oscillator (32 kHz) clock input
- Single supply 5V In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) via two pins
- · In-Circuit Debug (ICD) via two pins


### **CMOS Technology:**

- Low power, high speed FLASH/EEPROM technology
- Fully static design
- Wide operating voltage range (2.0V to 5.5V)
- Industrial and Extended temperature ranges
- · Low power consumption:
  - < 1.6 mA typical @ 5V, 4 MHz
  - 25 μA typical @ 3V, 32 kHz
  - < 0.2 μA typical standby current

### Pin Diagrams



### Pin Diagrams (Cont.'d)



### **Table of Contents**

1.0	Device Overview	7
2.0	Oscillator Configurations	. 17
3.0	Reset	. 25
4.0	Memory Organization	. 35
5.0	FLASH Program Memory	. 55
6.0	Data EEPROM Memory	. 65
7.0	8 X 8 Hardware Multiplier	. 71
8.0	Interrupts	. 73
9.0	I/O Ports	. 87
10.0	Timer0 Module	103
11.0	Timer1 Module	107
12.0	Timer2 Module	111
13.0	Timer3 Module	
14.0	Capture/Compare/PWM (CCP) Modules	117
15.0	Master Synchronous Serial Port (MSSP) Module	
16.0	Addressable Universal Synchronous Asynchronous Receiver Transmitter (USART)	165
17.0	Compatible 10-bit Analog-to-Digital Converter (A/D) Module	181
18.0	Low Voltage Detect	189
19.0	Special Features of the CPU	195
20.0	Instruction Set Summary	211
21.0	Development Support	253
	Electrical Characteristics	
23.0	DC and AC Characteristics Graphs and Tables	289
24.0	Packaging Information	305
Appe	ndix A: Revision History	313
Appe	ndix B: Device Differences	313
Appe	ndix C: Conversion Considerations	314
Appe	ndix D: Migration from Baseline to Enhanced Devices	314
Appe	ndix E: Migration from Mid-range to Enhanced Devices	315
Appe	ndix F: Migration from High-end to Enhanced Devices	315
		_
On-Li	ne Support	327
Read	er Response	328
PIC18	3FXX2 Product Identification System	329

### TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@mail.microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000A is version A of document DS30000).

#### **Errata**

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- · Microchip's Worldwide Web site; http://www.microchip.com
- · Your local Microchip sales office (see last page)
- The Microchip Corporate Literature Center; U.S. FAX: (480) 792-7277

When contacting a sales office or the literature center, please specify which device, revision of silicon and data sheet (include literature number) you are using.

### **Customer Notification System**

Register on our web site at www.microchip.com/cn to receive the most current information on all of our products.

NOTES:

### 1.0 DEVICE OVERVIEW

This document contains device specific information for the following devices:

PIC18F242PIC18F442PIC18F252PIC18F452


These devices come in 28-pin and 40/44-pin packages. The 28-pin devices do not have a Parallel Slave Port (PSP) implemented and the number of Analog-to-Digital (A/D) converter input channels is reduced to 5. An overview of features is shown in Table 1-1.

The following two figures are device block diagrams sorted by pin count: 28-pin for Figure 1-1 and 40/44-pin for Figure 1-2. The 28-pin and 40/44-pin pinouts are listed in Table 1-2 and Table 1-3, respectively.

### TABLE 1-1: DEVICE FEATURES

Features	PIC18F242	PIC18F252	PIC18F442	PIC18F452
Operating Frequency	DC - 40 MHz			
Program Memory (Bytes)	16K	32K	16K	32K
Program Memory (Instructions)	8192	16384	8192	16384
Data Memory (Bytes)	768	1536	768	1536
Data EEPROM Memory (Bytes)	256	256	256	256
Interrupt Sources	17	17	18	18
I/O Ports	Ports A, B, C	Ports A, B, C	Ports A, B, C, D, E	Ports A, B, C, D, E
Timers	4	4	4	4
Capture/Compare/PWM Modules	2	2	2	2
Serial Communications	MSSP, Addressable USART	MSSP, Addressable USART	MSSP, Addressable USART	MSSP, Addressable USART
Parallel Communications	_	_	PSP	PSP
10-bit Analog-to-Digital Module	5 input channels	5 input channels	8 input channels	8 input channels
RESETS (and Delays)	POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST)			
Programmable Low Voltage Detect	Yes	Yes	Yes	Yes
Programmable Brown-out Reset	Yes	Yes	Yes	Yes
Instruction Set	75 Instructions	75 Instructions	75 Instructions	75 Instructions
Packages	28-pin DIP 28-pin SOIC	28-pin DIP 28-pin SOIC	40-pin DIP 44-pin PLCC 44-pin TQFP	40-pin DIP 44-pin PLCC 44-pin TQFP

FIGURE 1-1: PIC18F2X2 BLOCK DIAGRAM Data Bus<8> **PORTA** Table Pointer Data Latch RA0/AN0 -8 RA1/AN1 Data RAM inc/dec logic RA2/AN2/VREF-RA3/AN3/VREF+ Address Latch RA4/T0CKI RA5/AN4/SS/LVDIN PCLATU PCLATH 12(2) Address Latch RA6 Address<12> Program Memory PCU | PCH | PCL (up to 2 Mbytes) Program Counter 12 N **4**\ Data Latch BSR FSR0 Bank0, F FSR1 31 Level Stack FSR2 12 16 inc/dec Decode logic Table Latch PORTB 8 ROM Latch RB0/INT0 RB1/INT1 RB2/INT2 Instruction RB3/CCP2(1) Register RB4 RB5/PGM 8 Instruction RB6/PCG Decode & RB7/PGD Control PRODH PRODL OSC2/CLKO 3 OSC1/CLKI 8 x 8 Multiply Power-up Timer Timing Oscillator T10SCI T10SCO BIT OP WREG Generation Start-up Time Power-on Reset ∤8 Watchdog 4X PLL ALU<8: Timer PORTC RC0/T1OSO/T1CKI RC1/T1OSI/CCP2(1) Brown-out 8 Precision Reset RC2/CCP1 Voltage Reference RC3/SCK/SCL Low Voltage MCLR RC4/SDI/SDA Programming  $\square$ RC5/SDO In-Circuit RC6/TX/CK VDD, VSS



- 2: The high order bits of the Direct Address for the RAM are from the BSR register (except for the MOVFF instruction).
- 3: Many of the general purpose I/O pins are multiplexed with one or more peripheral module functions. The multiplexing combinations are device dependent.

FIGURE 1-2: PIC18F4X2 BLOCK DIAGRAM Data Bus<8> PORTA BAO/ANO Table Pointer Data Latch RA1/AN1 Data RAM RA2/AN2/VREF-(up to 4K RA3/AN3/VREF+ inc/dec logic address reach) RA4/T0CKI RA5/AN4/SS/LVDIN Address Latch RA6 21 12(2) PCLATU PCLATH Address Latch Program Memory Address<12> PCU PCH PCL (up to 2 Mbytes) **PORTB** Program Counter **4**N 12 \ 4 Data Latch RB0/INT0 BSR FSR0 Bank0, F RB1/INT1 FSR1 31 Level Stack RB2/INT2 FSR2 RB3/CCP2<sup>(1)</sup> 12 RB4 RB5/PGM 16 inc/dec Decode RB6/PCG logic Table Latch RB7/PGD ₩8 ROM Latch PORTC RC0/T1OSO/T1CKI RC1/T1OSI/CCP2(1) RC2/CCP1 Instruction Register RC3/SCK/SCL RC4/SDI/SDA 8 RC5/SDO Instruction RC6/TX/CK Decode & RC7/RX/DT Control PRODH PRODL OSC2/CLKO 3 OSC1/CLKI 8 x 8 Multiply Power-up PORTD Timer RD0/PSP0 Timing RD1/PSP1 Oscillator T1OSCI T1OSCO BIT OP WREG Generation Start-up Time RD2/PSP2 RD3/PSP3  $\mathbb{Z}$ Power-on RD4/PSP4 Reset ∤8 RD5/PSP5 Watchdog 4X PLL RD6/PSP6 ALV<8> Timer RD7/PSP7 Brown-out Precision Reset PORTE Voltage Reference Low Voltage MCLR RE0/AN5/RD ⊃rogramming  $\boxtimes$ In-Circuit RE1/AN6/WR VDD, VSS Debugger X RE2/AN7/CS A/D Converter Timer0 Timer1 Timer2 Timer3 Master Addressable CCP1 Synchronous Data EEPROM Parallel Slave Port CCP2 USART Serial Port 1: Optional multiplexing of CCP2 input/output with RB3 is enabled by selection of configuration bit. Note 2: The high order bits of the Direct Address for the RAM are from the BSR register (except for the MOVFF instruction). 3: Many of the general purpose I/O pins are multiplexed with one or more peripheral module functions. The multiplexing combinations are device dependent.

© 2002 Microchip Technology Inc.

**TABLE 1-2:** PIC18F2X2 PINOUT I/O DESCRIPTIONS

Pin Name	Pin N	umber	Pin	Buffer	Description
Pili Name	DIP	SOIC	Туре	Туре	Description
MCLR/VPP	1	1			Master Clear (input) or high voltage ICSP programming
MCLR			1	ST	enable pin.  Master Clear (Reset) input. This pin is an active low RESET to the device.
VPP			I	ST	High voltage ICSP programming enable pin.
NC	_	_	_	_	These pins should be left unconnected.
OSC1/CLKI OSC1	9	9	ı	ST	Oscillator crystal or external clock input.  Oscillator crystal input or external clock source input.  ST buffer when configured in RC mode, CMOS otherwise.
CLKI			I	CMOS	External clock source input. Always associated with pin function OSC1. (See related OSC1/CLKI, OSC2/CLKO pins.)
OSC2/CLKO/RA6 OSC2	10	10	0	_	Oscillator crystal or clock output. Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode.
CLKO			0	_	In RC mode, OSC2 pin outputs CLKO which has 1/4 the frequency of OSC1, and denotes the instruction
RA6			I/O	TTL	cycle rate. General Purpose I/O pin.
					PORTA is a bi-directional I/O port.
RA0/AN0	2	2			
RA0			1/0	TTL	Digital I/O.
ANO			ı	Analog	Analog input 0.
RA1/AN1 RA1	3	3	I/O	TTL	Digital I/O.
AN1			ı, O	Analog	Analog input 1.
RA2/AN2/VREF-	4	4		· ·	
RA2			I/O	TTL	Digital I/O.
AN2			I	Analog	Analog input 2.
VREF-	_	_	ı	Analog	A/D Reference Voltage (Low) input.
RA3/AN3/VREF+ RA3	5	5	I/O	TTL	Digital I/O.
AN3			ı, O	Analog	Analog input 3.
VREF+			- 1	Analog	A/D Reference Voltage (High) input.
RA4/T0CKI	6	6			
RA4 T0CKI			I/O I	ST/OD ST	Digital I/O. Open drain when configured as output. Timer0 external clock input.
RA5/AN4/SS/LVDIN	7	7			
RA5			I/O	TTL	Digital I/O.
AN4			1	Analog	Analog input 4.
SS LVDIN				ST Analog	SPI Slave Select input. Low Voltage Detect Input.
RA6			'	Analog	See the OSC2/CLKO/RA6 pin.
10.0					oco ino odoz/otrico pin.

Legend: TTL = TTL compatible input

ST = Schmitt Trigger input with CMOS levels

O = Output

OD = Open Drain (no P diode to VDD)

CMOS = CMOS compatible input or output

I = Input

TABLE 1-2: PIC18F2X2 PINOUT I/O DESCRIPTIONS (CONTINUED)

Pin Name	Pin Number		Pin Buffer		Description	
Fili Name	DIP	SOIC	Туре	Туре	Description	
					PORTB is a bi-directional I/O port. PORTB can be software programmed for internal weak pull-ups on all inputs.	
RB0/INT0	21	21				
RB0			I/O	TTL	Digital I/O.	
INT0			I	ST	External Interrupt 0.	
RB1/INT1	22	22				
RB1			I/O	TTL		
INT1			1	ST	External Interrupt 1.	
RB2/INT2	23	23				
RB2			1/0	TTL	Digital I/O.	
INT2			ı	ST	External Interrupt 2.	
RB3/CCP2	24	24				
RB3			1/0	TTL	Digital I/O.	
CCP2			I/O	ST	Capture2 input, Compare2 output, PWM2 output.	
RB4	25	25	I/O	TTL	Digital I/O. Interrupt-on-change pin.	
RB5/PGM	26	26				
RB5			I/O	TTL	Digital I/O. Interrupt-on-change pin.	
PGM			I/O	ST	Low Voltage ICSP programming enable pin.	
RB6/PGC	27	27				
RB6			I/O	TTL	Digital I/O. Interrupt-on-change pin.	
PGC			I/O	ST	In-Circuit Debugger and ICSP programming clock pin.	
RB7/PGD	28	28				
RB7			I/O	TTL	Digital I/O. Interrupt-on-change pin.	
PGD			1/0	ST	In-Circuit Debugger and ICSP programming data pin.	

Legend: TTL = TTL compatible input

ST = Schmitt Trigger input with CMOS levels

O = Output

OD = Open Drain (no P diode to VDD)

CMOS = CMOS compatible input or output

I = Input

TABLE 1-2: PIC18F2X2 PINOUT I/O DESCRIPTIONS (CONTINUED)

Pin Name	Pin Number		Pin	Buffer	Description		
Pili Name	DIP	SOIC	Туре	Туре	Description		
					PORTC is a bi-directional I/O port.		
RC0/T1OSO/T1CKI	11	11					
RC0			I/O	ST	Digital I/O.		
T10S0			0	_	Timer1 oscillator output.		
T1CKI				ST	Timer1/Timer3 external clock input.		
RC1/T1OSI/CCP2	12	12					
RC1			I/O	ST	Digital I/O.		
T1OSI			1/0	CMOS	Timer1 oscillator input.		
CCP2			I/O	ST	Capture2 input, Compare2 output, PWM2 output.		
RC2/CCP1	13	13	1/0	O.T.	District 1/O		
RC2 CCP1			I/O I/O	ST ST	Digital I/O. Capture1 input/Compare1 output/PWM1 output.		
			1/0	31	Capturer input/Comparer output/Pytivir output.		
RC3/SCK/SCL RC3	14	14	I/O	ST	Digital I/O.		
SCK			1/0	ST	Synchronous serial clock input/output for SPI mode.		
SCL			1/0	ST	Synchronous serial clock input/output for I <sup>2</sup> C mode		
RC4/SDI/SDA	15	15			Synometrous containers in the mode		
RC4	'0	'0	I/O	ST	Digital I/O.		
SDI			1	ST	SPI Data In.		
SDA			I/O	ST	I <sup>2</sup> C Data I/O.		
RC5/SDO	16	16					
RC5			I/O	ST	Digital I/O.		
SDO			0	_	SPI Data Out.		
RC6/TX/CK	17	17					
RC6			I/O	ST	Digital I/O.		
TX			0	_	USART Asynchronous Transmit.		
CK			I/O	ST	USART Synchronous Clock (see related RX/DT).		
RC7/RX/DT	18	18		O.T.	B: 11.11/0		
RC7 RX			1/0	ST	Digital I/O.		
DT			1/0	ST ST	USART Asynchronous Receive. USART Synchronous Data (see related TX/CK).		
Vss	8, 19	8, 19	P		Ground reference for logic and I/O pins.		
					-		
VDD	20	20	Р	_	Positive supply for logic and I/O pins.		

Legend: TTL = TTL compatible input

ST = Schmitt Trigger input with CMOS levels

O = Output

OD = Open Drain (no P diode to VDD)

CMOS = CMOS compatible input or output

I = Input

TABLE 1-3: PIC18F4X2 PINOUT I/O DESCRIPTIONS

Pin Name	Pi	n Numt	er	Pin	Buffer	Description
Pili Name	DIP	PLCC	TQFP	Туре	Туре	Description
MCLR/VPP MCLR	1	2	18	ı	ST	Master Clear (input) or high voltage ICSP programming enable pin.  Master Clear (Reset) input. This pin is an active low RESET to the device.
VPP				I	ST	High voltage ICSP programming enable pin.
NC	_			_	_	These pins should be left unconnected.
OSC1/CLKI OSC1	13	14	30	1	ST	Oscillator crystal or external clock input.  Oscillator crystal input or external clock source input. ST buffer when configured in RC mode, CMOS otherwise.
CLKI				I	CMOS	External clock source input. Always associated with pin function OSC1. (See related OSC1/CLKI, OSC2/CLKO pins.)
OSC2/CLKO/RA6 OSC2	14	15	31	0	_	Oscillator crystal or clock output. Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode.
CLKO				0	_	In RC mode, OSC2 pin outputs CLKO, which has 1/4 the frequency of OSC1 and denotes the instruction cycle rate.
RA6				I/O	ΤΤL	General Purpose I/O pin.
						PORTA is a bi-directional I/O port.
RA0/AN0 RA0 AN0	2	3	19	I/O I	TTL Analog	Digital I/O. Analog input 0.
RA1/AN1 RA1 AN1	3	4	20	I/O I	TTL Analog	Digital I/O. Analog input 1.
RA2/AN2/VREF- RA2	4	5	21	1/0	TTL	Digital I/O.
AN2 VREF-	_			I	Analog Analog	Analog input 2.  A/D Reference Voltage (Low) input.
RA3/AN3/VREF+ RA3 AN3 VREF+	5	6	22	I/O I I	TTL Analog Analog	Digital I/O. Analog input 3. A/D Reference Voltage (High) input.
RA4/T0CKI RA4 T0CKI	6	7	23	I/O I	ST/OD ST	Digital I/O. Open drain when configured as output. Timer0 external clock input.
RA5/AN4/SS/LVDIN RA5 AN4 SS LVDIN	7	8	24	I/O    - 	TTL Analog ST Analog	Digital I/O. Analog input 4. SPI Slave Select input. Low Voltage Detect Input.
RA6	- 41					(See the OSC2/CLKO/RA6 pin.)

Legend: TTL = TTL compatible input

ST = Schmitt Trigger input with CMOS levels

O = Output

OD = Open Drain (no P diode to VDD)

CMOS = CMOS compatible input or output

I = Input

TABLE 1-3: PIC18F4X2 PINOUT I/O DESCRIPTIONS (CONTINUED)

Pin Name	Pin Number			Pin	Pin Buffer	Description	
Pili Name	DIP	PLCC	TQFP	Туре	Туре	Description	
						PORTB is a bi-directional I/O port. PORTB can be	
						software programmed for internal weak pull-ups on all inputs.	
RB0/INT0	33	36	8				
RB0				I/O	TTL	Digital I/O.	
INT0				1	ST	External Interrupt 0.	
RB1/INT1	34	37	9				
RB1				I/O	TTL		
INT1				I	ST	External Interrupt 1.	
RB2/INT2	35	38	10				
RB2				I/O	TTL	Digital I/O.	
INT2				1	ST	External Interrupt 2.	
RB3/CCP2	36	39	11				
RB3				I/O	TTL	Digital I/O.	
CCP2				I/O	ST	Capture2 input, Compare2 output, PWM2 output.	
RB4	37	41	14	I/O	TTL	Digital I/O. Interrupt-on-change pin.	
RB5/PGM	38	42	15				
RB5				I/O	TTL	Digital I/O. Interrupt-on-change pin.	
PGM				I/O	ST	Low Voltage ICSP programming enable pin.	
RB6/PGC	39	43	16				
RB6				I/O	TTL	Digital I/O. Interrupt-on-change pin.	
PGC				I/O	ST	In-Circuit Debugger and ICSP programming clock pin.	
RB7/PGD	40	44	17				
RB7				I/O	TTL	Digital I/O. Interrupt-on-change pin.	
PGD				I/O	ST	In-Circuit Debugger and ICSP programming data pin.	

Legend: TTL = TTL compatible input

ST = Schmitt Trigger input with CMOS levels

O = Output

OD = Open Drain (no P diode to VDD)

CMOS = CMOS compatible input or output

I = Input

TABLE 1-3: PIC18F4X2 PINOUT I/O DESCRIPTIONS (CONTINUED)

Din Nome	Pin Number			Pin Buffer	Donasistics.	
Pin Name	DIP	PLCC	TQFP	Туре	Туре	Description
						PORTC is a bi-directional I/O port.
RC0/T1OSO/T1CKI RC0 T1OSO T1CKI	15	16	32	I/O O I	ST — ST	Digital I/O. Timer1 oscillator output. Timer1/Timer3 external clock input.
RC1/T1OSI/CCP2 RC1 T1OSI CCP2	16	18	35	I/O I I/O	ST CMOS ST	Digital I/O. Timer1 oscillator input. Capture2 input, Compare2 output, PWM2 output.
RC2/CCP1 RC2 CCP1	17	19	36	I/O I/O	ST ST	Digital I/O. Capture1 input/Compare1 output/PWM1 output.
RC3/SCK/SCL RC3 SCK	18	20	37	I/O I/O	ST ST	Digital I/O. Synchronous serial clock input/output for SPI mode.
SCL				I/O	ST	Synchronous serial clock input/output for I <sup>2</sup> C mode.
RC4/SDI/SDA RC4 SDI SDA	23	25	42	I/O I I/O	ST ST ST	Digital I/O. SPI Data In. I <sup>2</sup> C Data I/O.
RC5/SDO RC5 SDO	24	26	43	I/O O	ST —	Digital I/O. SPI Data Out.
RC6/TX/CK RC6 TX CK	25	27	44	I/O O I/O	ST — ST	Digital I/O. USART Asynchronous Transmit. USART Synchronous Clock (see related RX/DT).
RC7/RX/DT RC7 RX DT	26	29	1	I/O I I/O	ST ST ST	Digital I/O. USART Asynchronous Receive. USART Synchronous Data (see related TX/CK).

Legend: TTL = TTL compatible input

ST = Schmitt Trigger input with CMOS levels

O = Output

OD = Open Drain (no P diode to VDD)

CMOS = CMOS compatible input or output

I = Input

TABLE 1-3: PIC18F4X2 PINOUT I/O DESCRIPTIONS (CONTINUED)

Pin Name	Pi	n Numb	er	Pin	Buffer	Description
Pili Name	DIP	PLCC	TQFP	Туре	Туре	Description
						PORTD is a bi-directional I/O port, or a Parallel Slave Port (PSP) for interfacing to a microprocessor port. These pins have TTL input buffers when PSP module is enabled.
RD0/PSP0	19	21	38	I/O	ST TTL	Digital I/O. Parallel Slave Port Data.
RD1/PSP1	20	22	39	I/O	ST TTL	Digital I/O. Parallel Slave Port Data.
RD2/PSP2	21	23	40	I/O	ST TTL	Digital I/O. Parallel Slave Port Data.
RD3/PSP3	22	24	41	I/O	ST TTL	Digital I/O. Parallel Slave Port Data.
RD4/PSP4	27	30	2	I/O	ST TTL	Digital I/O. Parallel Slave Port Data.
RD5/PSP5	28	31	3	I/O	ST TTL	Digital I/O. Parallel Slave Port Data.
RD6/PSP6	29	32	4	I/O	ST TTL	Digital I/O. Parallel Slave Port Data.
RD7/PSP7	30	33	5	I/O	ST TTL	Digital I/O. Parallel Slave Port Data.
						PORTE is a bi-directional I/O port.
RE0/RD/AN5 RE0 RD	8	9	25	I/O	ST TTL	Digital I/O. Read control for parallel slave port (see also WR and CS pins).
AN5					Analog	Analog input 5.
RE1/WR/AN6 RE1 WR	9	10	26	I/O	ST TTL	Digital I/O. Write control for parallel slave port (see CS and RD pins).
AN6					Analog	Analog input 6.
RE2/CS/AN7 RE2 CS	10	11	27	I/O	ST TTL	Digital I/O. Chip Select control for parallel slave port (see related RD and WR).
AN7 Vss	10 21	13, 34	6 20	Р	Analog	Analog input 7.  Ground reference for logic and I/O pins.
VDD		12, 35		P	_	Positive supply for logic and I/O pins.
* 50	11,02	12, 00	1,20	'		i ositive supply for logic and 1/O pins.

Legend: TTL = TTL compatible input

ST = Schmitt Trigger input with CMOS levels

O = Output

OD = Open Drain (no P diode to VDD)

CMOS = CMOS compatible input or output

I = Input

### 2.0 OSCILLATOR CONFIGURATIONS

### 2.1 Oscillator Types

The PIC18FXX2 can be operated in eight different Oscillator modes. The user can program three configuration bits (FOSC2, FOSC1, and FOSC0) to select one of these eight modes:

1.	LP	Low Power Crystal						
2.	XT	Crystal/Resonator						
3.	HS	High Speed Crystal/Resonator						
4.	HS + PLL	High Speed Crystal/Resonator with PLL enabled						
5.	RC	External Resistor/Capacitor						
6.	RCIO	External Resistor/Capacitor with I/O pin enabled						
7.	EC	External Clock						
8.	ECIO	External Clock with I/O pin enabled						


### 2.2 Crystal Oscillator/Ceramic Resonators

In XT, LP, HS or HS+PLL Oscillator modes, a crystal or ceramic resonator is connected to the OSC1 and OSC2 pins to establish oscillation. Figure 2-1 shows the pin connections.

The PIC18FXX2 oscillator design requires the use of a parallel cut crystal.

**Note:** Use of a series cut crystal may give a frequency out of the crystal manufacturers specifications.

# FIGURE 2-1: CRYSTAL/CERAMIC RESONATOR OPERATION (HS, XT OR LP CONFIGURATION)



Note 1: See Table 2-1 and Table 2-2 for recommended values of C1 and C2.

- 2: A series resistor (Rs) may be required for AT strip cut crystals.
- 3: RF varies with the Oscillator mode chosen.

TABLE 2-1: CAPACITOR SELECTION FOR CERAMIC RESONATORS

Ranges Tested:								
Mode	Freq	C1	C2					
XT	455 kHz	68 - 100 pF	68 - 100 pF					
	2.0 MHz	15 - 68 pF	15 - 68 pF					
	4.0 MHz	15 - 68 pF	15 - 68 pF					
HS	8.0 MHz	10 - 68 pF	10 - 68 pF					
	16.0 MHz	10 - 22 pF	10 - 22 pF					
These valu	ues are for de	sign guidance	only.					
See notes	following this	table.						
	Resona	ntors Used:						
455 kHz	Panasonic E	FO-A455K04B	± 0.3%					
2.0 MHz	Murata Erie (	CSA2.00MG	± 0.5%					
4.0 MHz	Murata Erie CSA4.00MG ± 0.5%							
8.0 MHz	Murata Erie CSA8.00MT ± 0.5%							
16.0 MHz	Murata Erie (	CSA16.00MX	± 0.5%					
All resonat	All resonators used did not have built-in capacitors.							

- **Note 1:** Higher capacitance increases the stability of the oscillator, but also increases the start-up time.
  - 2: When operating below 3V VDD, or when using certain ceramic resonators at any voltage, it may be necessary to use high-gain HS mode, try a lower frequency resonator, or switch to a crystal oscillator.
  - 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components, or verify oscillator performance.

TABLE 2-2: CAPACITOR SELECTION FOR CRYSTAL OSCILLATOR

	Ranges Tested:											
Mode	Freq	C1	C2									
LP	32.0 kHz	33 pF	33 pF									
	200 kHz	15 pF	15 pF									
XT	200 kHz	22-68 pF	22-68 pF									
	1.0 MHz	15 pF	15 pF									
	4.0 MHz	15 pF	15 pF									
HS	4.0 MHz	15 pF	15 pF									
	8.0 MHz	15-33 pF	15-33 pF									
	20.0 MHz	15-33 pF	15-33 pF									
	25.0 MHz	15-33 pF	15-33 pF									


These values are for design guidance only. See notes following this table.

Crystals Used										
32.0 kHz	32.0 kHz Epson C-001R32.768K-A									
200 kHz	STD XTL 200.000KHz	± 20 PPM								
1.0 MHz	1.0 MHz ECS ECS-10-13-1									
4.0 MHz	ECS ECS-40-20-1	± 50 PPM								
8.0 MHz	Epson CA-301 8.000M-C	± 30 PPM								
20.0 MHz	Epson CA-301 20.000M-C	± 30 PPM								

- **Note 1:** Higher capacitance increases the stability of the oscillator, but also increases the start-up time.
  - 2: Rs may be required in HS mode, as well as XT mode, to avoid overdriving crystals with low drive level specification.
  - 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components., or verify oscillator performance.

An external clock source may also be connected to the OSC1 pin in the HS, XT and LP modes, as shown in Figure 2-2.

FIGURE 2-2: EXTERNAL CLOCK INPUT OPERATION (HS, XT OR LP OSC CONFIGURATION)




### 2.3 RC Oscillator

For timing-insensitive applications, the "RC" and "RCIO" device options offer additional cost savings. The RC oscillator frequency is a function of the supply voltage, the resistor (REXT) and capacitor (CEXT) values and the operating temperature. In addition to this, the oscillator frequency will vary from unit to unit due to normal process parameter variation. Furthermore, the difference in lead frame capacitance between package types will also affect the oscillation frequency, especially for low CEXT values. The user also needs to take into account variation due to tolerance of external R and C components used. Figure 2-3 shows how the R/C combination is connected.

In the RC Oscillator mode, the oscillator frequency divided by 4 is available on the OSC2 pin. This signal may be used for test purposes or to synchronize other logic.

**Note:** If the oscillator frequency divided by 4 signal is not required in the application, it is recommended to use RCIO mode to save current.

### FIGURE 2-3: RC OSCILLATOR MODE




The RCIO Oscillator mode functions like the RC mode, except that the OSC2 pin becomes an additional general purpose I/O pin. The I/O pin becomes bit 6 of PORTA (RA6).

### 2.4 External Clock Input

The EC and ECIO Oscillator modes require an external clock source to be connected to the OSC1 pin. The feedback device between OSC1 and OSC2 is turned off in these modes to save current. There is no oscillator start-up time required after a Power-on Reset or after a recovery from SLEEP mode.


In the EC Oscillator mode, the oscillator frequency divided by 4 is available on the OSC2 pin. This signal may be used for test purposes or to synchronize other logic. Figure 2-4 shows the pin connections for the EC Oscillator mode.

FIGURE 2-4: EXTERNAL CLOCK INPUT OPERATION (EC CONFIGURATION)



The ECIO Oscillator mode functions like the EC mode, except that the OSC2 pin becomes an additional general purpose I/O pin. The I/O pin becomes bit 6 of PORTA (RA6). Figure 2-5 shows the pin connections for the ECIO Oscillator mode.

# FIGURE 2-5: EXTERNAL CLOCK INPUT OPERATION (ECIO CONFIGURATION)



### 2.5 HS/PLL


A Phase Locked Loop circuit is provided as a programmable option for users that want to multiply the frequency of the incoming crystal oscillator signal by 4. For an input clock frequency of 10 MHz, the internal clock frequency will be multiplied to 40 MHz. This is useful for customers who are concerned with EMI due to high frequency crystals.

The PLL can only be enabled when the oscillator configuration bits are programmed for HS mode. If they are programmed for any other mode, the PLL is not enabled and the system clock will come directly from OSC1.

The PLL is one of the modes of the FOSC<2:0> configuration bits. The Oscillator mode is specified during device programming.

A PLL lock timer is used to ensure that the PLL has locked before device execution starts. The PLL lock timer has a time-out that is called TPLL.

FIGURE 2-6: PLL BLOCK DIAGRAM




### 2.6 Oscillator Switching Feature

The PIC18FXX2 devices include a feature that allows the system clock source to be switched from the main oscillator to an alternate low frequency clock source. For the PIC18FXX2 devices, this alternate clock source is the Timer1 oscillator. If a low frequency crystal (32 kHz, for example) has been attached to the Timer1 oscillator pins and the Timer1 oscillator has been enabled, the device can switch to a Low Power Execu-

tion mode. Figure 2-7 shows a block diagram of the system clock sources. The clock switching feature is enabled by programming the Oscillator Switching Enable (OSCSEN) bit in Configuration Register1H to a '0'. Clock switching is disabled in an erased device. See Section 11.0 for further details of the Timer1 oscillator. See Section 19.0 for Configuration Register details.

FIGURE 2-7: DEVICE CLOCK SOURCES



#### SYSTEM CLOCK SWITCH BIT 2.6.1

The system clock source switching is performed under software control. The system clock switch bit, SCS (OSCCON<0>) controls the clock switching. When the SCS bit is '0', the system clock source comes from the main oscillator that is selected by the FOSC configuration bits in Configuration Register1H. When the SCS bit is set, the system clock source will come from the Timer1 oscillator. The SCS bit is cleared on all forms of RESET.

The Timer1 oscillator must be enabled and operating to switch the system clock source. The Timer1 oscillator is enabled by setting the T1OSCEN bit in the Timer1 control register (T1CON). If the Timer1 oscillator is not enabled, then any write to the SCS bit will be ignored (SCS bit forced cleared) and the main oscillator will continue to be the system clock source.

#### **REGISTER 2-1: OSCCON REGISTER**

U-0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-1
_	_	_	_	_	_	_	SCS
bit 7							bit 0

Note:

bit 7-1 Unimplemented: Read as '0' bit 0

SCS: System Clock Switch bit

When OSCSEN configuration bit = '0' and T1OSCEN bit is set:

1 = Switch to Timer1 oscillator/clock pin

0 = Use primary oscillator/clock input pin

When OSCSEN and T1OSCEN are in other states:

bit is forced clear


Legend: R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' - n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 2.6.2 OSCILLATOR TRANSITIONS

The PIC18FXX2 devices contain circuitry to prevent "glitches" when switching between oscillator sources. Essentially, the circuitry waits for eight rising edges of the clock source that the processor is switching to. This ensures that the new clock source is stable and that its pulse width will not be less than the shortest pulse width of the two clock sources.

A timing diagram indicating the transition from the main oscillator to the Timer1 oscillator is shown in Figure 2-8. The Timer1 oscillator is assumed to be running all the time. After the SCS bit is set, the processor is frozen at the next occurring Q1 cycle. After eight synchronization cycles are counted from the Timer1 oscillator, operation resumes. No additional delays are required after the synchronization cycles.






The sequence of events that takes place when switching from the Timer1 oscillator to the main oscillator will depend on the mode of the main oscillator. In addition to eight clock cycles of the main oscillator, additional delays may take place.


If the main oscillator is configured for an external crystal (HS, XT, LP), then the transition will take place after an oscillator start-up time (TOST) has occurred. A timing diagram, indicating the transition from the Timer1 oscillator to the main oscillator for HS, XT and LP modes, is shown in Figure 2-9.

### FIGURE 2-9: TIMING FOR TRANSITION BETWEEN TIMER1 AND OSC1 (HS, XT, LP)




If the main oscillator is configured for HS-PLL mode, an oscillator start-up time (Tost) plus an additional PLL time-out (TPLL) will occur. The PLL time-out is typically 2 ms and allows the PLL to lock to the main oscillator frequency. A timing diagram indicating the transition from the Timer1 oscillator to the main oscillator for HS-PLL mode is shown in Figure 2-10.

FIGURE 2-10: TIMING FOR TRANSITION BETWEEN TIMER1 AND OSC1 (HS WITH PLL)



If the main oscillator is configured in the RC, RCIO, EC or ECIO modes, there is no oscillator start-up time-out. Operation will resume after eight cycles of the main oscillator have been counted. A timing diagram, indicating the transition from the Timer1 oscillator to the main oscillator for RC, RCIO, EC and ECIO modes, is shown in Figure 2-11.

FIGURE 2-11: TIMING FOR TRANSITION BETWEEN TIMER1 AND OSC1 (RC, EC)



### 2.7 Effects of SLEEP Mode on the On-Chip Oscillator

When the device executes a SLEEP instruction, the on-chip clocks and oscillator are turned off and the device is held at the beginning of an instruction cycle (Q1 state). With the oscillator off, the OSC1 and OSC2 signals will stop oscillating. Since all the transistor

switching currents have been removed, SLEEP mode achieves the lowest current consumption of the device (only leakage currents). Enabling any on-chip feature that will operate during SLEEP will increase the current consumed during SLEEP. The user can wake from SLEEP through external RESET, Watchdog Timer Reset, or through an interrupt.

TABLE 2-3: OSC1 AND OSC2 PIN STATES IN SLEEP MODE

OSC Mode	OSC1 Pin	OSC2 Pin
RC	Floating, external resistor should pull high	At logic low
RCIO	Floating, external resistor should pull high	Configured as PORTA, bit 6
ECIO	Floating	Configured as PORTA, bit 6
EC	Floating	At logic low
LP, XT, and HS	Feedback inverter disabled, at quiescent voltage level	Feedback inverter disabled, at quiescent voltage level

Note: See Table 3-1, in the "Reset" section, for time-outs due to SLEEP and MCLR Reset.

### 2.8 Power-up Delays

Power up delays are controlled by two timers, so that no external RESET circuitry is required for most applications. The delays ensure that the device is kept in RESET, until the device power supply and clock are stable. For additional information on RESET operation, see Section 3.0.

The first timer is the Power-up Timer (PWRT), which optionally provides a fixed delay of 72 ms (nominal) on power-up only (POR and BOR). The second timer is the Oscillator Start-up Timer (OST), intended to keep the chip in RESET until the crystal oscillator is stable.

With the PLL enabled (HS/PLL Oscillator mode), the time-out sequence following a Power-on Reset is different from other Oscillator modes. The time-out sequence is as follows: First, the PWRT time-out is invoked after a POR time delay has expired. Then, the Oscillator Start-up Timer (OST) is invoked. However, this is still not a sufficient amount of time to allow the PLL to lock at high frequencies. The PWRT timer is used to provide an additional fixed 2 ms (nominal) time-out to allow the PLL ample time to lock to the incoming clock frequency.

#### 3.0 RESET

The PIC18FXXX differentiates between various kinds of RESET:

- a) Power-on Reset (POR)
- MCLR Reset during normal operation
- c) MCLR Reset during SLEEP
- Watchdog Timer (WDT) Reset (during normal d) operation)
- e) Programmable Brown-out Reset (BOR)
- f) RESET Instruction
- Stack Full Reset q)
- Stack Underflow Reset

Most registers are unaffected by a RESET. Their status is unknown on POR and unchanged by all other RESETS. The other registers are forced to a "RESET state" on Power-on Reset, MCLR, WDT Reset, Brownout Reset, MCLR Reset during SLEEP and by the RESET instruction.


Most registers are not affected by a WDT wake-up, since this is viewed as the resumption of normal operation. Status bits from the RCON register, RI, TO, PD, POR and BOR, are set or cleared differently in different RESET situations, as indicated in Table 3-2. These bits are used in software to determine the nature of the RESET. See Table 3-3 for a full description of the RESET states of all registers.

A simplified block diagram of the On-Chip Reset Circuit is shown in Figure 3-1.

The Enhanced MCU devices have a MCLR noise filter in the MCLR Reset path. The filter will detect and ignore small pulses.

The MCLR pin is not driven low by any internal RESETS, including the WDT.

FIGURE 3-1: SIMPLIFIED BLOCK DIAGRAM OF ON-CHIP RESET CIRCUIT




### 3.1 Power-On Reset (POR)

A Power-on Reset pulse is generated on-chip when VDD rise is detected. To take advantage of the POR circuitry, just tie the MCLR pin directly (or through a resistor) to VDD. This will eliminate external RC components usually needed to create a Power-on Reset delay. A minimum rise rate for VDD is specified (parameter D004). For a slow rise time, see Figure 3-2.

When the device starts normal operation (i.e., exits the RESET condition), device operating parameters (voltage, frequency, temperature, etc.) must be met to ensure operation. If these conditions are not met, the device must be held in RESET until the operating conditions are met.

FIGURE 3-2: EXTERNAL POWER-ON RESET CIRCUIT (FOR SLOW VDD POWER-UP)



Note 1: External Power-on Reset circuit is required only if the VDD power-up slope is too slow.

The diode D helps discharge the capacitor quickly when VDD powers down.

- 2:  $R < 40 \text{ k}\Omega$  is recommended to make sure that the voltage drop across R does not violate the device's electrical specification.
- 3: R1 =  $100\Omega$  to 1 k $\Omega$  will limit any current flowing into  $\overline{\text{MCLR}}$  from external capacitor C, in the event of  $\overline{\text{MCLR}}/\text{VPP}$  pin breakdown due to Electrostatic Discharge (ESD) or Electrical Overstress (EOS).

### 3.2 Power-up Timer (PWRT)

The Power-up Timer provides a fixed nominal time-out (parameter 33) only on power-up from the POR. The Power-up Timer operates on an internal RC oscillator. The chip is kept in RESET as long as the PWRT is active. The PWRT's time delay allows VDD to rise to an acceptable level. A configuration bit is provided to enable/disable the PWRT.

The power-up time delay will vary from chip-to-chip due to VDD, temperature and process variation. See DC parameter D033 for details.

### 3.3 Oscillator Start-up Timer (OST)

The Oscillator Start-up Timer (OST) provides a 1024 oscillator cycle (from OSC1 input) delay after the PWRT delay is over (parameter 32). This ensures that the crystal oscillator or resonator has started and stabilized.

The OST time-out is invoked only for XT, LP and HS modes and only on Power-on Reset or wake-up from SLEEP.

### 3.4 PLL Lock Time-out

With the PLL enabled, the time-out sequence following a Power-on Reset is different from other Oscillator modes. A portion of the Power-up Timer is used to provide a fixed time-out that is sufficient for the PLL to lock to the main oscillator frequency. This PLL lock time-out (TPLL) is typically 2 ms and follows the oscillator start-up time-out (OST).

### 3.5 Brown-out Reset (BOR)

A configuration bit, BOREN, can disable (if clear/programmed), or enable (if set) the Brown-out Reset circuitry. If VDD falls below parameter D005 for greater than parameter 35, the brown-out situation will reset the chip. A RESET may not occur if VDD falls below parameter D005 for less than parameter 35. The chip will remain in Brown-out Reset until VDD rises above BVDD. If the Power-up Timer is enabled, it will be invoked after VDD rises above BVDD; it then will keep the chip in RESET for an additional time delay (parameter 33). If VDD drops below BVDD while the Power-up Timer is running, the chip will go back into a Brown-out Reset and the Power-up Timer will be initialized. Once VDD rises above BVDD, the Power-up Timer will execute the additional time delay.

### 3.6 Time-out Sequence

On power-up, the time-out sequence is as follows: First, PWRT time-out is invoked after the POR time delay has expired. Then, OST is activated. The total time-out will vary based on oscillator configuration and the status of the PWRT. For example, in RC mode with the PWRT disabled, there will be no time-out at all. Figure 3-3, Figure 3-4, Figure 3-5, Figure 3-6 and Figure 3-7 depict time-out sequences on power-up.

Since the time-outs occur from the POR pulse, if MCLR is kept low long enough, the time-outs will expire. Bringing MCLR high will begin execution immediately (Figure 3-5). This is useful for testing purposes or to synchronize more than one PIC18FXXX device operating in parallel.

Table 3-2 shows the RESET conditions for some Special Function Registers, while Table 3-3 shows the RESET conditions for all the registers.

TABLE 3-1: TIME-OUT IN VARIOUS SITUATIONS

Oscillator	Power-up	(2)		Wake-up from
Configuration	PWRTE = 0	PWRTE = 1	Brown-out	SLEEP or Oscillator Switch
HS with PLL enabled <sup>(1)</sup>	72 ms + 1024 Tosc + 2ms	1024 Tosc + 2 ms	72 ms <sup>(2)</sup> + 1024 Tosc + 2 ms	1024 Tosc + 2 ms
HS, XT, LP	72 ms + 1024 Tosc	1024 Tosc	72 ms <sup>(2)</sup> + 1024 Tosc	1024 Tosc
EC	72 ms	_	72 ms <sup>(2)</sup>	_
External RC	72 ms	_	72 ms <sup>(2)</sup>	_

Note 1: 2 ms is the nominal time required for the 4x PLL to lock.

2: 72 ms is the nominal power-up timer delay, if implemented.

REGISTER 3-1: RCON REGISTER BITS AND POSITIONS

R/W-0	U-0	U-0	R/W-1	R-1	R-1	R/W-0	R/W-0
IPEN	_	_	RI	TO	PD	POR	BOR
bit 7							bit 0

Note 1: Refer to Section 4.14 (page 53) for bit definitions.

TABLE 3-2: STATUS BITS, THEIR SIGNIFICANCE AND THE INITIALIZATION CONDITION FOR RCON REGISTER

Condition	Program Counter	RCON Register	RI	то	PD	POR	BOR	STKFUL	STKUNF
Power-on Reset	0000h	01 1100	1	1	1	0	0	u	u
MCLR Reset during normal operation	0000h	0u uuuu	u	u	u	u	u	u	u
Software Reset during normal operation	0000h	00 uuuu	0	u	u	u	u	u	u
Stack Full Reset during normal operation	0000h	0u uu11	u	u	u	u	u	u	1
Stack Underflow Reset during normal operation	0000h	0u uu11	u	u	u	u	u	1	u
MCLR Reset during SLEEP	0000h	0u 10uu	u	1	0	u	u	u	u
WDT Reset	0000h	0u 01uu	1	0	1	u	u	u	u
WDT Wake-up	PC + 2	uu 00uu	u	0	0	u	u	u	u
Brown-out Reset	0000h	01 11u0	1	1	1	1	0	u	u
Interrupt wake-up from SLEEP	PC + 2 <sup>(1)</sup>	uu 00uu	u	1	0	u	u	u	u

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0'

Note 1: When the wake-up is due to an interrupt and the GIEH or GIEL bits are set, the PC is loaded with the interrupt vector (0x000008h or 0x000018h).

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS

Register	gister Applicable Devices		Power-on Reset, Brown-out Reset	MCLR Resets WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt		
TOSU	242	442	252	452	0 0000	0 0000	0 uuuu <sup>(3)</sup>
TOSH	242	442	252	452	0000 0000	0000 0000	uuuu uuuu(3)
TOSL	242	442	252	452	0000 0000	0000 0000	uuuu uuuu(3)
STKPTR	242	442	252	452	00-0 0000	uu-0 0000	uu-u uuuu <sup>(3)</sup>
PCLATU	242	442	252	452	0 0000	0 0000	u uuuu
PCLATH	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
PCL	242	442	252	452	0000 0000	0000 0000	PC + 2 <sup>(2)</sup>
TBLPTRU	242	442	252	452	00 0000	00 0000	uu uuuu
TBLPTRH	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
TBLPTRL	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
TABLAT	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
PRODH	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
PRODL	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
INTCON	242	442	252	452	0000 000x	0000 000u	uuuu uuuu(1)
INTCON2	242	442	252	452	1111 -1-1	1111 -1-1	uuuu -u-u <sup>(1)</sup>
INTCON3	242	442	252	452	11-0 0-00	11-0 0-00	uu-u u-uu <sup>(1)</sup>
INDF0	242	442	252	452	N/A	N/A	N/A
POSTINC0	242	442	252	452	N/A	N/A	N/A
POSTDEC0	242	442	252	452	N/A	N/A	N/A
PREINC0	242	442	252	452	N/A	N/A	N/A
PLUSW0	242	442	252	452	N/A	N/A	N/A
FSR0H	242	442	252	452	xxxx	uuuu	uuuu
FSR0L	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
WREG	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
INDF1	242	442	252	452	N/A	N/A	N/A
POSTINC1	242	442	252	452	N/A	N/A	N/A
POSTDEC1	242	442	252	452	N/A	N/A	N/A
PREINC1	242	442	252	452	N/A	N/A	N/A
PLUSW1	242	442	252	452	N/A	N/A	N/A

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - **4:** See Table 3-2 for RESET value for specific condition.
  - 5: Bit 6 of PORTA, LATA, and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other Oscillator modes, they are disabled and read '0'.
  - 6: Bit 6 of PORTA, LATA and TRISA are not available on all devices. When unimplemented, they are read '0'.

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Register	Applicable Devices		Power-on Reset, Brown-out Reset	MCLR Resets WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt		
FSR1H	242	442	252	452	xxxx	uuuu	uuuu
FSR1L	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
BSR	242	442	252	452	0000	0000	uuuu
INDF2	242	442	252	452	N/A	N/A	N/A
POSTINC2	242	442	252	452	N/A	N/A	N/A
POSTDEC2	242	442	252	452	N/A	N/A	N/A
PREINC2	242	442	252	452	N/A	N/A	N/A
PLUSW2	242	442	252	452	N/A	N/A	N/A
FSR2H	242	442	252	452	xxxx	uuuu	uuuu
FSR2L	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
STATUS	242	442	252	452	x xxxx	u uuuu	u uuuu
TMR0H	242	442	252	452	0000 0000	uuuu uuuu	uuuu uuuu
TMR0L	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
T0CON	242	442	252	452	1111 1111	1111 1111	uuuu uuuu
OSCCON	242	442	252	452	0	0	u
LVDCON	242	442	252	452	00 0101	00 0101	uu uuuu
WDTCON	242	442	252	452	0	0	u
RCON <sup>(4)</sup>	242	442	252	452	0q 11qq	0q qquu	uu qquu
TMR1H	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
TMR1L	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
T1CON	242	442	252	452	0-00 0000	u-uu uuuu	u-uu uuuu
TMR2	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
PR2	242	442	252	452	1111 1111	1111 1111	1111 1111
T2CON	242	442	252	452	-000 0000	-000 0000	-uuu uuuu
SSPBUF	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
SSPADD	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
SSPSTAT	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
SSPCON1	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
SSPCON2	242	442	252	452	0000 0000	0000 0000	uuuu uuuu

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for RESET value for specific condition.
  - 5: Bit 6 of PORTA, LATA, and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other Oscillator modes, they are disabled and read '0'.
  - 6: Bit 6 of PORTA, LATA and TRISA are not available on all devices. When unimplemented, they are read '0'.

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Register	Applicable Devices				Power-on Reset, Brown-out Reset	MCLR Resets WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt
ADRESH	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
ADRESL	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
ADCON0	242	442	252	452	0000 00-0	0000 00-0	uuuu uu-u
ADCON1	242	442	252	452	00 0000	00 0000	uu uuuu
CCPR1H	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
CCPR1L	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
CCP1CON	242	442	252	452	00 0000	00 0000	uu uuuu
CCPR2H	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
CCPR2L	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
CCP2CON	242	442	252	452	00 0000	00 0000	uu uuuu
TMR3H	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
TMR3L	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
T3CON	242	442	252	452	0000 0000	uuuu uuuu	uuuu uuuu
SPBRG	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
RCREG	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
TXREG	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
TXSTA	242	442	252	452	0000 -010	0000 -010	uuuu -uuu
RCSTA	242	442	252	452	0000 000x	0000 000x	uuuu uuuu
EEADR	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
EEDATA	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
EECON1	242	442	252	452	xx-0 x000	uu-0 u000	uu-0 u000
EECON2	242	442	252	452			

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - **4:** See Table 3-2 for RESET value for specific condition.
  - 5: Bit 6 of PORTA, LATA, and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other Oscillator modes, they are disabled and read '0'.
  - 6: Bit 6 of PORTA, LATA and TRISA are not available on all devices. When unimplemented, they are read '0'.

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Register	Applicable Devices			ces	Power-on Reset, Brown-out Reset	MCLR Resets WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt
IPR2	242	442	252	452	1 1111	1 1111	u uuuu
PIR2	242	442	252	452	0 0000	0 0000	u uuuu <sup>(1)</sup>
PIE2	242	442	252	452	0 0000	0 0000	u uuuu
IPR1	242	442	252	452	1111 1111	1111 1111	uuuu uuuu
IFNI	242	442	252	452	-111 1111	-111 1111	-uuu uuuu
PIR1	242	442	252	452	0000 0000	0000 0000	uuuu uuuu <sup>(1)</sup>
PIKI	242	442	252	452	-000 0000	-000 0000	-uuu uuuu(1)
PIE1	242	442	252	452	0000 0000	0000 0000	uuuu uuuu
PIEI	242	442	252	452	-000 0000	-000 0000	-uuu uuuu
TRISE	242	442	252	452	0000 -111	0000 -111	uuuu -uuu
TRISD	242	442	252	452	1111 1111	1111 1111	uuuu uuuu
TRISC	242	442	252	452	1111 1111	1111 1111	uuuu uuuu
TRISB	242	442	252	452	1111 1111	1111 1111	uuuu uuuu
TRISA <sup>(5,6)</sup>	242	442	252	452	-111 1111 <sup>(5)</sup>	-111 1111 <sup>(5)</sup>	-uuu uuuu <sup>(5)</sup>
LATE	242	442	252	452	xxx	uuu	uuu
LATD	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
LATC	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
LATB	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
LATA <sup>(5,6)</sup>	242	442	252	452	-xxx xxxx <sup>(5)</sup>	-uuu uuuu( <sup>5)</sup>	-uuu uuuu(5)
PORTE	242	442	252	452	000	000	uuu
PORTD	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
PORTC	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
PORTB	242	442	252	452	xxxx xxxx	uuuu uuuu	uuuu uuuu
PORTA <sup>(5,6)</sup>	242	442	252	452	-x0x 0000 <sup>(5)</sup>	-u0u 0000 <sup>(5)</sup>	-uuu uuuu( <b>5)</b>

 $\label{eq:unchanged} \begin{tabular}{ll} $u$ = unchanged, $x$ = unknown, $-$ = unimplemented bit, read as '0', $q$ = value depends on condition. \\ Shaded cells indicate conditions do not apply for the designated device. \\ \end{tabular}$ 

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - 3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack
  - **4:** See Table 3-2 for RESET value for specific condition.
  - **5:** Bit 6 of PORTA, LATA, and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other Oscillator modes, they are disabled and read '0'.
  - 6: Bit 6 of PORTA, LATA and TRISA are not available on all devices. When unimplemented, they are read '0'.

FIGURE 3-3: TIME-OUT SEQUENCE ON POWER-UP (MCLR TIED TO VDD)




FIGURE 3-4: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 1







FIGURE 3-5: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 2











**NOTES:** 

## 4.0 MEMORY ORGANIZATION

There are three memory blocks in Enhanced MCU devices. These memory blocks are:

- · Program Memory
- Data RAM
- Data EEPROM

Data and program memory use separate busses, which allows for concurrent access of these blocks.

Additional detailed information for FLASH program memory and Data EEPROM is provided in Section 5.0 and Section 6.0, respectively.

## 4.1 Program Memory Organization

A 21-bit program counter is capable of addressing the 2-Mbyte program memory space. Accessing a location between the physically implemented memory and the 2-Mbyte address will cause a read of all '0's (a NOP instruction).

The PIC18F252 and PIC18F452 each have 32 Kbytes of FLASH memory, while the PIC18F242 and PIC18F442 have 16 Kbytes of FLASH. This means that PIC18FX52 devices can store up to 16K of single word instructions, and PIC18FX42 devices can store up to 8K of single word instructions.

The RESET vector address is at 0000h and the interrupt vector addresses are at 0008h and 0018h.

Figure 4-1 shows the Program Memory Map for PIC18F242/442 devices and Figure 4-2 shows the Program Memory Map for PIC18F252/452 devices.

FIGURE 4-1: PROGRAM MEMORY MAP AND STACK FOR PIC18F442/242





FIGURE 4-2: PROGRAM MEMORY MAP AND STACK FOR PIC18F452/252



### 4.2 Return Address Stack

The return address stack allows any combination of up to 31 program calls and interrupts to occur. The PC (Program Counter) is pushed onto the stack when a CALL or RCALL instruction is executed, or an interrupt is acknowledged. The PC value is pulled off the stack on a RETURN, RETLW or a RETFIE instruction. PCLATU and PCLATH are not affected by any of the RETURN or CALL instructions.

The stack operates as a 31-word by 21-bit RAM and a 5-bit stack pointer, with the stack pointer initialized to 00000b after all RESETS. There is no RAM associated with stack pointer 00000b. This is only a RESET value. During a CALL type instruction, causing a push onto the stack, the stack pointer is first incremented and the RAM location pointed to by the stack pointer is written with the contents of the PC. During a RETURN type instruction, causing a pop from the stack, the contents of the RAM location pointed to by the STKPTR are transferred to the PC and then the stack pointer is decremented.

The stack space is not part of either program or data space. The stack pointer is readable and writable, and the address on the top of the stack is readable and writable through SFR registers. Data can also be pushed to, or popped from, the stack using the top-of-stack SFRs. Status bits indicate if the stack pointer is at, or beyond the 31 levels provided.

### 4.2.1 TOP-OF-STACK ACCESS

The top of the stack is readable and writable. Three register locations, TOSU, TOSH and TOSL hold the contents of the stack location pointed to by the STKPTR register. This allows users to implement a software stack if necessary. After a CALL, RCALL or interrupt, the software can read the pushed value by reading the TOSU, TOSH and TOSL registers. These values can be placed on a user defined software stack. At return time, the software can replace the TOSU, TOSH and TOSL and do a return.

The user must disable the global interrupt enable bits during this time to prevent inadvertent stack operations.

## 4.2.2 RETURN STACK POINTER (STKPTR)

The STKPTR register contains the stack pointer value, the STKFUL (stack full) status bit, and the STKUNF (stack underflow) status bits. Register 4-1 shows the STKPTR register. The value of the stack pointer can be 0 through 31. The stack pointer increments when values are pushed onto the stack and decrements when values are popped off the stack. At RESET, the stack pointer value will be 0. The user may read and write the stack pointer value. This feature can be used by a Real Time Operating System for return stack maintenance.

After the PC is pushed onto the stack 31 times (without popping any values off the stack), the STKFUL bit is set. The STKFUL bit can only be cleared in software or by a POR.

The action that takes place when the stack becomes full depends on the state of the STVREN (Stack Overflow Reset Enable) configuration bit. Refer to Section 20.0 for a description of the device configuration bits. If STVREN is set (default), the 31st push will push the (PC + 2) value onto the stack, set the STKFUL bit, and reset the device. The STKFUL bit will remain set and the stack pointer will be set to '0'.

If STVREN is cleared, the STKFUL bit will be set on the 31st push and the stack pointer will increment to 31. Any additional pushes will not overwrite the 31st push, and STKPTR will remain at 31.

When the stack has been popped enough times to unload the stack, the next pop will return a value of zero to the PC and sets the STKUNF bit, while the stack pointer remains at 0. The STKUNF bit will remain set until cleared in software or a POR occurs.

Note:

Returning a value of zero to the PC on an underflow has the effect of vectoring the program to the RESET vector, where the stack conditions can be verified and appropriate actions can be taken.

## **REGISTER 4-1: STKPTR REGISTER**

R/C-0	R/C-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
STKOVF	STKUNF	_	SP4	SP3	SP2	SP1	SP0
bit 7							bit 0

bit 7(1) STKOVF: Stack Full Flag bit

1 = Stack became full or overflowed

0 = Stack has not become full or overflowed

bit 6(1) STKUNF: Stack Underflow Flag bit

1 = Stack underflow occurred

0 = Stack underflow did not occur


bit 5 Unimplemented: Read as '0'

bit 4-0 SP4:SP0: Stack Pointer Location bits

Note 1: Bit 7 and bit 6 can only be cleared in user software or by a POR.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

## FIGURE 4-3: RETURN ADDRESS STACK AND ASSOCIATED REGISTERS



## 4.2.3 PUSH AND POP INSTRUCTIONS

Since the Top-of-Stack (TOS) is readable and writable, the ability to push values onto the stack and pull values off the stack without disturbing normal program execution is a desirable option. To push the current PC value onto the stack, a PUSH instruction can be executed. This will increment the stack pointer and load the current PC value onto the stack. TOSU, TOSH and TOSL can then be modified to place a return address on the stack.

The ability to pull the TOS value off of the stack and replace it with the value that was previously pushed onto the stack, without disturbing normal execution, is achieved by using the POP instruction. The POP instruction discards the current TOS by decrementing the stack pointer. The previous value pushed onto the stack then becomes the TOS value.

### 4.2.4 STACK FULL/UNDERFLOW RESETS

These resets are enabled by programming the STVREN configuration bit. When the STVREN bit is disabled, a full or underflow condition will set the appropriate STKFUL or STKUNF bit, but not cause a device RESET. When the STVREN bit is enabled, a full or underflow will set the appropriate STKFUL or STKUNF bit and then cause a device RESET. The STKFUL or STKUNF bits are only cleared by the user software or a POR Reset.

## 4.3 Fast Register Stack

A "fast interrupt return" option is available for interrupts. A Fast Register Stack is provided for the STATUS, WREG and BSR registers and are only one in depth. The stack is not readable or writable and is loaded with the current value of the corresponding register when the processor vectors for an interrupt. The values in the registers are then loaded back into the working registers, if the FAST RETURN instruction is used to return from the interrupt.


A low or high priority interrupt source will push values into the stack registers. If both low and high priority interrupts are enabled, the stack registers cannot be used reliably for low priority interrupts. If a high priority interrupt occurs while servicing a low priority interrupt, the stack register values stored by the low priority interrupt will be overwritten.

If high priority interrupts are not disabled during low priority interrupts, users must save the key registers in software during a low priority interrupt.

If no interrupts are used, the fast register stack can be used to restore the STATUS, WREG and BSR registers at the end of a subroutine call. To use the fast register stack for a subroutine call, a FAST CALL instruction must be executed.

Example 4-1 shows a source code example that uses the fast register stack.

## EXAMPLE 4-1: FAST REGISTER STACK CODE EXAMPLE



## 4.4 PCL, PCLATH and PCLATU

The program counter (PC) specifies the address of the instruction to fetch for execution. The PC is 21-bits wide. The low byte is called the PCL register. This register is readable and writable. The high byte is called the PCH register. This register contains the PC<15:8> bits and is not directly readable or writable. Updates to the PCH register may be performed through the PCLATH register. The upper byte is called PCU. This register contains the PC<20:16> bits and is not directly readable or writable. Updates to the PCU register may be performed through the PCLATU register.

The PC addresses bytes in the program memory. To prevent the PC from becoming misaligned with word instructions, the LSB of PCL is fixed to a value of '0'. The PC increments by 2 to address sequential instructions in the program memory.


The CALL, RCALL, GOTO and program branch instructions write to the program counter directly. For these instructions, the contents of PCLATH and PCLATU are not transferred to the program counter.

The contents of PCLATH and PCLATU will be transferred to the program counter by an operation that writes PCL. Similarly, the upper two bytes of the program counter will be transferred to PCLATH and PCLATU by an operation that reads PCL. This is useful for computed offsets to the PC (see Section 4.8.1).

## 4.5 Clocking Scheme/Instruction Cycle

The clock input (from OSC1) is internally divided by four to generate four non-overlapping quadrature clocks, namely Q1, Q2, Q3 and Q4. Internally, the program counter (PC) is incremented every Q1, the instruction is fetched from the program memory and latched into the instruction register in Q4. The instruction is decoded and executed during the following Q1 through Q4. The clocks and instruction execution flow are shown in Figure 4-4.





## 4.6 Instruction Flow/Pipelining

An "Instruction Cycle" consists of four Q cycles (Q1, Q2, Q3 and Q4). The instruction fetch and execute are pipelined such that fetch takes one instruction cycle, while decode and execute takes another instruction cycle. However, due to the pipelining, each instruction effectively executes in one cycle. If an instruction causes the program counter to change (e.g., GOTO) then two cycles are required to complete the instruction (Example 4-2).

A fetch cycle begins with the program counter (PC) incrementing in Q1.

In the execution cycle, the fetched instruction is latched into the "Instruction Register" (IR) in cycle Q1. This instruction is then decoded and executed during the Q2, Q3, and Q4 cycles. Data memory is read during Q2 (operand read) and written during Q4 (destination write).

### **EXAMPLE 4-2: INSTRUCTION PIPELINE FLOW**

	TCY0	Tcy1	Tcy2	Tcy3	Tcy4	Tcy5
1. MOVLW 55h	Fetch 1	Execute 1	<u>'</u>		'	'
2. MOVWF PORTB		Fetch 2	Execute 2			
3. BRA SUB_1			Fetch 3	Execute 3		
4. BSF PORTA, BIT3 (Fore	ced NOP)	-		Fetch 4	Flush (NOP)	
5. Instruction @ address s	SUB_1		·		Fetch SUB_1	Execute SUB_1

All instructions are single cycle, except for any program branches. These take two cycles since the fetch instruction is "flushed" from the pipeline while the new instruction is being fetched and then executed.

## 4.7 Instructions in Program Memory

The program memory is addressed in bytes. Instructions are stored as two bytes or four bytes in program memory. The Least Significant Byte of an instruction word is always stored in a program memory location with an even address (LSB ='0'). Figure 4-5 shows an example of how instruction words are stored in the program memory. To maintain alignment with instruction boundaries, the PC increments in steps of 2 and the LSB will always read '0' (see Section 4.4).

The CALL and GOTO instructions have an absolute program memory address embedded into the instruction. Since instructions are always stored on word boundaries, the data contained in the instruction is a word address. The word address is written to PC<20:1>, which accesses the desired byte address in program memory. Instruction #2 in Figure 4-5 shows how the instruction "GOTO 000006h" is encoded in the program memory. Program branch instructions which encode a relative address offset operate in the same manner. The offset value stored in a branch instruction represents the number of single word instructions that the PC will be offset by. Section 20.0 provides further details of the instruction set.

FIGURE 4-5: INSTRUCTIONS IN PROGRAM MEMORY

			LSB = 1	LSB = 0	Word Address ↓
	Program M				000000h
	Byte Locat	ions $ ightarrow$			000002h
					000004h
					000006h
Instruction 1:	MOVLW	055h	0Fh	55h	000008h
Instruction 2:	GOTO	000006h	EFh	03h	00000Ah
			F0h	00h	00000Ch
Instruction 3:	MOVFF	123h, 456h	C1h	23h	00000Eh
			F4h	56h	000010h
					000012h
					000014h

### 4.7.1 TWO-WORD INSTRUCTIONS

The PIC18FXX2 devices have four two-word instructions: MOVFF, CALL, GOTO and LFSR. The second word of these instructions has the 4 MSBs set to 1's and is a special kind of NOP instruction. The lower 12 bits of the second word contain data to be used by the instruction. If the first word of the instruction is executed, the data in the second word is accessed. If the

second word of the instruction is executed by itself (first word was skipped), it will execute as a NOP. This action is necessary when the two-word instruction is preceded by a conditional instruction that changes the PC. A program example that demonstrates this concept is shown in Example 4-3. Refer to Section 20.0 for further details of the instruction set.

## **EXAMPLE 4-3: TWO-WORD INSTRUCTIONS**

CASE 1:	
Object Code	Source Code
0110 0110 0000 0000	TSTFSZ REG1 ; is RAM location 0?
1100 0001 0010 0011	MOVFF REG1, REG2 ; No, execute 2-word instruction
1111 0100 0101 0110	; 2nd operand holds address of REG2
0010 0100 0000 0000	ADDWF REG3 ; continue code
CASE 2:	
Object Code	Source Code
0110 0110 0000 0000	TSTFSZ REG1 ; is RAM location 0?
1100 0001 0010 0011	MOVFF REG1, REG2 ; Yes
1111 0100 0101 0110	; 2nd operand becomes NOP
0010 0100 0000 0000	ADDWF REG3 ; continue code

## 4.8 Lookup Tables

Lookup tables are implemented two ways. These are:

- Computed GOTO
- Table Reads

### 4.8.1 COMPUTED GOTO

A computed GOTO is accomplished by adding an offset to the program counter (ADDWF  $\ PCL$ ).

A lookup table can be formed with an ADDWF PCL instruction and a group of RETLW 0xnn instructions. WREG is loaded with an offset into the table before executing a call to that table. The first instruction of the called routine is the ADDWF PCL instruction. The next instruction executed will be one of the RETLW 0xnn instructions, that returns the value 0xnn to the calling function.

The offset value (value in WREG) specifies the number of bytes that the program counter should advance.

In this method, only one data byte may be stored in each instruction location and room on the return address stack is required.

Note: The ADDWF PCL instruction does not update PCLATH and PCLATU. A read operation on PCL must be performed to update PCLATH and PCLATU.

## 4.8.2 TABLE READS/TABLE WRITES

A better method of storing data in program memory allows 2 bytes of data to be stored in each instruction location.

Lookup table data may be stored 2 bytes per program word by using table reads and writes. The table pointer (TBLPTR) specifies the byte address and the table latch (TABLAT) contains the data that is read from, or written to program memory. Data is transferred to/from program memory, one byte at a time.

A description of the Table Read/Table Write operation is shown in Section 3.0.

## 4.9 Data Memory Organization

The data memory is implemented as static RAM. Each register in the data memory has a 12-bit address, allowing up to 4096 bytes of data memory. Figure 4-6 and Figure 4-7 show the data memory organization for the PIC18FXX2 devices.

The data memory map is divided into as many as 16 banks that contain 256 bytes each. The lower 4 bits of the Bank Select Register (BSR<3:0>) select which bank will be accessed. The upper 4 bits for the BSR are not implemented.

The data memory contains Special Function Registers (SFR) and General Purpose Registers (GPR). The SFRs are used for control and status of the controller and peripheral functions, while GPRs are used for data storage and scratch pad operations in the user's application. The SFRs start at the last location of Bank 15 (0xFFF) and extend downwards. Any remaining space beyond the SFRs in the Bank may be implemented as GPRs. GPRs start at the first location of Bank 0 and grow upwards. Any read of an unimplemented location will read as '0's.

The entire data memory may be accessed directly or indirectly. Direct addressing may require the use of the BSR register. Indirect addressing requires the use of a File Select Register (FSRn) and a corresponding Indirect File Operand (INDFn). Each FSR holds a 12-bit address value that can be used to access any location in the Data Memory map without banking.

The instruction set and architecture allow operations across all banks. This may be accomplished by indirect addressing or by the use of the MOVFF instruction. The MOVFF instruction is a two-word/two-cycle instruction that moves a value from one register to another.

To ensure that commonly used registers (SFRs and select GPRs) can be accessed in a single cycle, regardless of the current BSR values, an Access Bank is implemented. A segment of Bank 0 and a segment of Bank 15 comprise the Access RAM. Section 4.10 provides a detailed description of the Access RAM.

## 4.9.1 GENERAL PURPOSE REGISTER FILE

The register file can be accessed either directly or indirectly. Indirect addressing operates using a File Select Register and corresponding Indirect File Operand. The operation of indirect addressing is shown in Section 4.12.

Enhanced MCU devices may have banked memory in the GPR area. GPRs are not initialized by a Power-on Reset and are unchanged on all other RESETS.

Data RAM is available for use as GPR registers by all instructions. The top half of Bank 15 (0xF80 to 0xFFF) contains SFRs. All other banks of data memory contain GPR registers, starting with Bank 0.


### 4.9.2 SPECIAL FUNCTION REGISTERS

The Special Function Registers (SFRs) are registers used by the CPU and Peripheral Modules for controlling the desired operation of the device. These registers are implemented as static RAM. A list of these registers is given in Table 4-1 and Table 4-2.

The SFRs can be classified into two sets; those associated with the "core" function and those related to the peripheral functions. Those registers related to the "core" are described in this section, while those related to the operation of the peripheral features are described in the section of that peripheral feature.

The SFRs are typically distributed among the peripherals whose functions they control.

The unused SFR locations will be unimplemented and read as '0's. See Table 4-1 for addresses for the SFRs.






FIGURE 4-7: DATA MEMORY MAP FOR PIC18F252/452

TABLE 4-1: SPECIAL FUNCTION REGISTER MAP

Address	Name	Address	Name	Address	Name	Address	Name
FFFh	TOSU	FDFh	INDF2 <sup>(3)</sup>	FBFh	CCPR1H	F9Fh	IPR1
FFEh	TOSH	FDEh	POSTINC2 <sup>(3)</sup>	FBEh	CCPR1L	F9Eh	PIR1
FFDh	TOSL	FDDh	POSTDEC2 <sup>(3)</sup>	FBDh	CCP1CON	F9Dh	PIE1
FFCh	STKPTR	FDCh	PREINC2 <sup>(3)</sup>	FBCh	CCPR2H	F9Ch	_
FFBh	PCLATU	FDBh	PLUSW2 <sup>(3)</sup>	FBBh	CCPR2L	F9Bh	_
FFAh	PCLATH	FDAh	FSR2H	FBAh	CCP2CON	F9Ah	_
FF9h	PCL	FD9h	FSR2L	FB9h	_	F99h	_
FF8h	TBLPTRU	FD8h	STATUS	FB8h	<del></del>	F98h	_
FF7h	TBLPTRH	FD7h	TMR0H	FB7h	_	F97h	_
FF6h	TBLPTRL	FD6h	TMR0L	FB6h	_	F96h	TRISE <sup>(2)</sup>
FF5h	TABLAT	FD5h	T0CON	FB5h	<del></del>	F95h	TRISD <sup>(2)</sup>
FF4h	PRODH	FD4h	_	FB4h	_	F94h	TRISC
FF3h	PRODL	FD3h	OSCCON	FB3h	TMR3H	F93h	TRISB
FF2h	INTCON	FD2h	LVDCON	FB2h	TMR3L	F92h	TRISA
FF1h	INTCON2	FD1h	WDTCON	FB1h	T3CON	F91h	_
FF0h	INTCON3	FD0h	RCON	FB0h	_	F90h	_
FEFh	INDF0 <sup>(3)</sup>	FCFh	TMR1H	FAFh	SPBRG	F8Fh	_
FEEh	POSTINCO <sup>(3)</sup>	FCEh	TMR1L	FAEh	RCREG	F8Eh	_
FEDh	POSTDEC0 <sup>(3)</sup>	FCDh	T1CON	FADh	TXREG	F8Dh	LATE <sup>(2)</sup>
FECh	PREINC0 <sup>(3)</sup>	FCCh	TMR2	FACh	TXSTA	F8Ch	LATD <sup>(2)</sup>
FEBh	PLUSW0 <sup>(3)</sup>	FCBh	PR2	FABh	RCSTA	F8Bh	LATC
FEAh	FSR0H	FCAh	T2CON	FAAh	_	F8Ah	LATB
FE9h	FSR0L	FC9h	SSPBUF	FA9h	EEADR	F89h	LATA
FE8h	WREG	FC8h	SSPADD	FA8h	EEDATA	F88h	_
FE7h	INDF1 <sup>(3)</sup>	FC7h	SSPSTAT	FA7h	EECON2	F87h	_
FE6h	POSTINC1 <sup>(3)</sup>	FC6h	SSPCON1	FA6h	EECON1	F86h	_
FE5h	POSTDEC1 <sup>(3)</sup>	FC5h	SSPCON2	FA5h		F85h	_
FE4h	PREINC1 <sup>(3)</sup>	FC4h	ADRESH	FA4h	<del></del>	F84h	PORTE <sup>(2)</sup>
FE3h	PLUSW1 <sup>(3)</sup>	FC3h	ADRESL	FA3h	<del>_</del>	F83h	PORTD <sup>(2)</sup>
FE2h	FSR1H	FC2h	ADCON0	FA2h	IPR2	F82h	PORTC
FE1h	FSR1L	FC1h	ADCON1	FA1h	PIR2	F81h	PORTB
FE0h	BSR	FC0h	_	FA0h	PIE2	F80h	PORTA

Note 1: Unimplemented registers are read as '0'.

2: This register is not available on PIC18F2X2 devices.

3: This is not a physical register.

## PIC18FXX2

## TABLE 4-2: REGISTER FILE SUMMARY

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on page:
TOSU	-	1	_	Top-of-Stack	upper Byte (	TOS<20:16>	)		0 0000	37
TOSH	Top-of-Stack	k High Byte (T	OS<15:8>)						0000 0000	37
TOSL	Top-of-Stack	k Low Byte (T	OS<7:0>)						0000 0000	37
STKPTR	STKFUL	STKUNF	_	Return Stack	Pointer				00-0 0000	38
PCLATU	1		_	Holding Reg	ister for PC<	20:16>			0 0000	39
PCLATH	Holding Reg	gister for PC<	15:8>						0000 0000	39
PCL	PC Low Byt	e (PC<7:0>)							0000 0000	39
TBLPTRU	_	_	bit21 <sup>(2)</sup>	Program Me	mory Table P	ointer Upper	Byte (TBLPT	R<20:16>)	00 0000	58
TBLPTRH	Program Memory Table Pointer High Byte (TBLPTR<15:8>)							0000 0000	58	
TBLPTRL	Program Me	emory Table P	ointer Low E	Byte (TBLPTR	(<7:0>)				0000 0000	58
TABLAT	Program Me	emory Table L	atch						0000 0000	58
PRODH	Product Reg	gister High By	te						xxxx xxxx	71
PRODL	Product Reg	gister Low Byt	e						xxxx xxxx	71
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	75
INTCON2	RBPU	INTEDG0	INTEDG1	INTEDG2	_	TMR0IP	_	RBIP	1111 -1-1	76
INTCON3	INT2IP	INT1IP	_	INT2IE	INT1IE	_	INT2IF	INT1IF	11-0 0-00	77
INDF0	Uses conten	ts of FSR0 to	address data	memory - val	ue of FSR0 no	ot changed (no	ot a physical r	egister)	n/a	50
POSTINC0	Uses contents of FSR0 to address data memory - value of FSR0 post-incremented (not a physical registe								n/a	50
POSTDEC0	Uses contents of FSR0 to address data memory - value of FSR0 post-decremented (not a physical registe								n/a	50
PREINC0	Uses contents of FSR0 to address data memory - value of FSR0 pre-incremented (not a physical register								n/a	50
PLUSW0	Uses contents of FSR0 to address data memory - value of FSR0 (not a physical register).  Offset by value in WREG.								n/a	50
FSR0H	I	I		_	Indirect Data	Memory Add	lress Pointer	0 High Byte	0000	50
FSR0L	Indirect Data	a Memory Ad	dress Pointe	r 0 Low Byte					xxxx xxxx	50
WREG	Working Re	gister							xxxx xxxx	n/a
INDF1	Uses conter	nts of FSR1 to	address da	ta memory - v	alue of FSR1	not changed	(not a physi	cal register)	n/a	50
POSTINC1	Uses conten	ts of FSR1 to	address data	memory - val	ue of FSR1 po	st-incremente	ed (not a phys	sical register)	n/a	50
POSTDEC1	Uses conten	ts of FSR1 to	address data	memory - valu	ue of FSR1 po	st-decremente	ed (not a phys	sical register)	n/a	50
PREINC1	Uses conten	ts of FSR1 to	address data	memory - val	ue of FSR1 pr	e-incremente	d (not a physi	cal register)	n/a	50
PLUSW1		nts of FSR1 to lue in WREG.		ta memory - v	alue of FSR1	(not a physic	cal register).		n/a	50
FSR1H	-	_	_	_	Indirect Data	Memory Add	lress Pointer	1 High Byte	0000	50
FSR1L	Indirect Data	a Memory Ad	dress Pointe	r 1 Low Byte					xxxx xxxx	50
BSR	l	I		_	Bank Select	Register			0000	49
INDF2	Uses conter	nts of FSR2 to	address da	ta memory - v	alue of FSR2	not changed	(not a physi	cal register)	n/a	50
POSTINC2	Uses conten	ts of FSR2 to	address data	memory - val	ue of FSR2 po	st-incremente	ed (not a phys	ical register)	n/a	50
POSTDEC2	Uses conten	ts of FSR2 to	address data	memory - valu	ue of FSR2 po	st-decrement	ed (not a phys	sical register)	n/a	50
PREINC2	Uses conten	ts of FSR2 to	address data	memory - val	ue of FSR2 pr	e-incremente	d (not a physi	cal register)	n/a	50
PLUSW2	Uses contents of FSR2 to address data memory - value of FSR2 (not a physical register).  Offset by value in WREG.								n/a	50
FSR2H	— — — Indirect Data Memory Address Pointer 2 High B							2 High Byte	0000	50
FSR2L	Indirect Data Memory Address Pointer 2 Low Byte							xxxx xxxx	50	
STATUS	_	_	_	N	OV	Z	DC	С	x xxxx	52
TMR0H	Timer0 Reg	ister High Byt	е						0000 0000	105
TMR0L	Timer0 Reg	ister Low Byte	•						xxxx xxxx	105
TOCON	TMR0ON	T08BIT	T0CS	T0SE	PSA	T0PS2	T0PS1	T0PS0	1111 1111	103

Legend: x = unknown, u = unchanged, - = unimplemented, q = value depends on condition

Note 1: RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other Oscillator modes.

<sup>2:</sup> Bit 21 of the TBLPTRU allows access to the device configuration bits.

<sup>3:</sup> These registers and bits are reserved on the PIC18F2X2 devices; always maintain these clear.

**REGISTER FILE SUMMARY (CONTINUED) TABLE 4-2:** 

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Valu POR,	e on BOR	Details on page:
OSCCON	_	_	_	_	_	_	_	SCS		0	21
LVDCON	_	_	IRVST	LVDEN	LVDL3	LVDL2	LVDL1	LVDL0	00	0101	191
WDTCON	_	_	_	_	_	_	_	SWDTE		0	203
RCON	IPEN	_	_	RI	TO	PD	POR	BOR	01	11qq	53, 28, 84
TMR1H	Timer1 Reg	ister High Byt	te		•				xxxx	xxxx	107
TMR1L	Timer1 Reg	ister Low Byte	е						xxxx	xxxx	107
T1CON	RD16	_	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	0-00	0000	107
TMR2	Timer2 Reg	ister		•				•	0000	0000	111
PR2	Timer2 Peri	od Register							1111	1111	112
T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000	0000	111
SSPBUF	SSP Receiv	e Buffer/Tran	smit Registe	r	•			•	xxxx	xxxx	125
SSPADD	SSP Addres	SSP Address Register in I <sup>2</sup> C Slave mode. SSP Baud Rate Reload Register in I <sup>2</sup> C Master mode.								0000	134
SSPSTAT	SMP	CKE	D/Ā	Р	S	R/W	UA	BF	0000	0000	126
SSPCON1	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0	0000	0000	127
SSPCON2	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN	0000	0000	137
ADRESH	A/D Result	Register High	Byte						xxxx	xxxx	187,188
ADRESL	A/D Result	Register Low	Byte						xxxx	xxxx	187,188
ADCON0	ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE	_	ADON	0000	00-0	181
ADCON1	ADFM	ADCS2	_	_	PCFG3	PCFG2	PCFG1	PCFG0	00	0000	182
CCPR1H	Capture/Co	mpare/PWM	Register1 Hig	h Byte					xxxx	xxxx	121, 123
CCPR1L	Capture/Co	mpare/PWM	Register1 Lo	w Byte					xxxx	xxxx	121, 123
CCP1CON	_	_	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00	0000	117
CCPR2H	Capture/Co	mpare/PWM	Register2 Hiç	h Byte					xxxx	xxxx	121, 123
CCPR2L	Capture/Co	mpare/PWM	Register2 Lo	w Byte					xxxx	xxxx	121, 123
CCP2CON	_	_	DC2B1	DC2B0	CCP2M3	CCP2M2	CCP2M1	CCP2M0	00	0000	117
TMR3H	Timer3 Reg	ister High Byt	te						xxxx	xxxx	113
TMR3L	Timer3 Reg	ister Low Byte	е						xxxx	xxxx	113
T3CON	RD16	T3CCP2	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON	0000	0000	113
SPBRG	USART1 Ba	aud Rate Gen	erator						0000	0000	168
RCREG	USART1 Re	eceive Registo	er						0000	0000	175, 178, 180
TXREG	USART1 Tr	ansmit Regist	ter						0000	0000	173, 176, 179
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000	-010	166
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000	000x	167
EEADR	Data EEPROM Address Register								0000	0000	65, 69
EEDATA	Data EEPR	Data EEPROM Data Register								0000	69
EECON2	Data EEPR	OM Control R	tegister 2 (no	t a physical re	egister)						65, 69
EECON1	EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD	xx~0	x000	66

Legend: x = unknown, u = unchanged, - = unimplemented, q = value depends on condition

Note 1: RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other Oscillator modes.

<sup>2:</sup> Bit 21 of the TBLPTRU allows access to the device configuration bits.

<sup>3:</sup> These registers and bits are reserved on the PIC18F2X2 devices; always maintain these clear.

## PIC18FXX2

**REGISTER FILE SUMMARY (CONTINUED) TABLE 4-2:** 

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on page:	
IPR2	_	-	_	EEIP	BCLIP	LVDIP	TMR3IP	CCP2IP	1 1111	. 83	
PIR2	_	_	_	EEIF	BCLIF	LVDIF	TMR3IF	CCP2IF	0 0000	79	
PIE2	_	-	_	EEIE	BCLIE	LVDIE	TMR3IE	CCP2IE	0 0000	81	
IPR1	PSPIP <sup>(3)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	82	
PIR1	PSPIF <sup>(3)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	78	
PIE1	PSPIE <sup>(3)</sup>	ADIE	RCIE	TXIE SSPIE CCP1IE TMR2IE TMR1IE					0000 0000	80	
TRISE <sup>(3)</sup>	IBF	IBF OBF IBOV PSPMODE — Data Direction bits for PORTE								. 98	
TRISD(3)	Data Directi	ata Direction Control Register for PORTD									
TRISC	Data Directi	Data Direction Control Register for PORTC									
TRISB	Data Directi	on Control Re	egister for PC	RTB					1111 1111	. 90	
TRISA	_	TRISA6 <sup>(1)</sup>	Data Directi	on Control Re	gister for PO	RTA			-111 1111	. 87	
LATE <sup>(3)</sup>	_	_	_	_	_	Read PORT		,	xxx	99	
LATD <sup>(3)</sup>	Read PORT	D Data Latch	, Write POR	ΓD Data Latch	1				xxxx xxxx	95	
LATC	Read PORT	C Data Latch	, Write POR	TC Data Latch	1				xxxx xxxx	93	
LATB	Read PORT	B Data Latch	, Write POR	ΓB Data Latch	1				xxxx xxxx	90	
LATA	_	LATA6 <sup>(1)</sup>	Read PORT	A Data Latch,	Write PORT	A Data Latch <sup>(</sup>	(1)		-xxx xxxx	87	
PORTE <sup>(3)</sup>	Read PORT	E pins, Write	PORTE Data	a Latch					000	99	
PORTD <sup>(3)</sup>	Read PORT	D pins, Write	PORTD Dat	a Latch					xxxx xxxx	95	
PORTC	Read PORT	C pins, Write	PORTC Dat	a Latch					xxxx xxxx	93	
PORTB	Read PORT	B pins, Write	PORTB Data	a Latch					xxxx xxxx	90	
PORTA	_	RA6 <sup>(1)</sup>	Read PORT	A pins, Write	PORTA Data	Latch <sup>(1)</sup>			-x0x 0000	87	

Legend: x = unknown, u = unchanged, - = unimplemented, q = value depends on condition

Note 1: RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other Oscillator modes.

<sup>2:</sup> Bit 21 of the TBLPTRU allows access to the device configuration bits.

<sup>3:</sup> These registers and bits are reserved on the PIC18F2X2 devices; always maintain these clear.

### 4.10 Access Bank

The Access Bank is an architectural enhancement which is very useful for C compiler code optimization. The techniques used by the C compiler may also be useful for programs written in assembly.

This data memory region can be used for:

- · Intermediate computational values
- · Local variables of subroutines
- Faster context saving/switching of variables
- · Common variables
- Faster evaluation/control of SFRs (no banking)

The Access Bank is comprised of the upper 128 bytes in Bank 15 (SFRs) and the lower 128 bytes in Bank 0. These two sections will be referred to as Access RAM High and Access RAM Low, respectively. Figure 4-6 and Figure 4-7 indicate the Access RAM areas.

A bit in the instruction word specifies if the operation is to occur in the bank specified by the BSR register or in the Access Bank. This bit is denoted by the 'a' bit (for access bit).

When forced in the Access Bank (a = 0), the last address in Access RAM Low is followed by the first address in Access RAM High. Access RAM High maps the Special Function registers, so that these registers can be accessed without any software overhead. This is useful for testing status flags and modifying control bits.

## 4.11 Bank Select Register (BSR)

The need for a large general purpose memory space dictates a RAM banking scheme. The data memory is partitioned into sixteen banks. When using direct addressing, the BSR should be configured for the desired bank.

BSR<3:0> holds the upper 4 bits of the 12-bit RAM address. The BSR<7:4> bits will always read '0's, and writes will have no effect.

A MOVLB instruction has been provided in the instruction set to assist in selecting banks.


If the currently selected bank is not implemented, any read will return all '0's and all writes are ignored. The STATUS register bits will be set/cleared as appropriate for the instruction performed.

Each Bank extends up to FFh (256 bytes). All data memory is implemented as static RAM.

A MOVFF instruction ignores the BSR, since the 12-bit addresses are embedded into the instruction word.

Section 4.12 provides a description of indirect addressing, which allows linear addressing of the entire RAM space.

### FIGURE 4-8: DIRECT ADDRESSING



2: The access bit of the instruction can be used to force an override of the selected bank (BSR<3:0>) to the

3: The MOVFF instruction embeds the entire 12-bit address in the instruction.

registers of the Access Bank.

## 4.12 Indirect Addressing, INDF and FSR Registers

Indirect addressing is a mode of addressing data memory, where the data memory address in the instruction is not fixed. An FSR register is used as a pointer to the data memory location that is to be read or written. Since this pointer is in RAM, the contents can be modified by the program. This can be useful for data tables in the data memory and for software stacks. Figure 4-9 shows the operation of indirect addressing. This shows the moving of the value to the data memory address specified by the value of the FSR register.

Indirect addressing is possible by using one of the INDF registers. Any instruction using the INDF register actually accesses the register pointed to by the File Select Register, FSR. Reading the INDF register itself, indirectly (FSR = 0), will read 00h. Writing to the INDF register indirectly, results in a no operation. The FSR register contains a 12-bit address, which is shown in Figure 4-10.

The INDFn register is not a physical register. Addressing INDFn actually addresses the register whose address is contained in the FSRn register (FSRn is a pointer). This is indirect addressing.

Example 4-4 shows a simple use of indirect addressing to clear the RAM in Bank1 (locations 100h-1FFh) in a minimum number of instructions.

# EXAMPLE 4-4: HOW TO CLEAR RAM (BANK1) USING INDIRECT ADDRESSING

```
LFSR FSR0 ,0x100 ;

NEXT CLRF POSTINC0 ; Clear INDF ; register and ; inc pointer BTFSS FSR0H, 1 ; All done with ; Bank1?

GOTO NEXT ; NO, clear next CONTINUE ; YES, continue
```

There are three indirect addressing registers. To address the entire data memory space (4096 bytes), these registers are 12-bit wide. To store the 12-bits of addressing information, two 8-bit registers are required. These indirect addressing registers are:

- FSR0: composed of FSR0H:FSR0L
- 2. FSR1: composed of FSR1H:FSR1L
- FSR2: composed of FSR2H:FSR2L

In addition, there are registers INDF0, INDF1 and INDF2, which are not physically implemented. Reading or writing to these registers activates indirect addressing, with the value in the corresponding FSR register being the address of the data. If an instruction writes a value to INDF0, the value will be written to the address pointed to by FSR0H:FSR0L. A read from INDF1 reads

the data from the address pointed to by FSR1H:FSR1L. INDFn can be used in code anywhere an operand can be used.

If INDF0, INDF1 or INDF2 are read indirectly via an FSR, all '0's are read (zero bit is set). Similarly, if INDF0, INDF1 or INDF2 are written to indirectly, the operation will be equivalent to a NOP instruction and the STATUS bits are not affected.

## 4.12.1 INDIRECT ADDRESSING OPERATION

Each FSR register has an INDF register associated with it, plus four additional register addresses. Performing an operation on one of these five registers determines how the FSR will be modified during indirect addressing.

When data access is done to one of the five INDFn locations, the address selected will configure the FSRn register to:

- Do nothing to FSRn after an indirect access (no change) INDFn
- Auto-decrement FSRn after an indirect access (post-decrement) - POSTDECn
- Auto-increment FSRn after an indirect access (post-increment) - POSTINCn
- Auto-increment FSRn before an indirect access (pre-increment) - PREINCn
- Use the value in the WREG register as an offset to FSRn. Do not modify the value of the WREG or the FSRn register after an indirect access (no change) - PLUSWn

When using the auto-increment or auto-decrement features, the effect on the FSR is not reflected in the STATUS register. For example, if the indirect address causes the FSR to equal '0', the Z bit will not be set.

Incrementing or decrementing an FSR affects all 12 bits. That is, when FSRnL overflows from an increment, FSRnH will be incremented automatically.


Adding these features allows the FSRn to be used as a stack pointer, in addition to its uses for table operations in data memory.

Each FSR has an address associated with it that performs an indexed indirect access. When a data access to this INDFn location (PLUSWn) occurs, the FSRn is configured to add the signed value in the WREG register and the value in FSR to form the address before an indirect access. The FSR value is not changed.


If an FSR register contains a value that points to one of the INDFn, an indirect read will read 00h (zero bit is set), while an indirect write will be equivalent to a NOP (STATUS bits are not affected).

If an indirect addressing operation is done where the target address is an FSRnH or FSRnL register, the write operation will dominate over the pre- or post-increment/decrement functions.

FIGURE 4-9: INDIRECT ADDRESSING OPERATION



## FIGURE 4-10: INDIRECT ADDRESSING



## 4.13 STATUS Register

The STATUS register, shown in Register 4-2, contains the arithmetic status of the ALU. The STATUS register can be the destination for any instruction, as with any other register. If the STATUS register is the destination for an instruction that affects the Z, DC, C, OV, or N bits, then the write to these five bits is disabled. These bits are set or cleared according to the device logic. Therefore, the result of an instruction with the STATUS register as destination may be different than intended.

For example, CLRF STATUS will clear the upper three bits and set the Z bit. This leaves the STATUS register as 000u uluu (where u = unchanged).

It is recommended, therefore, that only BCF, BSF, SWAPF, MOVFF and MOVWF instructions are used to alter the STATUS register, because these instructions do not affect the  $\tt Z$ ,  $\tt C$ ,  $\tt DC$ ,  $\tt OV$ , or  $\tt N$  bits from the STATUS register. For other instructions not affecting any status bits, see Table 20-2.

Note: The C and DC bits operate as a borrow and digit borrow bit respectively, in subtraction.

## **REGISTER 4-2: STATUS REGISTER**

U-0	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
_	_	_	N	OV	Z	DC	С
bit 7				•			bit 0

## bit 7-5 Unimplemented: Read as '0'

bit 4 N: Negative bit

This bit is used for signed arithmetic (2's complement). It indicates whether the result was negative (ALU MSB = 1).

- 1 = Result was negative
- 0 = Result was positive
- bit 3 **OV:** Overflow bit

This bit is used for signed arithmetic (2's complement). It indicates an overflow of the 7-bit magnitude, which causes the sign bit (bit7) to change state.

- 1 = Overflow occurred for signed arithmetic (in this arithmetic operation)
- 0 = No overflow occurred
- bit 2 Z: Zero bit
  - 1 = The result of an arithmetic or logic operation is zero
  - 0 = The result of an arithmetic or logic operation is not zero
- bit 1 **DC:** Digit carry/borrow bit

For ADDWF, ADDLW, SUBLW, and SUBWF instructions

- 1 = A carry-out from the 4th low order bit of the result occurred
- 0 = No carry-out from the 4th low order bit of the result

Note: For borrow, the polarity is reversed. A subtraction is executed by adding the two's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either the bit 4 or bit 3 of the source register.

## bit 0 C: Carry/borrow bit

For ADDWF, ADDLW, SUBLW, and SUBWF instructions

- 1 = A carry-out from the Most Significant bit of the result occurred
- 0 = No carry-out from the Most Significant bit of the result occurred

Note: For borrow, the polarity is reversed. A subtraction is executed by adding the two's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either the high or low order bit of the source register.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

## 4.14 RCON Register

The Reset Control (RCON) register contains flag bits that allow differentiation between the sources of a device RESET. These flags include the  $\overline{\text{TO}}$ ,  $\overline{\text{PD}}$ ,  $\overline{\text{POR}}$ ,  $\overline{\text{BOR}}$  and  $\overline{\text{RI}}$  bits. This register is readable and writable.

- Note 1: If the BOREN configuration bit is set (Brown-out Reset enabled), the BOR bit is '1' on a Power-on Reset. After a Brown-out Reset has occurred, the BOR bit will be cleared, and must be set by firmware to indicate the occurrence of the next Brown-out Reset.
  - 2: It is recommended that the POR bit be set after a Power-on Reset has been detected, so that subsequent Power-on Resets may be detected.

### **REGISTER 4-3: RCON REGISTER**

R/W-0	U-0	U-0	R/W-1	R-1	R-1	R/W-0	R/W-0
IPEN	_	_	RI	TO	PD	POR	BOR
bit 7							bit 0

bit 7 **IPEN:** Interrupt Priority Enable bit

1 = Enable priority levels on interrupts

0 = Disable priority levels on interrupts (16CXXX Compatibility mode)

bit 6-5 Unimplemented: Read as '0'

bit 4 RI: RESET Instruction Flag bit

1 = The RESET instruction was not executed

0 = The RESET instruction was executed causing a device RESET (must be set in software after a Brown-out Reset occurs)

bit 3 TO: Watchdog Time-out Flag bit

1 = After power-up, CLRWDT instruction, or SLEEP instruction

0 = A WDT time-out occurred

bit 2 PD: Power-down Detection Flag bit

1 = After power-up or by the CLRWDT instruction

0 = By execution of the SLEEP instruction

bit 1 POR: Power-on Reset Status bit

1 = A Power-on Reset has not occurred

0 = A Power-on Reset occurred

(must be set in software after a Power-on Reset occurs)

bit 0 BOR: Brown-out Reset Status bit

1 = A Brown-out Reset has not occurred

0 = A Brown-out Reset occurred

(must be set in software after a Brown-out Reset occurs)

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
- n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## PIC18FXX2

**NOTES:** 

#### 5.0 FLASH PROGRAM MEMORY

The FLASH Program Memory is readable, writable, and erasable during normal operation over the entire VDD range.

A read from program memory is executed on one byte at a time. A write to program memory is executed on blocks of 8 bytes at a time. Program memory is erased in blocks of 64 bytes at a time. A bulk erase operation may not be issued from user code.

Writing or erasing program memory will cease instruction fetches until the operation is complete. The program memory cannot be accessed during the write or erase, therefore, code cannot execute. An internal programming timer terminates program memory writes and erases.

A value written to program memory does not need to be a valid instruction. Executing a program memory location that forms an invalid instruction results in a NOP

#### 5.1 **Table Reads and Table Writes**

In order to read and write program memory, there are two operations that allow the processor to move bytes between the program memory space and the data RAM:

- Table Read (TBLRD)
- Table Write (TBLWT)


The program memory space is 16-bits wide, while the data RAM space is 8-bits wide. Table Reads and Table Writes move data between these two memory spaces through an 8-bit register (TABLAT).

Table Read operations retrieve data from program memory and places it into the data RAM space. Figure 5-1 shows the operation of a Table Read with program memory and data RAM.


Table Write operations store data from the data memory space into holding registers in program memory. The procedure to write the contents of the holding registers into program memory is detailed in Section 5.5, "Writing to FLASH Program Memory". Figure 5-2 shows the operation of a Table Write with program memory and data RAM.

Table operations work with byte entities. A table block containing data, rather than program instructions, is not required to be word aligned. Therefore, a table block can start and end at any byte address. If a Table Write is being used to write executable code into program memory, program instructions will need to be word aligned.

FIGURE 5-1: **TABLE READ OPERATION** 



### FIGURE 5-2: TABLE WRITE OPERATION



## 5.2 Control Registers

Several control registers are used in conjunction with the TBLRD and TBLWT instructions. These include the:

- · EECON1 register
- EECON2 register
- TABLAT register
- TBLPTR registers

## 5.2.1 EECON1 AND EECON2 REGISTERS

EECON1 is the control register for memory accesses.

EECON2 is not a physical register. Reading EECON2 will read all '0's. The EECON2 register is used exclusively in the memory write and erase sequences.

Control bit EEPGD determines if the access will be a program or data EEPROM memory access. When clear, any subsequent operations will operate on the data EEPROM memory. When set, any subsequent operations will operate on the program memory.

Control bit CFGS determines if the access will be to the configuration registers or to program memory/data EEPROM memory. When set, subsequent operations will operate on configuration registers, regardless of EEPGD (see "Special Features of the CPU", Section 19.0). When clear, memory selection access is determined by EEPGD.

The FREE bit, when set, will allow a program memory erase operation. When the FREE bit is set, the erase operation is initiated on the next WR command. When FREE is clear, only writes are enabled.

The WREN bit, when set, will allow a write operation. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a MCLR Reset or a WDT Time-out Reset during normal operation. In these situations, the user can check the WRERR bit and rewrite the location. It is necessary to reload the data and address registers (EEDATA and EEADR), due to RESET values of zero.

Control bit WR initiates write operations. This bit cannot be cleared, only set, in software. It is cleared in hardware at the completion of the write operation. The inability to clear the WR bit in software prevents the accidental or premature termination of a write operation.

**Note:** Interrupt flag bit EEIF, in the PIR2 register, is set when the write is complete. It must be cleared in software.

## REGISTER 5-1: EECON1 REGISTER (ADDRESS FA6h)

	R/W-x	R/W-x	U-0	R/W-0	R/W-x	R/W-0	R/S-0	R/S-0	
	EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD	
bit 7									

bit 7 **EEPGD:** FLASH Program or Data EEPROM Memory Select bit

1 = Access FLASH Program memory

0 = Access Data EEPROM memory

bit 6 CFGS: FLASH Program/Data EE or Configuration Select bit

1 = Access Configuration registers

0 = Access FLASH Program or Data EEPROM memory

bit 5 Unimplemented: Read as '0'

bit 4 FREE: FLASH Row Erase Enable bit

1 = Erase the program memory row addressed by TBLPTR on the next WR command (cleared by completion of erase operation)

0 = Perform write only

bit 3 WRERR: FLASH Program/Data EE Error Flag bit

1 = A write operation is prematurely terminated (any RESET during self-timed programming in normal operation)

0 = The write operation completed

**Note:** When a WRERR occurs, the EEPGD and CFGS bits are not cleared. This allows tracing of the error condition.

bit 2 WREN: FLASH Program/Data EE Write Enable bit

1 = Allows write cycles

0 = Inhibits write to the EEPROM

bit 1 WR: Write Control bit

1 = Initiates a data EEPROM erase/write cycle or a program memory erase cycle or write cycle. (The operation is self timed and the bit is cleared by hardware once write is complete. The WR bit can only be set (not cleared) in software.)

0 = Write cycle to the EEPROM is complete

bit 0 RD: Read Control bit

1 = Initiates an EEPROM read

(Read takes one cycle. RD is cleared in hardware. The RD bit can only be set (not cleared) in software. RD bit cannot be set when EEPGD = 1.)

0 = Does not initiate an EEPROM read

### 5.2.2 TABLAT - TABLE LATCH REGISTER

The Table Latch (TABLAT) is an 8-bit register mapped into the SFR space. The Table Latch is used to hold 8-bit data during data transfers between program memory and data RAM.

## 5.2.3 TBLPTR - TABLE POINTER REGISTER

The Table Pointer (TBLPTR) addresses a byte within the program memory. The TBLPTR is comprised of three SFR registers: Table Pointer Upper Byte, Table Pointer High Byte and Table Pointer Low Byte (TBLPTRU:TBLPTRH:TBLPTRL). These three registers join to form a 22-bit wide pointer. The low order 21 bits allow the device to address up to 2 Mbytes of program memory space. The 22nd bit allows access to the Device ID, the User ID and the Configuration bits.

The table pointer, TBLPTR, is used by the TBLRD and TBLWT instructions. These instructions can update the TBLPTR in one of four ways based on the table operation. These operations are shown in Table 5-1. These operations on the TBLPTR only affect the low order 21 bits.

### 5.2.4 TABLE POINTER BOUNDARIES

TBLPTR is used in reads, writes, and erases of the FLASH program memory.

When a TBLRD is executed, all 22 bits of the Table Pointer determine which byte is read from program memory into TABLAT.

When a TBLWT is executed, the three LSbs of the Table Pointer (TBLPTR<2:0>) determine which of the eight program memory holding registers is written to. When the timed write to program memory (long write) begins, the 19 MSbs of the Table Pointer, TBLPTR (TBLPTR<21:3>), will determine which program memory block of 8 bytes is written to. For more detail, see Section 5.5 ("Writing to FLASH Program Memory").


When an erase of program memory is executed, the 16 MSbs of the Table Pointer (TBLPTR<21:6>) point to the 64-byte block that will be erased. The Least Significant bits (TBLPTR<5:0>) are ignored.

Figure 5-3 describes the relevant boundaries of TBLPTR based on FLASH program memory operations.

TABLE 5-1: TABLE P	OINTER OPERATIONS	WITH TBLRD AND	TBLWT INSTRUCTIONS
--------------------	-------------------	----------------	--------------------

Example	Operation on Table Pointer
TBLRD* TBLWT*	TBLPTR is not modified
TBLRD*+ TBLWT*+	TBLPTR is incremented after the read/write
TBLRD*- TBLWT*-	TBLPTR is decremented after the read/write
TBLRD+* TBLWT+*	TBLPTR is incremented before the read/write

FIGURE 5-3: TABLE POINTER BOUNDARIES BASED ON OPERATION




## 5.3 Reading the FLASH Program Memory

The TBLRD instruction is used to retrieve data from program memory and place into data RAM. Table Reads from program memory are performed one byte at a time.

TBLPTR points to a byte address in program space. Executing TBLRD places the byte pointed to into TABLAT. In addition, TBLPTR can be modified automatically for the next Table Read operation.

The internal program memory is typically organized by words. The Least Significant bit of the address selects between the high and low bytes of the word. Figure 5-4 shows the interface between the internal program memory and the TABLAT.

FIGURE 5-4: READS FROM FLASH PROGRAM MEMORY



## **EXAMPLE 5-1: READING A FLASH PROGRAM MEMORY WORD**

```
MOVLW CODE ADDR UPPER
                                           ; Load TBLPTR with the base
           MOVWF TBLPTRU
                                           ; address of the word
           MOVLW CODE_ADDR_HIGH
           MOVWF TBLPTRH
           MOVLW CODE ADDR LOW
           MOVWF TBLPTRL
READ WORD
           \mathtt{TBLRD*}+
                                           ; read into TABLAT and increment
           MOVF TABLAT, W
                                           ; get data
           MOVWF WORD EVEN
           TBLRD*+
                                           ; read into TABLAT and increment
           MOVF TABLAT, W
                                           ; get data
           MOVWF WORD ODD
```

## 5.4 Erasing FLASH Program memory

The minimum erase block is 32 words or 64 bytes. Only through the use of an external programmer, or through ICSP control can larger blocks of program memory be bulk erased. Word erase in the FLASH array is not supported.

When initiating an erase sequence from the micro-controller itself, a block of 64 bytes of program memory is erased. The Most Significant 16 bits of the TBLPTR<21:6> point to the block being erased. TBLPTR<5:0> are ignored.

The EECON1 register commands the erase operation. The EEPGD bit must be set to point to the FLASH program memory. The WREN bit must be set to enable write operations. The FREE bit is set to select an erase operation.

For protection, the write initiate sequence for EECON2 must be used.

A long write is necessary for erasing the internal FLASH. Instruction execution is halted while in a long write cycle. The long write will be terminated by the internal programming timer.

## 5.4.1 FLASH PROGRAM MEMORY ERASE SEQUENCE

The sequence of events for erasing a block of internal program memory location is:

- Load table pointer with address of row being erased.
- Set EEPGD bit to point to program memory, clear CFGS bit to access program memory, set WREN bit to enable writes, and set FREE bit to enable the erase.
- 3. Disable interrupts.
- 4. Write 55h to EECON2.
- 5. Write AAh to EECON2.
- 6. Set the WR bit. This will begin the row erase cycle.
- 7. The CPU will stall for duration of the erase (about 2 ms using internal timer).
- Re-enable interrupts.

## **EXAMPLE 5-2: ERASING A FLASH PROGRAM MEMORY ROW**

```
CODE ADDR UPPER
                                               ; load TBLPTR with the base
               MOVIW
               MOVWF
                       TBLPTRU
                                               ; address of the memory block
                       CODE ADDR HIGH
               MOVIW
               MOVWF
                       TBLPTRH
                       CODE ADDR LOW
               MOVLW
                       TBLPTRL
               MOVWF
    ERASE ROW
               BSF
                       EECON1, EEPGD
                                               ; point to FLASH program memory
               BCF
                       EECON1, CFGS
                                               ; access FLASH program memory
               BSF
                       EECON1, WREN
                                               ; enable write to memory
               BSF
                       EECON1, FREE
                                               ; enable Row Erase operation
               BCF
                       INTCON, GIE
                                               ; disable interrupts
               MOVLW
                       55h
Required
               MOVWF
                       EECON2
                                               ; write 55h
Sequence
               M-TVOM
                       AAh
               MOVWF
                       EECON2
                                               ; write AAh
               BSF
                       EECON1, WR
                                               ; start erase (CPU stall)
               BSF
                       INTCON, GIE
                                               ; re-enable interrupts
```

## 5.5 Writing to FLASH Program Memory

The minimum programming block is 4 words or 8 bytes. Word or byte programming is not supported.

Table Writes are used internally to load the holding registers needed to program the FLASH memory. There are 8 holding registers used by the Table Writes for programming.


Since the Table Latch (TABLAT) is only a single byte, the TBLWT instruction has to be executed 8 times for each programming operation. All of the Table Write

operations will essentially be short writes, because only the holding registers are written. At the end of updating 8 registers, the EECON1 register must be written to, to start the programming operation with a long write.

The long write is necessary for programming the internal FLASH. Instruction execution is halted while in a long write cycle. The long write will be terminated by the internal programming timer.

The EEPROM on-chip timer controls the write time. The write/erase voltages are generated by an on-chip charge pump rated to operate over the voltage range of the device for byte or word operations.

FIGURE 5-5: TABLE WRITES TO FLASH PROGRAM MEMORY



## 5.5.1 FLASH PROGRAM MEMORY WRITE SEQUENCE

The sequence of events for programming an internal program memory location should be:

- 1. Read 64 bytes into RAM.
- 2. Update data values in RAM as necessary.
- 3. Load Table Pointer with address being erased.
- 4. Do the row erase procedure.
- Load Table Pointer with address of first byte being written.
- Write the first 8 bytes into the holding registers with auto-increment (TBLWT\*+ or TBLWT+\*).
- Set EEPGD bit to point to program memory, clear the CFGS bit to access program memory, and set WREN to enable byte writes.
- 8. Disable interrupts.
- 9. Write 55h to EECON2.

- 10. Write AAh to EECON2.
- 11. Set the WR bit. This will begin the write cycle.
- 12. The CPU will stall for duration of the write (about 2 ms using internal timer).
- 13. Re-enable interrupts.
- 14. Repeat steps 6-14 seven times, to write 64 bytes.
- 15. Verify the memory (Table Read).

This procedure will require about 18 ms to update one row of 64 bytes of memory. An example of the required code is given in Example 5-3.

**Note:** Before setting the WR bit, the table pointer address needs to be within the intended address range of the 8 bytes in the holding registers.

## **EXAMPLE 5-3: WRITING TO FLASH PROGRAM MEMORY**

```
MOVLW D'64
                                          ; number of bytes in erase block
          MOVWF COUNTER
          MOVLW BUFFER_ADDR_HIGH
                                          ; point to buffer
          MOVWF FSR0H
          MOVLW BUFFER_ADDR_LOW
          MOVWF
                 FSR0L
                                          ; Load TBLPTR with the base
          MOVLW
                 CODE ADDR UPPER
          MOVWF
                 TBLPTRU
                                          ; address of the memory block
          MOVLW CODE_ADDR_HIGH
          MOVWF TBLPTRH
          MOVLW CODE ADDR LOW
          MOVWF TBLPTRL
READ_BLOCK
          TBLRD*+
                                         ; read into TABLAT, and inc
                                         ; get data
          MOVF TABLAT, W
                                         ; store data
          MOVWF POSTINCO
          DECFSZ COUNTER
                                          ; done?
          BRA READ BLOCK
                                          ; repeat
MODIFY_WORD
          MOVLW DATA ADDR HIGH
                                    ; point to buffer
          MOVWF FSR0H
          MOVLW DATA_ADDR_LOW
          MOVWF FSR0L
          MOVLW NEW_DATA_LOW
                                         ; update buffer word
          MOVWF POSTINCO
          MOVLW
                 NEW DATA HIGH
          MOVWF INDF0
ERASE_BLOCK
                                         ; load TBLPTR with the base
          MOVLW CODE ADDR UPPER
          MOVWF TBLPTRU
                                          ; address of the memory block
          MOVLW CODE ADDR HIGH
          MOVWF TBLPTRH
          MOVLW CODE ADDR LOW
          MOVWF TBLPTRL
          BSF
                                     ; point to FLASH program memory
                 EECON1, EEPGD
                                        ; access FLASH program memory
                 EECON1, CFGS
                                        ; enable write to memory
          BSF
                 EECON1, WREN
               EECON1, FREE
          RSF
                                          ; enable Row Erase operation
          BCF INTCON, GIE
                                          ; disable interrupts
          MOVLW 55h
          MOVWF EECON2
                                          ; write 55h
          MOVLW AAh
          MOVWF EECON2
                                         ; write AAh
          BSF EECON1, WR
BSF INTCON, GIE
TBLRD*-
                                         ; start erase (CPU stall)
                                        ; re-enable interrupts
          TBLRD*-
                                         ; dummy read decrement
WRITE BUFFER BACK
                                         ; number of write buffer groups of 8 bytes
          MOVLW 8
          MOVWF COUNTER_HI
                                         ; point to buffer
          MOVLW BUFFER_ADDR_HIGH
          MOVWF FSR0H
          MOVLW BUFFER_ADDR_LOW
          MOVWF FSR0L
PROGRAM_LOOP
          MOVLW
                                          ; number of bytes in holding register
          MOVWF COUNTER
WRITE WORD TO HREGS
          MOVF POSTINCO, W
                                          ; get low byte of buffer data
          MOVWF TABLAT
                                          ; present data to table latch
          \mathtt{TBLWT}+*
                                          ; write data, perform a short write
                                          ; to internal TBLWT holding register.
          DECFSZ COUNTER
                                          ; loop until buffers are full
          BRA WRITE_WORD_TO_HREGS
```

## **EXAMPLE 5-3: WRITING TO FLASH PROGRAM MEMORY (CONTINUED)**

PROGRAM_ME	MORY		
	BSF	EECON1, EEPGD	; point to FLASH program memory
	BCF	EECON1,CFGS	; access FLASH program memory
	BSF	EECON1, WREN	; enable write to memory
	BCF	INTCON, GIE	; disable interrupts
	MOVLW	55h	
Required	MOVWF	EECON2	; write 55h
Sequence	MOVLW	AAh	
	MOVWF	EECON2	; write AAh
	BSF	EECON1,WR	; start program (CPU stall)
	BSF	INTCON, GIE	; re-enable interrupts
	DECFSZ	COUNTER_HI	; loop until done
	BRA	PROGRAM_LOOP	
	BCF	EECON1, WREN	; disable write to memory

## 5.5.2 WRITE VERIFY

Depending on the application, good programming practice may dictate that the value written to the memory should be verified against the original value. This should be used in applications where excessive writes can stress bits near the specification limit.

## 5.5.3 UNEXPECTED TERMINATION OF WRITE OPERATION

If a write is terminated by an unplanned event, such as loss of power or an unexpected RESET, the memory location just programmed should be verified and reprogrammed if needed. The WRERR bit is set when a write operation is interrupted by a MCLR Reset, or a WDT Time-out Reset during normal operation. In these situations, users can check the WRERR bit and rewrite the location.

## 5.5.4 PROTECTION AGAINST SPURIOUS WRITES

To protect against spurious writes to FLASH program memory, the write initiate sequence must also be followed. See "Special Features of the CPU" (Section 19.0) for more detail.

## 5.6 FLASH Program Operation During Code Protection

See "Special Features of the CPU" (Section 19.0) for details on code protection of FLASH program memory.

TABLE 5-2: REGISTERS ASSOCIATED WITH PROGRAM FLASH MEMORY

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on All Other RESETS
FF8h	TBLPTRU	_	_	bit21		Memory T R<20:16>)	00 0000	00 0000			
FF7h	TBPLTRH	Program I	Memory Ta	able Point	er High B	yte (TBLP	ΓR<15:8>)			0000 0000	0000 0000
FF6h	TBLPTRL	Program I	Memory Ta	able Point	er High B	yte (TBLP	ΓR<7:0>)			0000 0000	0000 0000
FF5h	TABLAT	Program I	Memory Ta	able Latch						0000 0000	0000 0000
FF2h	INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INTE	RBIE	TMR0IF	INTF	RBIF	0000 000x	0000 000u
FA7h	EECON2	EEPROM	EEPROM Control Register2 (not a physical register)								_
FA6h	EECON1	EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD	xx-0 x000	uu-0 u000
FA2h	IPR2	_	_		EEIP	BCLIP	LVDIP	TMR3IP	CCP2IP	1 1111	1 1111
FA1h	PIR2	_	_	_	EEIF	BCLIF	LVDIF	TMR3IF	CCP2IF	0 0000	0 0000
FA0h	PIE2	_	_	_	EEIE	BCLIE	LVDIE	TMR3IE	CCP2IE	0 0000	0 0000

Legend: x = unknown, u = unchanged, r = reserved, - = unimplemented read as '0'.

Shaded cells are not used during FLASH/EEPROM access.

## PIC18FXX2

**NOTES:** 

## 6.0 DATA EEPROM MEMORY

The Data EEPROM is readable and writable during normal operation over the entire VDD range. The data memory is not directly mapped in the register file space. Instead, it is indirectly addressed through the Special Function Registers (SFR).

There are four SFRs used to read and write the program and data EEPROM memory. These registers are:

- EECON1
- EECON2
- EEDATA
- EEADR

The EEPROM data memory allows byte read and write. When interfacing to the data memory block, EEDATA holds the 8-bit data for read/write and EEADR holds the address of the EEPROM location being accessed. These devices have 256 bytes of data EEPROM with an address range from 0h to FFh.

The EEPROM data memory is rated for high erase/write cycles. A byte write automatically erases the location and writes the new data (erase-before-write). The write time is controlled by an on-chip timer. The write time will vary with voltage and temperature, as well as from chip to chip. Please refer to parameter D122 (Electrical Characteristics, Section 22.0) for exact limits.

## 6.1 EEADR

The address register can address up to a maximum of 256 bytes of data EEPROM.

## 6.2 EECON1 and EECON2 Registers

EECON1 is the control register for EEPROM memory accesses.

EECON2 is not a physical register. Reading EECON2 will read all '0's. The EECON2 register is used exclusively in the EEPROM write sequence.

Control bits RD and WR initiate read and write operations, respectively. These bits cannot be cleared, only set, in software. They are cleared in hardware at the completion of the read or write operation. The inability to clear the WR bit in software prevents the accidental or premature termination of a write operation.

The WREN bit, when set, will allow a write operation. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a MCLR Reset, or a WDT Time-out Reset during normal operation. In these situations, the user can check the WRERR bit and rewrite the location. It is necessary to reload the data and address registers (EEDATA and EEADR), due to the RESET condition forcing the contents of the registers to zero.

Note: Interrupt flag bit, EEIF in the PIR2 register, is set when write is complete. It must be

cleared in software.

## REGISTER 6-1: EECON1 REGISTER (ADDRESS FA6h)

bit 7				L	L	I.	hit 0
EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD
R/W-x	R/W-x	U-0	R/W-0	R/W-x	R/W-0	R/S-0	R/S-0

bit 7 **EEPGD:** FLASH Program or Data EEPROM Memory Select bit

1 = Access FLASH Program memory

0 = Access Data EEPROM memory

bit 6 CFGS: FLASH Program/Data EE or Configuration Select bit

1 = Access Configuration or Calibration registers

0 = Access FLASH Program or Data EEPROM memory

bit 5 Unimplemented: Read as '0'

bit 4 FREE: FLASH Row Erase Enable bit

1 = Erase the program memory row addressed by TBLPTR on the next WR command (cleared by completion of erase operation)

0 = Perform write only

bit 3 WRERR: FLASH Program/Data EE Error Flag bit

1 = A write operation is prematurely terminated (any  $\overline{\text{MCLR}}$  or any WDT Reset during self-timed programming in normal operation)

0 = The write operation completed

**Note:** When a WRERR occurs, the EEPGD or FREE bits are not cleared. This allows tracing of the error condition.

bit 2 WREN: FLASH Program/Data EE Write Enable bit

1 = Allows write cycles

0 = Inhibits write to the EEPROM

bit 1 WR: Write Control bit

1 = Initiates a data EEPROM erase/write cycle or a program memory erase cycle or write cycle. (The operation is self-timed and the bit is cleared by hardware once write is complete. The WR bit can only be set (not cleared) in software.)

0 = Write cycle to the EEPROM is complete

bit 0 RD: Read Control bit

1 = Initiates an EEPROM read

(Read takes one cycle. RD is cleared in hardware. The RD bit can only be set (not cleared) in software. RD bit cannot be set when EEPGD = 1.)

0 = Does not initiate an EEPROM read

Legend:  $R = \text{Readable bit} \qquad W = \text{Writable bit} \qquad U = \text{Unimplemented bit, read as '0'} \\ - n = \text{Value at POR} \qquad \text{'1'} = \text{Bit is set} \qquad \text{'0'} = \text{Bit is cleared} \qquad x = \text{Bit is unknown}$ 

## 6.3 Reading the Data EEPROM Memory

To read a data memory location, the user must write the address to the EEADR register, clear the EEPGD control bit (EECON1<7>), clear the CFGS control bit

(EECON1<6>), and then set control bit RD (EECON1<0>). The data is available for the very next instruction cycle; therefore, the EEDATA register can be read by the next instruction. EEDATA will hold this value until another read operation, or until it is written to by the user (during a write operation).

### **EXAMPLE 6-1: DATA EEPROM READ**

```
MOVLW DATA_EE_ADDR ;

MOVWF EEADR ; Data Memory Address to read

BCF EECON1, EEPGD ; Point to DATA memory

BCF EECON1, CFGS ; Access program FLASH or Data EEPROM memory

BSF EECON1, RD ; EEPROM Read

MOVF EEDATA, W ; W = EEDATA
```

## 6.4 Writing to the Data EEPROM Memory

To write an EEPROM data location, the address must first be written to the EEADR register and the data written to the EEDATA register. Then the sequence in Example 6-2 must be followed to initiate the write cycle.

The write will not initiate if the above sequence is not exactly followed (write 55h to EECON2, write AAh to EECON2, then set WR bit) for each byte. It is strongly recommended that interrupts be disabled during this code segment.

Additionally, the WREN bit in EECON1 must be set to enable writes. This mechanism prevents accidental writes to data EEPROM due to unexpected code exe-

cution (i.e., runaway programs). The WREN bit should be kept clear at all times, except when updating the EEPROM. The WREN bit is not cleared by hardware.

After a write sequence has been initiated, EECON1, EEADR and EDATA cannot be modified. The WR bit will be inhibited from being set unless the WREN bit is set. The WREN bit must be set on a previous instruction. Both WR and WREN cannot be set with the same instruction.

At the completion of the write cycle, the WR bit is cleared in hardware and the EEPROM Write Complete Interrupt Flag bit (EEIF) is set. The user may either enable this interrupt, or poll this bit. EEIF must be cleared by software.

## **EXAMPLE 6-2: DATA EEPROM WRITE**

```
MOVLW DATA EE ADDR
         MOVWF EEADR
                              ; Data Memory Address to read
         MOVLW DATA_EE_DATA ;
         MOVWF EEDATA
                            ; Data Memory Value to write
          BCF
                EECON1, EEPGD ; Point to DATA memory
                EECON1, CFGS ; Access program FLASH or Data EEPROM memory
          BCF
                EECON1, WREN ; Enable writes
          BSF
         BCF
                INTCON, GIE ; Disable interrupts
                55h ;
Required
         MOVLW
Sequence
         MOVWF
                EECON2 ; Write 55h
                EECON2 ;
          MOVLW
                              ; Write AAh
          MOVWF
                EECON1, WR ; Set WR bit to begin write
          BSF
          BSF
                INTCON, GIE
                              ; Enable interrupts
                              ; user code execution
          BCF
                EECON1, WREN
                              ; Disable writes on write complete (EEIF set)
```

## 6.5 Write Verify

Depending on the application, good programming practice may dictate that the value written to the memory should be verified against the original value. This should be used in applications where excessive writes can stress bits near the specification limit.

## 6.6 Protection Against Spurious Write

There are conditions when the device may not want to write to the data EEPROM memory. To protect against spurious EEPROM writes, various mechanisms have been built-in. On power-up, the WREN bit is cleared. Also, the Power-up Timer (72 ms duration) prevents EEPROM write.

The write initiate sequence and the WREN bit together help prevent an accidental write during brown-out, power glitch, or software malfunction.

## 6.7 Operation During Code Protect

Data EEPROM memory has its own code protect mechanism. External Read and Write operations are disabled if either of these mechanisms are enabled.

The microcontroller itself can both read and write to the internal Data EEPROM, regardless of the state of the code protect configuration bit. Refer to "Special Features of the CPU" (Section 19.0) for additional information.

## 6.8 Using the Data EEPROM

The data EEPROM is a high endurance, byte addressable array that has been optimized for the storage of frequently changing information (e.g., program variables or other data that are updated often). Frequently changing values will typically be updated more often than specification D124. If this is not the case, an array refresh must be performed. For this reason, variables that change infrequently (such as constants, IDs, calibration, etc.) should be stored in FLASH program memory.

A simple data EEPROM refresh routine is shown in Example 6-3.

**Note:** If data EEPROM is only used to store constants and/or data that changes rarely, an array refresh is likely not required. See specification D124.

### EXAMPLE 6-3: DATA EEPROM REFRESH ROUTINE

```
clrf
               EEADR
                                      ; Start at address 0
       bcf
               EECON1, CFGS
                                      ; Set for memory
       bcf
               EECON1, EEPGD
                                      ; Set for Data EEPROM
               INTCON, GIE
       bcf
                                      : Disable interrupts
       bsf
               EECON1, WREN
                                      ; Enable writes
door
                                      ; Loop to refresh array
               EECON1, RD
       bsf
                                      ; Read current address
               55h
       mowlw
                                      ; Write 55h
       movwf
               EECON2
       movlw
              AAh
               EECON2
                                      ; Write AAh
       movwf
       bsf
               EECON1,WR
                                      ; Set WR bit to begin write
              EECON1,WR
       btfsc
                                      ; Wait for write to complete
       bra
               $-2
       incfsz EEADR, F
                                      ; Increment address
                                      ; Not zero, do it again
       bra
               Loop
       bcf
               EECON1, WREN
                                      ; Disable writes
               INTCON, GIE
                                      ; Enable interrupts
       bsf
```

TABLE 6-1: REGISTERS ASSOCIATED WITH DATA EEPROM MEMORY

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on All Other RESETS
FF2h	INTCON	GIE/ GIEH	PEIE/ GIEL	T01E	INTE	RBIE	T01F	INTF	RBIF	0000 000x	0000 000u
FA9h	EEADR	EEPROM	1 Address		0000 0000	0000 0000					
FA8h	EEDATA	EEPROM	1 Data Reg		0000 0000	0000 0000					
FA7h	EECON2	EEPROM	1 Control F		_	_					
FA6h	EECON1	EEPGD	EEPGD CFGS - FREE WRERR WREN WR RD							xx-0 x000	uu-0 u000
FA2h	IPR2	_	EEIP BCLIP LVDIP TMR3IP CCP2IP								1 1111
FA1h	PIR2	_	_	_	EEIF	BCLIF	LVDIF	TMR3IF	CCP2IF	0 0000	0 0000
FA0h	PIE2	_	_	_	EEIE	BCLIE	LVDIE	TMR3IE	CCP2IE	0 0000	0 0000

 $\label{eq:local_local_local_local} \begin{tabular}{ll} $\mathbf{x}$ = unknown, $\mathbf{u}$ = unchanged, $\mathbf{r}$ = reserved, $\mathbf{-}$ = unimplemented, read as '0'. \\ $\text{Shaded cells are not used during FLASH/EEPROM access.} \end{tabular}$ 

## PIC18FXX2

**NOTES:** 

## 7.0 8 X 8 HARDWARE MULTIPLIER

## 7.1 Introduction

An 8 x 8 hardware multiplier is included in the ALU of the PIC18FXX2 devices. By making the multiply a hardware operation, it completes in a single instruction cycle. This is an unsigned multiply that gives a 16-bit result. The result is stored into the 16-bit product register pair (PRODH:PRODL). The multiplier does not affect any flags in the ALUSTA register.

Making the 8 x 8 multiplier execute in a single cycle gives the following advantages:

- · Higher computational throughput
- Reduces code size requirements for multiply algorithms

The performance increase allows the device to be used in applications previously reserved for Digital Signal Processors.

Table 7-1 shows a performance comparison between enhanced devices using the single cycle hardware multiply, and performing the same function without the hardware multiply.

TABLE 7-1: PERFORMANCE COMPARISON

		Program Memory (Words)  Cycles (Max)		Time			
Routine	Multiply Method			@ 40 MHz	@ 10 MHz	@ 4 MHz	
0 v 0 unaigned	Without hardware multiply	13	69	6.9 µs	27.6 μs	69 μs	
8 x 8 unsigned	Hardware multiply	1	1	100 ns	400 ns	1 μs	
0 0	Without hardware multiply	33	91	9.1 μs	36.4 μs	91 μs	
8 x 8 signed	Hardware multiply	6	6	600 ns	2.4 μs	6 μs	
16 v 16 uppigned	Without hardware multiply	21	242	24.2 μs	96.8 μs	242 μs	
16 x 16 unsigned	Hardware multiply	24	24	2.4 μs	9.6 μs	24 μs	
16 x 16 signed	Without hardware multiply	52	254	25.4 μs	102.6 μs	254 μs	
	Hardware multiply	36	36	3.6 µs	14.4 μs	<b>3</b> 6 μs	

## 7.2 Operation

Example 7-1 shows the sequence to do an 8 x 8 unsigned multiply. Only one instruction is required when one argument of the multiply is already loaded in the WREG register.

Example 7-2 shows the sequence to do an 8 x 8 signed multiply. To account for the sign bits of the arguments, each argument's Most Significant bit (MSb) is tested and the appropriate subtractions are done.

## EXAMPLE 7-1: 8 x 8 UNSIGNED MULTIPLY ROUTINE

MOVF	ARG1,	W	;
MULWF	ARG2		; ARG1 * ARG2 ->
			; PRODH:PRODL

## EXAMPLE 7-2: 8 x 8 SIGNED MULTIPLY ROUTINE

MOVF	ARG1,	W	
MULWF	ARG2		; ARG1 * ARG2 ->
			; PRODH:PRODL
BTFSC	ARG2,	SB	; Test Sign Bit
SUBWF	PRODH,	F	; PRODH = PRODH
			; - ARG1
MOVF	ARG2,	M	
BTFSC	ARG1,	SB	; Test Sign Bit
SUBWF	PRODH,	F	; PRODH = PRODH
			; - ARG2

Example 7-3 shows the sequence to do a 16  $\times$  16 unsigned multiply. Equation 7-1 shows the algorithm that is used. The 32-bit result is stored in four registers, RES3:RES0.

# EQUATION 7-1: 16 x 16 UNSIGNED MULTIPLICATION ALGORITHM

```
RES3:RES0 = ARG1H:ARG1L \bullet ARG2H:ARG2L

= (ARG1H \bullet ARG2H \bullet 2<sup>16</sup>) +

(ARG1H \bullet ARG2L \bullet 2<sup>8</sup>) +

(ARG1L \bullet ARG2H \bullet 2<sup>8</sup>) +

(ARG1L \bullet ARG2L)
```

## EXAMPLE 7-3: 16 x 16 UNSIGNED MULTIPLY ROUTINE

```
ARG1L, W
MOVF
MULWF
       ARG2L
                   ; ARG1L * ARG2L ->
                   ; PRODH:PRODL
      PRODH, RES1 ;
MOVFF
MOVFF
      PRODL, RESO ;
MOVF
      ARG1H, W
                   ; ARG1H * ARG2H ->
{\tt MULWF}
      ARG2H
                  ; PRODH:PRODL
MOVFF
      PRODH, RES3 ;
MOVFF
      PRODL, RES2 ;
      ARG1L. W
MOVF
MULWF ARG2H
                  ; ARG1L * ARG2H ->
                  ; PRODH:PRODL
MOVF
       PRODL, W ;
ADDWF
      RES1, F ; Add cross
      PRODH, W ; products
MOVF
ADDWFC RES2, F
CLRF
       WREG
                  ;
ADDWFC RES3, F
                   ;
MOVF
      ARG1H, W
                   ; ARG1H * ARG2L ->
      ARG2L
MULWF
                  ; PRODH:PRODL
MOVF
      PRODL, W
      RES1, F
ADDWF
                 ; Add cross
MOVF
      PRODH, W ; products
ADDWFC RES2, F
CLRF
      WREG
ADDWFC RES3, F
```

Example 7-4 shows the sequence to do a 16 x 16 signed multiply. Equation 7-2 shows the algorithm used. The 32-bit result is stored in four registers, RES3:RES0. To account for the sign bits of the arguments, each argument pairs Most Significant bit (MSb) is tested and the appropriate subtractions are done.

# EQUATION 7-2: 16 x 16 SIGNED MULTIPLICATION ALGORITHM

```
RES3:RES0

= ARG1H:ARG1L • ARG2H:ARG2L

= (ARG1H • ARG2H • 2<sup>16</sup>) +
(ARG1H • ARG2L • 2<sup>8</sup>) +
(ARG1L • ARG2H • 2<sup>8</sup>) +
(ARG1L • ARG2L) +
(-1 • ARG2H<7> • ARG1H:ARG1L • 2<sup>16</sup>) +
(-1 • ARG1H<7> • ARG2H:ARG2L • 2<sup>16</sup>)
```

## EXAMPLE 7-4: 16 x 16 SIGNED MULTIPLY ROUTINE

```
ARG1L, W
   MOVF
   MULWF
          ARG2L
                      ; ARG1L * ARG2L ->
                      ; PRODH: PRODL
          PRODH, RES1 ;
   MOVEE
   MOVFF
          PRODL, RESO ;
   MOVF
          ARG1H, W
                      ; ARG1H * ARG2H ->
   MULWF
          ARG2H
                      ; PRODH: PRODL
   MOVFF
          PRODH, RES3 ;
   MOVFF
          PRODL, RES2 ;
          ARG1L, W
   MOVF
         ARG2H
                      ; ARG1L * ARG2H ->
   MULWF
                      ; PRODH: PRODL
   MOVF
          PRODL, W
   ADDWF
          RES1, F ; Add cross
          PRODH, W ; products
   MOVF
   ADDWFC RES2, F
   CLRF
          WREG
   ADDWFC RES3, F
   MOVF
          ARG1H, W
         ARG2L
                      ; ARG1H * ARG2L ->
   MULWF
                      ; PRODH:PRODL
   MOVF
          PRODL, W
          RES1, F ; Add cross
   ADDWF
                      ; products
   MOVE
          PRODH, W
   ADDWFC RES2, F
   CLRF
          WREG
   ADDWFC RES3, F
   BTFSS ARG2H, 7
                      ; ARG2H:ARG2L neg?
          SIGN ARG1
                      ; no, check ARG1
   BRA
   MOVE
          ARG1L, W
   SUBWF RES2
   MOVF
          ARG1H, W
   SUBWFB RES3
SIGN ARG1
   BTFSS
          ARG1H, 7
                      ; ARG1H:ARG1L neg?
          CONT_CODE
   BRA
                      ; no, done
          ARG2L, W
   MOVF
   SUBWF
          RES2
          ARG2H, W
   MOVF
   SUBWFB RES3
CONT_CODE
    :
```

## 8.0 INTERRUPTS

The PIC18FXX2 devices have multiple interrupt sources and an interrupt priority feature that allows each interrupt source to be assigned a high priority level or a low priority level. The high priority interrupt vector is at 000008h and the low priority interrupt vector is at 000018h. High priority interrupt events will override any low priority interrupts that may be in progress.

There are ten registers which are used to control interrupt operation. These registers are:

- RCON
- INTCON
- INTCON2
- INTCON3
- PIR1, PIR2
- PIE1, PIE2
- · IPR1, IPR2

It is recommended that the Microchip header files supplied with MPLAB® IDE be used for the symbolic bit names in these registers. This allows the assembler/compiler to automatically take care of the placement of these bits within the specified register.

Each interrupt source, except INTO, has three bits to control its operation. The functions of these bits are:

- Flag bit to indicate that an interrupt event occurred
- Enable bit that allows program execution to branch to the interrupt vector address when the flag bit is set
- · Priority bit to select high priority or low priority

The interrupt priority feature is enabled by setting the IPEN bit (RCON<7>). When interrupt priority is enabled, there are two bits which enable interrupts globally. Setting the GIEH bit (INTCON<7>) enables all interrupts that have the priority bit set. Setting the GIEL bit (INTCON<6>) enables all interrupts that have the priority bit cleared. When the interrupt flag, enable bit and appropriate global interrupt enable bit are set, the interrupt will vector immediately to address 000008h or 000018h, depending on the priority level. Individual interrupts can be disabled through their corresponding enable bits.

When the IPEN bit is cleared (default state), the interrupt priority feature is disabled and interrupts are compatible with PICmicro® mid-range devices. In Compatibility mode, the interrupt priority bits for each source have no effect. INTCON<6> is the PEIE bit, which enables/disables all peripheral interrupt sources. INTCON<7> is the GIE bit, which enables/disables all interrupt sources. All interrupts branch to address 000008h in Compatibility mode.

When an interrupt is responded to, the Global Interrupt Enable bit is cleared to disable further interrupts. If the IPEN bit is cleared, this is the GIE bit. If interrupt priority levels are used, this will be either the GIEH or GIEL bit. High priority interrupt sources can interrupt a low priority interrupt.

The return address is pushed onto the stack and the PC is loaded with the interrupt vector address (000008h or 000018h). Once in the Interrupt Service Routine, the source(s) of the interrupt can be determined by polling the interrupt flag bits. The interrupt flag bits must be cleared in software before re-enabling interrupts to avoid recursive interrupts.


The "return from interrupt" instruction, RETFIE, exits the interrupt routine and sets the GIE bit (GIEH or GIEL if priority levels are used), which re-enables interrupts.

For external interrupt events, such as the INT pins or the PORTB input change interrupt, the interrupt latency will be three to four instruction cycles. The exact latency is the same for one or two-cycle instructions. Individual interrupt flag bits are set, regardless of the status of their corresponding enable bit or the GIE bit.

Note:

Do not use the MOVFF instruction to modify any of the Interrupt control registers while **any** interrupt is enabled. Doing so may cause erratic microcontroller behavior.

FIGURE 8-1: INTERRUPT LOGIC



## 8.1 INTCON Registers

The INTCON Registers are readable and writable registers, which contain various enable, priority and flag bits.

Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling.

### **REGISTER 8-1: INTCON REGISTER**

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-x
GIE/GIEH	PEIE/GIEL	TMR0IE	INT01E	RBIE	TMR0IF	INT0IF	RBIF
bit 7							bit 0

Note:

bit 7 GIE/GIEH: Global Interrupt Enable bit

## When IPEN = 0:

- 1 = Enables all unmasked interrupts
- 0 = Disables all interrupts

## When IPEN = 1:

- 1 = Enables all high priority interrupts
- 0 = Disables all interrupts
- bit 6 PEIE/GIEL: Peripheral Interrupt Enable bit

## When IPEN = 0:

- 1 = Enables all unmasked peripheral interrupts
- 0 = Disables all peripheral interrupts

### When IPEN = 1:

- 1 = Enables all low priority peripheral interrupts
- 0 = Disables all low priority peripheral interrupts
- bit 5 TMR0IE: TMR0 Overflow Interrupt Enable bit
  - 1 = Enables the TMR0 overflow interrupt
  - 0 = Disables the TMR0 overflow interrupt
- bit 4 INTOIE: INTO External Interrupt Enable bit
  - 1 = Enables the INT0 external interrupt
  - 0 = Disables the INT0 external interrupt
- bit 3 RBIE: RB Port Change Interrupt Enable bit
  - 1 = Enables the RB port change interrupt
  - 0 = Disables the RB port change interrupt
- bit 2 TMR0IF: TMR0 Overflow Interrupt Flag bit
  - 1 = TMR0 register has overflowed (must be cleared in software)
  - 0 = TMR0 register did not overflow
- bit 1 INT0IF: INT0 External Interrupt Flag bit
  - 1 = The INT0 external interrupt occurred (must be cleared in software)
  - 0 = The INT0 external interrupt did not occur
- bit 0 RBIF: RB Port Change Interrupt Flag bit
  - 1 = At least one of the RB7:RB4 pins changed state (must be cleared in software)
  - 0 = None of the RB7:RB4 pins have changed state

**Note:** A mismatch condition will continue to set this bit. Reading PORTB will end the mismatch condition and allow the bit to be cleared.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

### REGISTER 8-2: INTCON2 REGISTER

R/W-1	R/W-1	R/W-1	R/W-1	U-0	R/W-1	U-0	R/W-1
RBPU	INTEDG0	INTEDG1	INTEDG2	_	TMR0IP	_	RBIP
bit 7							hit ()

bit 7 RBPU: PORTB Pull-up Enable bit

1 = All PORTB pull-ups are disabled

0 = PORTB pull-ups are enabled by individual port latch values

bit 6 INTEDG0:External Interrupt0 Edge Select bit

1 = Interrupt on rising edge

0 = Interrupt on falling edge

bit 5 INTEDG1: External Interrupt1 Edge Select bit

1 = Interrupt on rising edge

0 = Interrupt on falling edge

bit 4 INTEDG2: External Interrupt2 Edge Select bit

1 = Interrupt on rising edge

0 = Interrupt on falling edge

bit 3 Unimplemented: Read as '0'

bit 2 TMR0IP: TMR0 Overflow Interrupt Priority bit

1 = High priority

0 = Low priority

bit 1 Unimplemented: Read as '0'

bit 0 RBIP: RB Port Change Interrupt Priority bit

1 = High priority

0 = Low priority

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' - n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

Note: Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling.

## **REGISTER 8-3: INTCON3 REGISTER**

bit 7							bit 0
INT2IP	INT1IP	_	INT2IE	INT1IE		INT2IF	INT1IF
R/W-1	R/W-1	U-0	R/W-0	R/W-0	U-0	R/W-0	R/W-0

bit 7 INT2IP: INT2 External Interrupt Priority bit

1 = High priority

0 = Low priority

bit 6 INT1IP: INT1 External Interrupt Priority bit

1 = High priority

0 = Low priority

bit 5 Unimplemented: Read as '0'

bit 4 INT2IE: INT2 External Interrupt Enable bit

1 = Enables the INT2 external interrupt

0 = Disables the INT2 external interrupt

bit 3 INT1IE: INT1 External Interrupt Enable bit

1 = Enables the INT1 external interrupt

0 = Disables the INT1 external interrupt

bit 2 Unimplemented: Read as '0'

bit 1 INT2IF: INT2 External Interrupt Flag bit

1 = The INT2 external interrupt occurred (must be cleared in software)

0 = The INT2 external interrupt did not occur

bit 0 INT1IF: INT1 External Interrupt Flag bit

1 = The INT1 external interrupt occurred (must be cleared in software)

0 = The INT1 external interrupt did not occur

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' - n = Value at POR '1' = Bit is set '0' = Bit is cleared X = Bit is unknown

**Note:** Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling.

## 8.2 PIR Registers

The PIR registers contain the individual flag bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are two Peripheral Interrupt Flag Registers (PIR1, PIR2).

- Note 1: Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global enable bit, GIE (INTCON<7>).
  - 2: User software should ensure the appropriate interrupt flag bits are cleared prior to enabling an interrupt, and after servicing that interrupt.

## REGISTER 8-4: PIR1: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 1

R/W-0	R/W-0	R-0	R-0	R/W-0	R/W-0	R/W-0	R/W-0
PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF
bit 7				•	•		bit 0

- bit 7 **PSPIF**<sup>(1)</sup>: Parallel Slave Port Read/Write Interrupt Flag bit
  - 1 = A read or a write operation has taken place (must be cleared in software)
  - 0 = No read or write has occurred
- bit 6 ADIF: A/D Converter Interrupt Flag bit
  - 1 = An A/D conversion completed (must be cleared in software)
  - 0 = The A/D conversion is not complete
- bit 5 RCIF: USART Receive Interrupt Flag bit
  - 1 = The USART receive buffer, RCREG, is full (cleared when RCREG is read)
  - 0 = The USART receive buffer is empty
- bit 4 TXIF: USART Transmit Interrupt Flag bit (see Section 16.0 for details on TXIF functionality)
  - 1 = The USART transmit buffer, TXREG, is empty (cleared when TXREG is written)
  - 0 = The USART transmit buffer is full
- bit 3 SSPIF: Master Synchronous Serial Port Interrupt Flag bit
  - 1 = The transmission/reception is complete (must be cleared in software)
  - 0 = Waiting to transmit/receive
- bit 2 CCP1IF: CCP1 Interrupt Flag bit

### Capture mode:

- 1 = A TMR1 register capture occurred (must be cleared in software)
- 0 = No TMR1 register capture occurred

### Compare mode:

- 1 = A TMR1 register compare match occurred (must be cleared in software)
- 0 = No TMR1 register compare match occurred

## PWM mode:

Unused in this mode

- bit 1 TMR2IF: TMR2 to PR2 Match Interrupt Flag bit
  - 1 = TMR2 to PR2 match occurred (must be cleared in software)
  - 0 = No TMR2 to PR2 match occurred
- bit 0 TMR1IF: TMR1 Overflow Interrupt Flag bit
  - 1 = TMR1 register overflowed (must be cleared in software)
  - 0 = MR1 register did not overflow

Note 1: This bit is reserved on PIC18F2X2 devices; always maintain this bit clear.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit,	read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

## REGISTER 8-5: PIR2: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 2

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	_	_	EEIF	BCLIF	LVDIF	TMR3IF	CCP2IF
bit 7							bit 0

bit 7-5 **Unimplemented:** Read as '0'

bit 4 **EEIF**: Data EEPROM/FLASH Write Operation Interrupt Flag bit

1 =The Write operation is complete (must be cleared in software)

0 = The Write operation is not complete, or has not been started

bit 3 BCLIF: Bus Collision Interrupt Flag bit

1 = A bus collision occurred (must be cleared in software)

0 = No bus collision occurred

bit 2 LVDIF: Low Voltage Detect Interrupt Flag bit

1 = A low voltage condition occurred (must be cleared in software)

0 = The device voltage is above the Low Voltage Detect trip point

bit 1 TMR3IF: TMR3 Overflow Interrupt Flag bit

1 = TMR3 register overflowed (must be cleared in software)

0 = TMR3 register did not overflow

bit 0 CCP2IF: CCPx Interrupt Flag bit

Capture mode:

1 = A TMR1 register capture occurred (must be cleared in software)

0 = No TMR1 register capture occurred

Compare mode:

1 = A TMR1 register compare match occurred (must be cleared in software)

0 = No TMR1 register compare match occurred

PWM mode:

Unused in this mode

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

- n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 8.3 PIE Registers

The PIE registers contain the individual enable bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are two Peripheral Interrupt Enable Registers (PIE1, PIE2). When IPEN = 0, the PEIE bit must be set to enable any of these peripheral interrupts.

## REGISTER 8-6: PIE1: PERIPHERAL INTERRUPT ENABLE REGISTER 1

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE
bit 7							bit 0

	bit 7
bit 7	PSPIE <sup>(1)</sup> : Parallel Slave Port Read/Write Interrupt Enable bit  1 = Enables the PSP read/write interrupt  0 = Disables the PSP read/write interrupt
bit 6	ADIE: A/D Converter Interrupt Enable bit  1 = Enables the A/D interrupt  0 = Disables the A/D interrupt
bit 5	RCIE: USART Receive Interrupt Enable bit  1 = Enables the USART receive interrupt  0 = Disables the USART receive interrupt
bit 4	TXIE: USART Transmit Interrupt Enable bit  1 = Enables the USART transmit interrupt  0 = Disables the USART transmit interrupt
bit 3	SSPIE: Master Synchronous Serial Port Interrupt Enable bit  1 = Enables the MSSP interrupt  0 = Disables the MSSP interrupt
bit 2	CCP1IE: CCP1 Interrupt Enable bit  1 = Enables the CCP1 interrupt  0 = Disables the CCP1 interrupt
bit 1	TMR2IE: TMR2 to PR2 Match Interrupt Enable bit  1 = Enables the TMR2 to PR2 match interrupt  0 = Disables the TMR2 to PR2 match interrupt
bit 0	TMR1IE: TMR1 Overflow Interrupt Enable bit  1 = Enables the TMR1 overflow interrupt  0 = Disables the TMR1 overflow interrupt

Note 1: This bit is reserved on PIC18F2X2 devices; always maintain this bit clear.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	l bit, read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

## REGISTER 8-7: PIE2: PERIPHERAL INTERRUPT ENABLE REGISTER 2

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_			EEIE	BCLIE	LVDIE	TMR3IE	CCP2IE
bit 7							bit 0

bit 7-5 Unimplemented: Read as '0'

bit 4 **EEIE**: Data EEPROM/FLASH Write Operation Interrupt Enable bit

1 = Enabled 0 = Disabled

bit 3 BCLIE: Bus Collision Interrupt Enable bit

1 = Enabled 0 = Disabled

bit 2 LVDIE: Low Voltage Detect Interrupt Enable bit

1 = Enabled 0 = Disabled

bit 1 TMR3IE: TMR3 Overflow Interrupt Enable bit

1 = Enables the TMR3 overflow interrupt0 = Disables the TMR3 overflow interrupt

bit 0 CCP2IE: CCP2 Interrupt Enable bit

1 = Enables the CCP2 interrupt0 = Disables the CCP2 interrupt

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
- n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 8.4 IPR Registers

The IPR registers contain the individual priority bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are two Peripheral Interrupt Priority Registers (IPR1, IPR2). The operation of the priority bits requires that the Interrupt Priority Enable (IPEN) bit be set.

## REGISTER 8-8: IPR1: PERIPHERAL INTERRUPT PRIORITY REGISTER 1

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP
hit 7							hit 0

bit 7 **PSPIP**<sup>(1)</sup>: Parallel Slave Port Read/Write Interrupt Priority bit 1 = High priority 0 = Low priority ADIP: A/D Converter Interrupt Priority bit bit 6 1 = High priority 0 = Low priority bit 5 RCIP: USART Receive Interrupt Priority bit 1 = High priority 0 = Low priority bit 4 TXIP: USART Transmit Interrupt Priority bit 1 = High priority 0 = Low priority SSPIP: Master Synchronous Serial Port Interrupt Priority bit bit 3 1 = High priority 0 = Low priority CCP1IP: CCP1 Interrupt Priority bit bit 2 1 = High priority 0 = Low priority

bit 1 TMR2IP: TMR2 to PR2 Match Interrupt Priority bit

1 = High priority0 = Low priority

bit 0 TMR1IP: TMR1 Overflow Interrupt Priority bit

1 = High priority0 = Low priority

Note 1: This bit is reserved on PIC18F2X2 devices; always maintain this bit set.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

## REGISTER 8-9: IPR2: PERIPHERAL INTERRUPT PRIORITY REGISTER 2

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
_			EEIP	BCLIP	LVDIP	TMR3IP	CCP2IP
bit 7							bit 0

bit 7-5 Unimplemented: Read as '0'

bit 4 **EEIP**: Data EEPROM/FLASH Write Operation Interrupt Priority bit

1 = High priority0 = Low priority

bit 3 BCLIP: Bus Collision Interrupt Priority bit

1 = High priority0 = Low priority

bit 2 LVDIP: Low Voltage Detect Interrupt Priority bit

1 = High priority0 = Low priority

bit 1 TMR3IP: TMR3 Overflow Interrupt Priority bit

1 = High priority0 = Low priority

bit 0 CCP2IP: CCP2 Interrupt Priority bit

1 = High priority0 = Low priority

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

- n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 8.5 RCON Register

The RCON register contains the bit which is used to enable prioritized interrupts (IPEN).

### REGISTER 8-10: RCON REGISTER

R/W-0	U-0	U-0	R/W-1	R-1	R-1	R/W-0	R/W-0
IPEN	_	_	RI	TO	PD	POR	BOR
bit 7							bit 0

bit 7 IPEN: Interrupt Priority Enable bit

1 = Enable priority levels on interrupts

0 = Disable priority levels on interrupts (16CXXX Compatibility mode)

bit 6-5 Unimplemented: Read as '0'

bit 4 RI: RESET Instruction Flag bit

For details of bit operation, see Register 4-3

bit 3 TO: Watchdog Time-out Flag bit

For details of bit operation, see Register 4-3

bit 2 PD: Power-down Detection Flag bit

For details of bit operation, see Register 4-3

bit 1 POR: Power-on Reset Status bit

For details of bit operation, see Register 4-3

bit 0 BOR: Brown-out Reset Status bit

For details of bit operation, see Register 4-3

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

- n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 8.6 INT0 Interrupt

External interrupts on the RB0/INT0, RB1/INT1 and RB2/INT2 pins are edge triggered: either rising, if the corresponding INTEDGx bit is set in the INTCON2 register, or falling, if the INTEDGx bit is clear. When a valid edge appears on the RBx/INTx pin, the corresponding flag bit INTxF is set. This interrupt can be disabled by clearing the corresponding enable bit INTxE. Flag bit INTxF must be cleared in software in the Interrupt Service Routine before re-enabling the interrupt. All external interrupts (INT0, INT1 and INT2) can wake-up the processor from SLEEP, if bit INTxE was set prior to going into SLEEP. If the global interrupt enable bit GIE is set, the processor will branch to the interrupt vector following wake-up.

Interrupt priority for INT1 and INT2 is determined by the value contained in the interrupt priority bits, INT1IP (INTCON3<6>) and INT2IP (INTCON3<7>). There is no priority bit associated with INT0. It is always a high priority interrupt source.

## 8.7 TMR0 Interrupt

In 8-bit mode (which is the default), an overflow (FFh  $\rightarrow$  00h) in the TMR0 register will set flag bit TMR0IF. In 16-bit mode, an overflow (FFFh  $\rightarrow$  0000h) in the TMR0H:TMR0L registers will set flag bit TMR0IF. The interrupt can be enabled/disabled by setting/clearing enable bit T0IE (INTCON<5>). Interrupt priority for Timer0 is determined by the value contained in the interrupt priority bit TMR0IP (INTCON2<2>). See Section 10.0 for further details on the Timer0 module.

## 8.8 PORTB Interrupt-on-Change

An input change on PORTB<7:4> sets flag bit RBIF (INTCON<0>). The interrupt can be enabled/disabled by setting/clearing enable bit, RBIE (INTCON<3>). Interrupt priority for PORTB interrupt-on-change is determined by the value contained in the interrupt priority bit, RBIP (INTCON2<0>).

## 8.9 Context Saving During Interrupts

During an interrupt, the return PC value is saved on the stack. Additionally, the WREG, STATUS and BSR registers are saved on the fast return stack. If a fast return from interrupt is not used (See Section 4.3), the user may need to save the WREG, STATUS and BSR registers in software. Depending on the user's application, other registers may also need to be saved. Equation 8-1 saves and restores the WREG, STATUS and BSR registers during an Interrupt Service Routine.

## **EXAMPLE 8-1:** SAVING STATUS, WREG AND BSR REGISTERS IN RAM

```
MOVWF
       W TEMP
                                           ; W TEMP is in virtual bank
       STATUS, STATUS_TEMP
MOVFF
                                           ; STATUS TEMP located anywhere
MOVEE
               BSR_TEMP
       BSR,
                                           ; BSR located anywhere
; USER ISR CODE
MOVFF
       BSR TEMP,
                   BSR
                                           ; Restore BSR
                                           ; Restore WREG
MOVE
        W TEMP,
                   W
MOVFF
       STATUS TEMP, STATUS
                                           ; Restore STATUS
```

**NOTES:** 

#### 9.0 I/O PORTS

Depending on the device selected, there are either five ports or three ports available. Some pins of the I/O ports are multiplexed with an alternate function from the peripheral features on the device. In general, when a peripheral is enabled, that pin may not be used as a general purpose I/O pin.

Each port has three registers for its operation. These registers are:

- TRIS register (data direction register)
- · PORT register (reads the levels on the pins of the device)
- LAT register (output latch)

The data latch (LAT register) is useful for read-modifywrite operations on the value that the I/O pins are driving.

### 9.1 PORTA, TRISA and LATA Registers

PORTA is a 7-bit wide, bi-directional port. The corresponding Data Direction register is TRISA. Setting a TRISA bit (= 1) will make the corresponding PORTA pin an input (i.e., put the corresponding output driver in a Hi-Impedance mode). Clearing a TRISA bit (= 0) will make the corresponding PORTA pin an output (i.e., put the contents of the output latch on the selected pin).

Reading the PORTA register reads the status of the pins, whereas writing to it will write to the port latch.

The Data Latch register (LATA) is also memory mapped. Read-modify-write operations on the LATA register reads and writes the latched output value for PORTA.

The RA4 pin is multiplexed with the Timer0 module clock input to become the RA4/T0CKI pin. The RA4/ T0CKI pin is a Schmitt Trigger input and an open drain output. All other RA port pins have TTL input levels and full CMOS output drivers.

The other PORTA pins are multiplexed with analog inputs and the analog VREF+ and VREF- inputs. The operation of each pin is selected by clearing/setting the control bits in the ADCON1 register (A/D Control Register1).


On a Power-on Reset, RA5 and RA3:RA0 are configured as analog inputs and read as '0'. RA6 and RA4 are configured as digital inputs.

The TRISA register controls the direction of the RA pins, even when they are being used as analog inputs. The user must ensure the bits in the TRISA register are maintained set when using them as analog inputs.

#### **EXAMPLE 9-1:** INITIALIZING PORTA

CLRF PORTA	; Initialize PORTA by ; clearing output
CLRF LATA	; data latches : Alternate method
CLRF LAIA	; Alternate method
	; to clear output
	; data latches
MOVLW 0x07	; Configure A/D
MOVWF ADCON1	; for digital inputs
MOVLW 0xCF	; Value used to
	; initialize data
	; direction
MOVWF TRISA	; Set RA<3:0> as inputs
	; RA<5:4> as outputs

#### FIGURE 9-1: **BLOCK DIAGRAM OF RA3:RA0 AND RA5 PINS**



Note 1: I/O pins have protection diodes to VDD and Vss.

FIGURE 9-2: BLOCK DIAGRAM OF RA4/TOCKI PIN




FIGURE 9-3: BLOCK DIAGRAM OF RA6 PIN




TABLE 9-1: PORTA FUNCTIONS

Name	Bit#	Buffer	Function
RA0/AN0	bit0	TTL	Input/output or analog input.
RA1/AN1	bit1	TTL	Input/output or analog input.
RA2/AN2/VREF-	bit2	TTL	Input/output or analog input or VREF
RA3/AN3/VREF+	bit3	TTL	Input/output or analog input or VREF+.
RA4/T0CKI	bit4	ST	Input/output or external clock input for Timer0. Output is open drain type.
RA5/SS/AN4/LVDIN	bit5	TTL	Input/output or slave select input for synchronous serial port or analog input, or low voltage detect input.
OSC2/CLKO/RA6	bit6	TTL	OSC2 or clock output or I/O pin.

Legend: TTL = TTL input, ST = Schmitt Trigger input

TABLE 9-2: SUMMARY OF REGISTERS ASSOCIATED WITH PORTA

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
PORTA	_	RA6	RA5	RA4	RA3	RA2	RA1	RA0	-x0x 0000	-u0u 0000
LATA	_	LATA Dat	a Output F	Register					-xxx xxxx	-uuu uuuu
TRISA	_	PORTA D	PRTA Data Direction Register							-111 1111
ADCON1	ADFM	ADCS2	_	_	PCFG3	PCFG2	PCFG1	PCFG0	00 0000	00 0000

Legend: x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by PORTA.

## 9.2 PORTB, TRISB and LATB Registers

PORTB is an 8-bit wide, bi-directional port. The corresponding Data Direction register is TRISB. Setting a TRISB bit (= 1) will make the corresponding PORTB pin an input (i.e., put the corresponding output driver in a Hi-Impedance mode). Clearing a TRISB bit (= 0) will make the corresponding PORTB pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATB) is also memory mapped. Read-modify-write operations on the LATB register reads and writes the latched output value for PORTB.

### **EXAMPLE 9-2: INITIALIZING PORTB**

_/\/\		INTIALIZATORI D
CLRF	PORTB	; Initialize PORTB by
		; clearing output
		; data latches
CLRF	LATB	; Alternate method
		; to clear output
		; data latches
MOVLW	0xCF	; Value used to
		; initialize data
		; direction
MOVWF	TRISB	; Set RB<3:0> as inputs
		; RB<5:4> as outputs
		; RB<7:6> as inputs

Each of the PORTB pins has a weak internal pull-up. A single control bit can turn on all the pull-ups. This is performed by clearing bit  $\overline{\text{RBPU}}$  (INTCON2<7>). The weak pull-up is automatically turned off when the port pin is configured as an output. The pull-ups are disabled on a Power-on Reset.

**Note:** On a Power-on Reset, these pins are configured as digital inputs.

Four of the PORTB pins, RB7:RB4, have an interrupt-on-change feature. Only pins configured as inputs can cause this interrupt to occur (i.e., any RB7:RB4 pin configured as an output is excluded from the interrupt-on-change comparison). The input pins (of RB7:RB4) are compared with the old value latched on the last read of PORTB. The "mismatch" outputs of RB7:RB4 are OR'ed together to generate the RB Port Change Interrupt with flag bit, RBIF (INTCON<0>).

This interrupt can wake the device from SLEEP. The user, in the Interrupt Service Routine, can clear the interrupt in the following manner:


- Any read or write of PORTB (except with the MOVFF instruction). This will end the mismatch condition.
- b) Clear flag bit RBIF.

A mismatch condition will continue to set flag bit RBIF. Reading PORTB will end the mismatch condition and allow flag bit RBIF to be cleared.

The interrupt-on-change feature is recommended for wake-up on key depression operation and operations where PORTB is only used for the interrupt-on-change feature. Polling of PORTB is not recommended while using the interrupt-on-change feature.


RB3 can be configured by the configuration bit CCP2MX as the alternate peripheral pin for the CCP2 module (CCP2MX='0').

FIGURE 9-4: BLOCK DIAGRAM OF RB7:RB4 PINS



- Note 1: I/O pins have diode protection to VDD and Vss.
  - To enable weak pull-ups, set the appropriate TRIS bit(s) and clear the RBPU bit (INTCON2<7>).
- Note 1: While in Low Voltage ICSP mode, the RB5 pin can no longer be used as a general purpose I/O pin, and should be held low during normal operation to protect against inadvertent ICSP mode entry.
  - 2: When using Low Voltage ICSP programming (LVP), the pull-up on RB5 becomes disabled. If TRISB bit 5 is cleared, thereby setting RB5 as an output, LATB bit 5 must also be cleared for proper operation.

FIGURE 9-5: BLOCK DIAGRAM OF RB2:RB0 PINS



## FIGURE 9-6: BLOCK DIAGRAM OF RB3 PIN




TABLE 9-3: PORTB FUNCTIONS

Name	Bit#	Buffer	Function
RB0/INT0	bit0	TTL/ST <sup>(1)</sup>	Input/output pin or external interrupt input0. Internal software programmable weak pull-up.
RB1/INT1	bit1	TTL/ST <sup>(1)</sup>	Input/output pin or external interrupt input1. Internal software programmable weak pull-up.
RB2/INT2	bit2	TTL/ST <sup>(1)</sup>	Input/output pin or external interrupt input2. Internal software programmable weak pull-up.
RB3/CCP2 <sup>(3)</sup>	bit3	TTL/ST <sup>(4)</sup>	Input/output pin or Capture2 input/Compare2 output/PWM output when CCP2MX configuration bit is enabled. Internal software programmable weak pull-up.
RB4	bit4	TTL	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up.
RB5/PGM <sup>(5)</sup>	bit5	TTL/ST <sup>(2)</sup>	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Low voltage ICSP enable pin.
RB6/PGC	bit6	TTL/ST <sup>(2)</sup>	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Serial programming clock.
RB7/PGD	bit7	TTL/ST <sup>(2)</sup>	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Serial programming data.

Legend: TTL = TTL input, ST = Schmitt Trigger input

Note 1: This buffer is a Schmitt Trigger input when configured as the external interrupt.

- 2: This buffer is a Schmitt Trigger input when used in Serial Programming mode.
- 3: A device configuration bit selects which I/O pin the CCP2 pin is multiplexed on.
- 4: This buffer is a Schmitt Trigger input when configured as the CCP2 input.
- 5: Low Voltage ICSP Programming (LVP) is enabled by default, which disables the RB5 I/O function. LVP must be disabled to enable RB5 as an I/O pin and allow maximum compatibility to the other 28-pin and 40-pin mid-range devices.

TABLE 9-4: SUMMARY OF REGISTERS ASSOCIATED WITH PORTB

Name	Bit 7	Bit 6	Bit 5 Bit 4 Bit 3 Bit 2 Bit 1 Bit 0				Value on POR, BOR	Value on All Other RESETS		
PORTB	RB7	RB6	RB5	RB4	RB3	RB2	RB1	RB0	xxxx xxxx	uuuu uuuu
LATB	LATB Da	ata Output Re	egister						xxxx xxxx	uuuu uuuu
TRISB	PORTB	Data Direction	n Register						1111 1111	1111 1111
INTCON	GIE/ GIEH	5.2.						0000 000x	0000 000u	
INTCON2	RBPU	INTEDG0	INTEDG1	INTEDG2	_	TMR0IP	_	RBIP	1111 -1-1	1111 -1-1
INTCON3	INT2IP	INT1IP	_	INT2IE	INT1IE	_	INT2IF	INT1IF	11-0 0-00	11-0 0-00

Legend: x = unknown, u = unchanged. Shaded cells are not used by PORTB.

### 9.3 PORTC, TRISC and LATC Registers

PORTC is an 8-bit wide, bi-directional port. The corresponding Data Direction register is TRISC. Setting a TRISC bit (= 1) will make the corresponding PORTC pin an input (i.e., put the corresponding output driver in a Hi-Impedance mode). Clearing a TRISC bit (= 0) will make the corresponding PORTC pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATC) is also memory mapped. Read-modify-write operations on the LATC register reads and writes the latched output value for PORTC.

PORTC is multiplexed with several peripheral functions (Table 9-5). PORTC pins have Schmitt Trigger input buffers.

When enabling peripheral functions, care should be taken in defining TRIS bits for each PORTC pin. Some peripherals override the TRIS bit to make a pin an output, while other peripherals override the TRIS bit to make a pin an input. The user should refer to the corresponding peripheral section for the correct TRIS bit settings.

Note: On a Power-on Reset, these pins are configured as digital inputs.


The pin override value is not loaded into the TRIS register. This allows read-modify-write of the TRIS register. without concern due to peripheral overrides.

RC1 is normally configured by configuration bit. CCP2MX, as the default peripheral pin of the CCP2 module (default/erased state, CCP2MX = '1').

#### **EXAMPLE 9-3: INITIALIZING PORTC**

CLRF PORTC	; Initialize PORTC by
	; clearing output
	; data latches
CLRF LATC	; Alternate method
	; to clear output
	; data latches
MOVLW 0xCF	; Value used to
	; initialize data
	; direction
MOVWF TRISC	; Set RC<3:0> as inputs
	; RC<5:4> as outputs
	; RC<7:6> as inputs

#### FIGURE 9-7: PORTC BLOCK DIAGRAM (PERIPHERAL OUTPUT OVERRIDE)



2: Port/Peripheral Select signal selects between port data (input) and peripheral output.

3: Peripheral Output Enable is only active if peripheral select is active.

TABLE 9-5: PORTC FUNCTIONS

Name	Bit#	Buffer Type	Function
RC0/T1OSO/T1CKI	bit0	ST	Input/output port pin or Timer1 oscillator output/Timer1 clock input.
RC1/T1OSI/CCP2	bit1	ST	Input/output port pin, Timer1 oscillator input, or Capture2 input/ Compare2 output/PWM output when CCP2MX configuration bit is set.
RC2/CCP1	bit2	ST	Input/output port pin or Capture1 input/Compare1 output/PWM1 output.
RC3/SCK/SCL	bit3	ST	RC3 can also be the synchronous serial clock for both SPI and I <sup>2</sup> C modes.
RC4/SDI/SDA	bit4	ST	RC4 can also be the SPI Data In (SPI mode) or Data I/O (I <sup>2</sup> C mode).
RC5/SDO	bit5	ST	Input/output port pin or Synchronous Serial Port data output.
RC6/TX/CK	bit6	ST	Input/output port pin, Addressable USART Asynchronous Transmit, or Addressable USART Synchronous Clock.
RC7/RX/DT	bit7	ST	Input/output port pin, Addressable USART Asynchronous Receive, or Addressable USART Synchronous Data.

Legend: ST = Schmitt Trigger input

TABLE 9-6: SUMMARY OF REGISTERS ASSOCIATED WITH PORTC

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
PORTC	RC7	RC6	RC5	RC4	RC3	RC2	RC1	RC0	xxxx xxxx	uuuu uuuu
LATC	LATC Da	LATC Data Output Register							xxxx xxxx	uuuu uuuu
TRISC	PORTC I	ORTC Data Direction Register								1111 1111

Legend: x = unknown, u = unchanged

### 9.4 PORTD, TRISD and LATD Registers

This section is applicable only to the PIC18F4X2 devices.

PORTD is an 8-bit wide, bi-directional port. The corresponding Data Direction register is TRISD. Setting a TRISD bit (= 1) will make the corresponding PORTD pin an input (i.e., put the corresponding output driver in a Hi-Impedance mode). Clearing a TRISD bit (= 0) will make the corresponding PORTD pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATD) is also memory mapped. Read-modify-write operations on the LATD register reads and writes the latched output value for PORTD.

PORTD is an 8-bit port with Schmitt Trigger input buffers. Each pin is individually configurable as an input or output.

Note: On a Power-on Reset, these pins are configured as digital inputs.

PORTD can be configured as an 8-bit wide microprocessor port (parallel slave port) by setting control bit PSPMODE (TRISE<4>). In this mode, the input buffers are TTL. See Section 9.6 for additional information on the Parallel Slave Port (PSP).

#### **EXAMPLE 9-4: INITIALIZING PORTD**

CLRF	PORTD	,
		; clearing output
		; data latches
CLRF	LATD	; Alternate method
		; to clear output
		; data latches
MOVLW	0xCF	; Value used to
		; initialize data
		; direction
MOVWF	TRISD	; Set RD<3:0> as inputs
		; RD<5:4> as outputs
		; RD<7:6> as inputs

#### FIGURE 9-8: PORTD BLOCK DIAGRAM IN I/O PORT MODE




TABLE 9-7: PORTD FUNCTIONS

Name	Bit#	Buffer Type	Function
RD0/PSP0	bit0	ST/TTL <sup>(1)</sup>	Input/output port pin or parallel slave port bit0.
RD1/PSP1	bit1	ST/TTL <sup>(1)</sup>	Input/output port pin or parallel slave port bit1.
RD2/PSP2	bit2	ST/TTL <sup>(1)</sup>	Input/output port pin or parallel slave port bit2.
RD3/PSP3	bit3	ST/TTL <sup>(1)</sup>	Input/output port pin or parallel slave port bit3.
RD4/PSP4	bit4	ST/TTL <sup>(1)</sup>	Input/output port pin or parallel slave port bit4.
RD5/PSP5	bit5	ST/TTL <sup>(1)</sup>	Input/output port pin or parallel slave port bit5.
RD6/PSP6	bit6	ST/TTL <sup>(1)</sup>	Input/output port pin or parallel slave port bit6.
RD7/PSP7	bit7	ST/TTL <sup>(1)</sup>	Input/output port pin or parallel slave port bit7.

Legend: ST = Schmitt Trigger input, TTL = TTL input

Note 1: Input buffers are Schmitt Triggers when in I/O mode and TTL buffer when in Parallel Slave Port mode.

TABLE 9-8: SUMMARY OF REGISTERS ASSOCIATED WITH PORTD

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
PORTD	RD7	RD6	RD5	RD5 RD4 RD3 RD2 RD1 RD0						uuuu uuuu
LATD	LATD D	ata Outpi	ut Register		xxxx xxxx	uuuu uuuu				
TRISD	PORTD	Data Dir	ection Reg		1111 1111	1111 1111				
TRISE	IBF	OBF IBOV PSPMODE — PORTE Data Direction bits							0000 -111	0000 -111

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by PORTD.

## 9.5 PORTE, TRISE and LATE Registers

This section is only applicable to the PIC18F4X2 devices.

PORTE is a 3-bit wide, bi-directional port. The corresponding Data Direction register is TRISE. Setting a TRISE bit (= 1) will make the corresponding PORTE pin an input (i.e., put the corresponding output driver in a Hi-Impedance mode). Clearing a TRISE bit (= 0) will make the corresponding PORTE pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATE) is also memory mapped. Read-modify-write operations on the LATE register reads and writes the latched output value for PORTE.

PORTE has three pins (RE0/RD/AN5, RE1/WR/AN6 and RE2/CS/AN7) which are individually configurable as inputs or outputs. These pins have Schmitt Trigger input buffers.

Register 9-1 shows the TRISE register, which also controls the parallel slave port operation.

PORTE pins are multiplexed with analog inputs. When selected as an analog input, these pins will read as '0's.


TRISE controls the direction of the RE pins, even when they are being used as analog inputs. The user must make sure to keep the pins configured as inputs when using them as analog inputs.

**Note:** On a Power-on Reset, these pins are configured as analog inputs.

### **EXAMPLE 9-5: INITIAL IZING PORTE**

	LL 3-J.	INITIALIZING FOTTE
CLRF	PORTE	; Initialize PORTE by ; clearing output
CLRF	LATE	; data latches ; Alternate method ; to clear output
MOVLW	0x07	; data latches ; Configure A/D
MOVWF	ADCON1	; for digital inputs
MOVLW	0x05	; Value used to
MOVWF	TRISE	<pre>; initialize data ; direction ; Set RE&lt;0&gt; as inputs ; RE&lt;1&gt; as outputs ; RE&lt;2&gt; as inputs</pre>
		•

## FIGURE 9-9: PORTE BLOCK DIAGRAM IN I/O PORT MODE



Note 1: I/O pins have diode protection to VDD and Vss.

#### **REGISTER 9-1:** TRISE REGISTER

R-0	R-0	R/W-0	R/W-0	U-0	R/W-1	R/W-1	R/W-1
IBF	OBF	IBOV	PSPMODE	_	TRISE2	TRISE1	TRISE0
bit 7			•				hit 0

IBF: Input Buffer Full Status bit bit 7

1 = A word has been received and waiting to be read by the CPU

0 = No word has been received

bit 6 **OBF**: Output Buffer Full Status bit

1 = The output buffer still holds a previously written word

0 = The output buffer has been read

**IBOV**: Input Buffer Overflow Detect bit (in Microprocessor mode) bit 5

1 = A write occurred when a previously input word has not been read

(must be cleared in software)

0 = No overflow occurred

PSPMODE: Parallel Slave Port Mode Select bit bit 4

> 1 = Parallel Slave Port mode 0 = General purpose I/O mode

Unimplemented: Read as '0' bit 3

bit 2 TRISE2: RE2 Direction Control bit

> 1 = Input0 = Output

TRISE1: RE1 Direction Control bit bit 1

> 1 = Input0 = Output

TRISEO: RE0 Direction Control bit bit 0

> 1 = Input0 = Output

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' x = Bit is unknown

- n = Value at POR '1' = Bit is set '0' = Bit is cleared

TABLE 9-9: PORTE FUNCTIONS

Name	Bit#	Buffer Type	Function
RE0/RD/AN5	bit0	ST/TTL <sup>(1)</sup>	Input/output port pin or read control input in Parallel Slave Port mode or analog input:  RD
			<ul><li>1 = Not a read operation</li><li>0 = Read operation. Reads PORTD register (if chip selected).</li></ul>
RE1/WR/AN6	bit1	ST/TTL <sup>(1)</sup>	Input/output port pin or write control input in Parallel Slave Port mode or analog input:  WR
			<ul><li>1 = Not a write operation</li><li>0 = Write operation. Writes PORTD register (if chip selected).</li></ul>
RE2/CS/AN7	bit2	ST/TTL <sup>(1)</sup>	Input/output port pin or chip select control input in Parallel Slave Port mode or analog input:  CS
			1 = Device is not selected 0 = Device is selected

Legend: ST = Schmitt Trigger input, TTL = TTL input

Note 1: Input buffers are Schmitt Triggers when in I/O mode and TTL buffers when in Parallel Slave Port mode.

TABLE 9-10: SUMMARY OF REGISTERS ASSOCIATED WITH PORTE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
PORTE	_	_	_	_	_	RE2	RE1	RE0	000	000
LATE	_	_	_	_	_	LATE Data Output Register			xxx	uuu
TRISE	IBF	OBF	IBOV	PSPMODE	_	PORTE Da	ta Direction	bits	0000 -111	0000 -111
ADCON1	ADFM	ADCS2	_	_	PCFG3	PCFG2	PCFG1	PCFG0	00 0000	00 0000

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by PORTE.

### 9.6 Parallel Slave Port

The Parallel Slave Port is implemented on the 40-pin devices only (PIC18F4X2).

PORTD operates as an 8-bit wide Parallel Slave Port, or microprocessor port when control bit, PSPMODE (TRISE<4>) is set. It is asynchronously readable and writable by the external world through RD control input pin, RE0/RD and WR control input pin, RE1/WR.

It can directly interface to an 8-bit microprocessor data bus. The external microprocessor can read or write the PORTD latch as an 8-bit latch. Setting bit PSPMODE enables port pin RE0/ $\overline{RD}$  to be the  $\overline{RD}$  input, RE1/ $\overline{WR}$  to be the  $\overline{WR}$  input and RE2/ $\overline{CS}$  to be the  $\overline{CS}$  (chip select) input. For this functionality, the corresponding data direction bits of the TRISE register (TRISE<2:0>) must be configured as inputs (set). The A/D port configuration bits PCFG2:PCFG0 (ADCON1<2:0>) must be set, which will configure pins RE2:RE0 as digital I/O.

A write to the PSP occurs when both the  $\overline{CS}$  and  $\overline{WR}$  lines are first detected low. A read from the PSP occurs when both the  $\overline{CS}$  and  $\overline{RD}$  lines are first detected low.

The PORTE I/O pins become control inputs for the microprocessor port when bit PSPMODE (TRISE<4>) is set. In this mode, the user must make sure that the TRISE<2:0> bits are set (pins are configured as digital inputs), and the ADCON1 is configured for digital I/O. In this mode, the input buffers are TTL.

FIGURE 9-10: PORTD AND PORTE BLOCK DIAGRAM (PARALLEL SLAVE PORT)





FIGURE 9-11: PARALLEL SLAVE PORT WRITE WAVEFORMS






TABLE 9-11: REGISTERS ASSOCIATED WITH PARALLEL SLAVE PORT

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
PORTD	Port Data	Latch whe	n written; F	ort pins when	read			xxxx xxxx	uuuu uuuu	
LATD	LATD Data	a Output b	its						xxxx xxxx	uuuu uuuu
TRISD	PORTD D	ata Directi	on bits						1111 1111	1111 1111
PORTE	_	_	_	_	_	RE2	RE1	RE0	000	000
LATE	_	_	_	_	_	LATE Data	a Output bits	3	xxx	uuu
TRISE	IBF	OBF	IBOV	PSPMODE	_	PORTE D	ata Directio	n bits	0000 -111	0000 -111
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IF	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000 0000	0000 0000
ADCON1	ADFM	ADCS2	_	_	PCFG3	PCFG2	PCFG1	PCFG0	00 0000	00 0000

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Parallel Slave Port.

**NOTES:** 

## 10.0 TIMERO MODULE

The Timer0 module has the following features:

- Software selectable as an 8-bit or 16-bit timer/ counter
- · Readable and writable
- Dedicated 8-bit software programmable prescaler
- · Clock source selectable to be external or internal
- Interrupt-on-overflow from FFh to 00h in 8-bit mode and FFFFh to 0000h in 16-bit mode
- · Edge select for external clock

Figure 10-1 shows a simplified block diagram of the Timer0 module in 8-bit mode and Figure 10-2 shows a simplified block diagram of the Timer0 module in 16-bit mode.

The T0CON register (Register 10-1) is a readable and writable register that controls all the aspects of Timer0, including the prescale selection.

### REGISTER 10-1: TOCON: TIMERO CONTROL REGISTER


R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
TMR0ON	T08BIT	T0CS	T0SE	PSA	T0PS2	T0PS1	T0PS0
bit 7							bit 0

- bit 7 TMR0ON: Timer0 On/Off Control bit
  - 1 = Enables Timer0
  - 0 = Stops Timer0
- bit 6 T08BIT: Timer0 8-bit/16-bit Control bit
  - 1 = Timer0 is configured as an 8-bit timer/counter
  - 0 = Timer0 is configured as a 16-bit timer/counter
- bit 5 TOCS: Timer0 Clock Source Select bit
  - 1 = Transition on TOCKI pin
  - 0 = Internal instruction cycle clock (CLKO)
- bit 4 T0SE: Timer0 Source Edge Select bit
  - 1 = Increment on high-to-low transition on TOCKI pin
  - 0 = Increment on low-to-high transition on T0CKI pin
- bit 3 PSA: Timer0 Prescaler Assignment bit
  - 1 = TImer0 prescaler is NOT assigned. Timer0 clock input bypasses prescaler.
  - 0 = Timer0 prescaler is assigned. Timer0 clock input comes from prescaler output.
- bit 2-0 TOPS2:TOPS0: Timer0 Prescaler Select bits
  - 111 = 1:256 prescale value
  - 110 = 1:128 prescale value
  - 101 = 1:64 prescale value
  - 100 = 1:32 prescale value
  - 011 = 1:16 prescale value
  - 010 = 1:8 prescale value
  - 001 = 1:4 prescale value
  - 000 = 1:2 prescale value


### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
- n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## FIGURE 10-1: TIMERO BLOCK DIAGRAM IN 8-BIT MODE



## FIGURE 10-2: TIMERO BLOCK DIAGRAM IN 16-BIT MODE



## 10.1 Timer0 Operation

Timer0 can operate as a timer or as a counter.

Timer mode is selected by clearing the T0CS bit. In Timer mode, the Timer0 module will increment every instruction cycle (without prescaler). If the TMR0L register is written, the increment is inhibited for the following two instruction cycles. The user can work around this by writing an adjusted value to the TMR0L register.

Counter mode is selected by setting the T0CS bit. In Counter mode, Timer0 will increment, either on every rising or falling edge of pin RA4/T0CKI. The incrementing edge is determined by the Timer0 Source Edge Select bit (T0SE). Clearing the T0SE bit selects the rising edge. Restrictions on the external clock input are discussed below.

When an external clock input is used for Timer0, it must meet certain requirements. The requirements ensure the external clock can be synchronized with the internal phase clock (Tosc). Also, there is a delay in the actual incrementing of Timer0 after synchronization.

## 10.2 Prescaler

An 8-bit counter is available as a prescaler for the Timer0 module. The prescaler is not readable or writable.

The PSA and T0PS2:T0PS0 bits determine the prescaler assignment and prescale ratio.

Clearing bit PSA will assign the prescaler to the Timer0 module. When the prescaler is assigned to the Timer0 module, prescale values of 1:2, 1:4,..., 1:256 are selectable.

When assigned to the Timer0 module, all instructions writing to the TMR0L register (e.g., CLRF  $_{\mbox{\scriptsize TMR0}}$ , MOVWF  $_{\mbox{\scriptsize TMR0}}$ , BSF  $_{\mbox{\scriptsize TMR0}}$ , x....etc.) will clear the prescaler count.

Note:

Writing to TMR0L when the prescaler is assigned to Timer0 will clear the prescaler count, but will not change the prescaler assignment.

### 10.2.1 SWITCHING PRESCALER ASSIGNMENT

The prescaler assignment is fully under software control, (i.e., it can be changed "on-the-fly" during program execution).

## 10.3 Timer0 Interrupt

The TMR0 interrupt is generated when the TMR0 register overflows from FFh to 00h in 8-bit mode, or FFFFh to 0000h in 16-bit mode. This overflow sets the TMR0IF bit. The interrupt can be masked by clearing the TMR0IE bit. The TMR0IE bit must be cleared in software by the Timer0 module Interrupt Service Routine before re-enabling this interrupt. The TMR0 interrupt cannot awaken the processor from SLEEP, since the timer is shut-off during SLEEP.

## 10.4 16-Bit Mode Timer Reads and Writes

TMR0H is not the high byte of the timer/counter in 16-bit mode, but is actually a buffered version of the high byte of Timer0 (refer to Figure 10-2). The high byte of the Timer0 counter/timer is not directly readable nor writable. TMR0H is updated with the contents of the high byte of Timer0 during a read of TMR0L. This provides the ability to read all 16-bits of Timer0 without having to verify that the read of the high and low byte were valid due to a rollover between successive reads of the high and low byte.

A write to the high byte of Timer0 must also take place through the TMR0H buffer register. Timer0 high byte is updated with the contents of TMR0H when a write occurs to TMR0L. This allows all 16-bits of Timer0 to be updated at once.

## TABLE 10-1: REGISTERS ASSOCIATED WITH TIMERO

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
TMR0L	Timer0 Module Low Byte Register								xxxx xxxx	uuuu uuuu
TMR0H	Timer0 Module High Byte Register								0000 0000	0000 0000
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
T0CON	TMR0ON	T08BIT	T0CS	T0SE	PSA	T0PS2	T0PS1	T0PS0	1111 1111	1111 1111
TRISA	_	PORTA Data Direction Register								-111 1111

Legend: x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by Timer0.

**NOTES:** 

#### 11.0 TIMER1 MODULE

The Timer1 module timer/counter has the following features:

- 16-bit timer/counter (two 8-bit registers; TMR1H and TMR1L)
- · Readable and writable (both registers)
- · Internal or external clock select
- · Interrupt-on-overflow from FFFFh to 0000h
- · RESET from CCP module special event trigger

Figure 11-1 is a simplified block diagram of the Timer1 module.

Register 11-1 details the Timer1 control register. This register controls the Operating mode of the Timer1 module, and contains the Timer1 oscillator enable bit (T1OSCEN). Timer1 can be enabled or disabled by setting or clearing control bit TMR1ON (T1CON<0>).

#### REGISTER 11-1: T1CON: TIMER1 CONTROL REGISTER

R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
RD16	_	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N
bit 7							bit 0

- bit 7 RD16: 16-bit Read/Write Mode Enable bit
  - 1 = Enables register Read/Write of Timer1 in one 16-bit operation
  - 0 = Enables register Read/Write of Timer1 in two 8-bit operations
- bit 6 Unimplemented: Read as '0'
- bit 5-4 T1CKPS1:T1CKPS0: Timer1 Input Clock Prescale Select bits
  - 11 = 1:8 Prescale value
  - 10 = 1:4 Prescale value
  - 01 = 1:2 Prescale value
  - 00 = 1:1 Prescale value
- bit 3 T10SCEN: Timer1 Oscillator Enable bit
  - 1 = Timer1 Oscillator is enabled
  - 0 = Timer1 Oscillator is shut-off

The oscillator inverter and feedback resistor are turned off to eliminate power drain.

bit 2 T1SYNC: Timer1 External Clock Input Synchronization Select bit

#### When TMR1CS = 1:

- 1 = Do not synchronize external clock input
- 0 = Synchronize external clock input

#### When TMR1CS = 0:

This bit is ignored. Timer1 uses the internal clock when TMR1CS = 0.

- bit 1 TMR1CS: Timer1 Clock Source Select bit
  - 1 = External clock from pin RC0/T1OSO/T13CKI (on the rising edge)
  - 0 = Internal clock (Fosc/4)
- bit 0 TMR1ON: Timer1 On bit
  - 1 = Enables Timer1
  - 0 = Stops Timer1

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### 11.1 Timer1 Operation

Timer1 can operate in one of these modes:

- · As a timer
- · As a synchronous counter
- · As an asynchronous counter


The Operating mode is determined by the clock select bit, TMR1CS (T1CON<1>).

When TMR1CS = 0, Timer1 increments every instruction cycle. When TMR1CS = 1, Timer1 increments on every rising edge of the external clock input or the Timer1 oscillator, if enabled.

When the Timer1 oscillator is enabled (T1OSCEN is set), the RC1/T1OSI and RC0/T1OSO/T1CKI pins become inputs. That is, the TRISC<1:0> value is ignored, and the pins are read as '0'.


Timer1 also has an internal "RESET input". This RESET can be generated by the CCP module (Section 14.0).

#### FIGURE 11-1: TIMER1 BLOCK DIAGRAM



Note 1: When enable bit T1OSCEN is cleared, the inverter and feedback resistor are turned off. This eliminates power drain.

#### FIGURE 11-2: TIMER1 BLOCK DIAGRAM: 16-BIT READ/WRITE MODE



#### 11.2 Timer1 Oscillator

A crystal oscillator circuit is built-in between pins T1OSI (input) and T1OSO (amplifier output). It is enabled by setting control bit T1OSCEN (T1CON<3>). The oscillator is a low power oscillator rated up to 200 kHz. It will continue to run during SLEEP. It is primarily intended for a 32 kHz crystal. Table 11-1 shows the capacitor selection for the Timer1 oscillator.

The user must provide a software time delay to ensure proper start-up of the Timer1 oscillator.

TABLE 11-1: CAPACITOR SELECTION FOR THE ALTERNATE OSCILLATOR

Osc Type	Freq	C1	C2				
LP	32 kHz	TBD <sup>(1)</sup>	TBD <sup>(1)</sup>				
	Crystal to be Tested:						
32.768 kHz   Epson C-001R32.768K-A   ± 20 PPM							

**Note 1:** Microchip suggests 33 pF as a starting point in validating the oscillator circuit.

- 2: Higher capacitance increases the stability of the oscillator, but also increases the start-up time.
- 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.
- **4:** Capacitor values are for design guidance only.

#### 11.3 Timer1 Interrupt

The TMR1 Register pair (TMR1H:TMR1L) increments from 0000h to FFFFh and rolls over to 0000h. The TMR1 Interrupt, if enabled, is generated on overflow, which is latched in interrupt flag bit TMR1IF (PIR1<0>). This interrupt can be enabled/disabled by setting/clearing TMR1 interrupt enable bit, TMR1IE (PIE1<0>).

## 11.4 Resetting Timer1 using a CCP Trigger Output

If the CCP module is configured in Compare mode to generate a "special event trigger" (CCP1M3:CCP1M0 = 1011), this signal will reset Timer1 and start an A/D conversion (if the A/D module is enabled).

Note: The special event triggers from the CCP1 module will not set interrupt flag bit TMR1IF (PIR1<0>).

Timer1 must be configured for either Timer or Synchronized Counter mode to take advantage of this feature. If Timer1 is running in Asynchronous Counter mode, this RESET operation may not work.

In the event that a write to Timer1 coincides with a special event trigger from CCP1, the write will take precedence.

In this mode of operation, the CCPR1H:CCPR1L registers pair effectively becomes the period register for Timer1.

#### 11.5 Timer1 16-Bit Read/Write Mode

Timer1 can be configured for 16-bit reads and writes (see Figure 11-2). When the RD16 control bit (T1CON<7>) is set, the address for TMR1H is mapped to a buffer register for the high byte of Timer1. A read from TMR1L will load the contents of the high byte of Timer1 into the Timer1 high byte buffer. This provides the user with the ability to accurately read all 16-bits of Timer1 without having to determine whether a read of the high byte followed by a read of the low byte is valid, due to a rollover between reads.

A write to the high byte of Timer1 must also take place through the TMR1H buffer register. Timer1 high byte is updated with the contents of TMR1H when a write occurs to TMR1L. This allows a user to write all 16 bits to both the high and low bytes of Timer1 at once.

The high byte of Timer1 is not directly readable or writable in this mode. All reads and writes must take place through the Timer1 high byte buffer register. Writes to TMR1H do not clear the Timer1 prescaler. The prescaler is only cleared on writes to TMR1L.

## PIC18FXX2

## TABLE 11-2: REGISTERS ASSOCIATED WITH TIMER1 AS A TIMER/COUNTER

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Valu POR,		Valu All ( RES	Other
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000	0000	0000	0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP11P	TMR2IP	TMR1IP	0000	0000	0000	0000
TMR1L	Holding Reg	Holding Register for the Least Significant Byte of the 16-bit TMR1 Register								xxxx	uuuu	uuuu
TMR1H	Holding Reg	olding Register for the Most Significant Byte of the 16-bit TMR1 Register								xxxx	uuuu	uuuu
T1CON	RD16	_	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	0-00	0000	u-uu	uuuu

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Timer1 module.

Note 1: The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18F2X2 devices; always maintain these bits clear.

#### 12.0 TIMER2 MODULE

The Timer2 module timer has the following features:

- 8-bit timer (TMR2 register)
- 8-bit period register (PR2)
- Readable and writable (both registers)
- Software programmable prescaler (1:1, 1:4, 1:16)
- Software programmable postscaler (1:1 to 1:16)
- · Interrupt on TMR2 match of PR2
- SSP module optional use of TMR2 output to generate clock shift

Timer2 has a control register shown in Register 12-1. Timer2 can be shut-off by clearing control bit TMR2ON (T2CON<2>) to minimize power consumption. Figure 12-1 is a simplified block diagram of the Timer2 module. Register 12-1 shows the Timer2 control register. The prescaler and postscaler selection of Timer2 are controlled by this register.

### 12.1 Timer2 Operation

Timer2 can be used as the PWM time-base for the PWM mode of the CCP module. The TMR2 register is readable and writable, and is cleared on any device RESET. The input clock (Fosc/4) has a prescale option of 1:1, 1:4 or 1:16, selected by control bits T2CKPS1:T2CKPS0 (T2CON<1:0>). The match output of TMR2 goes through a 4-bit postscaler (which gives a 1:1 to 1:16 scaling inclusive) to generate a TMR2 interrupt (latched in flag bit TMR2IF, (PIR1<1>)).

The prescaler and postscaler counters are cleared when any of the following occurs:

- a write to the TMR2 register
- · a write to the T2CON register
- any device RESET (Power-on Reset, MCLR Reset, Watchdog Timer Reset, or Brown-out Reset)

TMR2 is not cleared when T2CON is written.

#### REGISTER 12-1: T2CON: TIMER2 CONTROL REGISTER

U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0
bit 7							bit 0

bit 7 Unimplemented: Read as '0'

bit 6-3 TOUTPS3:TOUTPS0: Timer2 Output Postscale Select bits

0000 = 1:1 Postscale 0001 = 1:2 Postscale

•

Ĭ

1111 = 1:16 Postscale

bit 2 TMR2ON: Timer2 On bit

1 = Timer2 is on 0 = Timer2 is off

bit 1-0 T2CKPS1:T2CKPS0: Timer2 Clock Prescale Select bits

00 =Prescaler is 1 01 =Prescaler is 4 1x =Prescaler is 16

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' - n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 12.2 Timer2 Interrupt

The Timer2 module has an 8-bit period register, PR2. Timer2 increments from 00h until it matches PR2 and then resets to 00h on the next increment cycle. PR2 is a readable and writable register. The PR2 register is initialized to FFh upon RESET.

## 12.3 Output of TMR2

The output of TMR2 (before the postscaler) is fed to the Synchronous Serial Port module, which optionally uses it to generate the shift clock.

FIGURE 12-1: TIMER2 BLOCK DIAGRAM




TABLE 12-1: REGISTERS ASSOCIATED WITH TIMER2 AS A TIMER/COUNTER

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value POR,		Valu All ( RES	Other
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000	0000	0000	0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000	0000	0000	0000
TMR2	Timer2 Mod	dule Register							0000	0000	0000	0000
T2CON	1	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000	0000	-000	0000
PR2	Timer2 Per	imer2 Period Register									1111	1111

Legend: x = unknown, u = unchanged, - = unimplemented read as '0'. Shaded cells are not used by the Timer2 module.

Note 1: The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18F2X2 devices; always maintain these bits clear.

#### 13.0 TIMER3 MODULE

The Timer3 module timer/counter has the following features:

- 16-bit timer/counter (two 8-bit registers; TMR3H and TMR3L)
- · Readable and writable (both registers)
- · Internal or external clock select
- · Interrupt-on-overflow from FFFFh to 0000h
- · RESET from CCP module trigger

Figure 13-1 is a simplified block diagram of the Timer3 module.

Register 13-1 shows the Timer3 control register. This register controls the Operating mode of the Timer3 module and sets the CCP clock source.

Register 11-1 shows the Timer1 control register. This register controls the Operating mode of the Timer1 module, as well as contains the Timer1 oscillator enable bit (T1OSCEN), which can be a clock source for Timer3.

#### REGISTER 13-1: T3CON: TIMER3 CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
RD16	T3CCP2	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON
bit 7							bit 0

- bit 7 RD16: 16-bit Read/Write Mode Enable bit
  - 1 = Enables register Read/Write of Timer3 in one 16-bit operation
  - 0 = Enables register Read/Write of Timer3 in two 8-bit operations
- bit 6-3 T3CCP2:T3CCP1: Timer3 and Timer1 to CCPx Enable bits
  - 1x = Timer3 is the clock source for compare/capture CCP modules
  - 01 = Timer3 is the clock source for compare/capture of CCP2, Timer1 is the clock source for compare/capture of CCP1
  - 00 = Timer1 is the clock source for compare/capture CCP modules
- bit 5-4 T3CKPS1:T3CKPS0: Timer3 Input Clock Prescale Select bits
  - 11 = 1:8 Prescale value
  - 10 = 1:4 Prescale value
  - 01 = 1:2 Prescale value
  - 00 = 1:1 Prescale value
- bit 2 T3SYNC: Timer3 External Clock Input Synchronization Control bit (Not usable if the system clock comes from Timer1/Timer3)

#### When TMR3CS = 1:

- 1 = Do not synchronize external clock input
- 0 = Synchronize external clock input

#### When TMR3CS = 0:

This bit is ignored. Timer3 uses the internal clock when TMR3CS = 0.

- bit 1 TMR3CS: Timer3 Clock Source Select bit
  - 1 = External clock input from Timer1 oscillator or T1CKI (on the rising edge after the first falling edge)
  - 0 = Internal clock (FOSC/4)
- bit 0 TMR3ON: Timer3 On bit
  - 1 = Enables Timer3
  - 0 = Stops Timer3

Legen	d٠
LOGOTI	u.

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' - n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 13.1 Timer3 Operation

Timer3 can operate in one of these modes:

- · As a timer
- · As a synchronous counter
- · As an asynchronous counter


The Operating mode is determined by the clock select bit, TMR3CS (T3CON<1>).

When TMR3CS = 0, Timer3 increments every instruction cycle. When TMR3CS = 1, Timer3 increments on every rising edge of the Timer1 external clock input or the Timer1 oscillator, if enabled.


When the Timer1 oscillator is enabled (T1OSCEN is set), the RC1/T1OSI and RC0/T1OSO/T1CKI pins become inputs. That is, the TRISC<1:0> value is ignored, and the pins are read as '0'.

Timer3 also has an internal "RESET input". This RESET can be generated by the CCP module (Section 14.0).

#### FIGURE 13-1: TIMER3 BLOCK DIAGRAM



#### FIGURE 13-2: TIMER3 BLOCK DIAGRAM CONFIGURED IN 16-BIT READ/WRITE MODE



#### 13.2 Timer1 Oscillator

The Timer1 oscillator may be used as the clock source for Timer3. The Timer1 oscillator is enabled by setting the T1OSCEN (T1CON<3>) bit. The oscillator is a low power oscillator rated up to 200 KHz. See Section 11.0 for further details.

## 13.3 Timer3 Interrupt

The TMR3 Register pair (TMR3H:TMR3L) increments from 0000h to FFFFh and rolls over to 0000h. The TMR3 Interrupt, if enabled, is generated on overflow, which is latched in interrupt flag bit, TMR3IF (PIR2<1>). This interrupt can be enabled/disabled by setting/clearing TMR3 interrupt enable bit, TMR3IE (PIE2<1>).

## 13.4 Resetting Timer3 Using a CCP Trigger Output

If the CCP module is configured in Compare mode to generate a "special event trigger" (CCP1M3:CCP1M0 = 1011), this signal will reset Timer3.

**Note:** The special event triggers from the CCP module will not set interrupt flag bit, TMR3IF (PIR1<0>).

Timer3 must be configured for either Timer or Synchronized Counter mode to take advantage of this feature. If Timer3 is running in Asynchronous Counter mode, this RESET operation may not work. In the event that a write to Timer3 coincides with a special event trigger from CCP1, the write will take precedence. In this mode of operation, the CCPR1H:CCPR1L registers pair effectively becomes the period register for Timer3.

TABLE 13-1: REGISTERS ASSOCIATED WITH TIMER3 AS A TIMER/COUNTER

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR2	_	_	_	EEIF	BCLIF	LVDIF	TMR3IF	CCP2IF	0 0000	0 0000
PIE2	_	_	_	EEIE	BCLIE	LVDIE	TMR3IE	CCP2IE	0 0000	0 0000
IPR2	_	_	_	EEIP	BCLIP	LVDIP	TMR3IP	CCP2IP	1 1111	1 1111
TMR3L	Holding F	Register for t	he Least Siç	gnificant Byt	e of the 16-b	it TMR3 Re	gister		xxxx xxxx	uuuu uuuu
TMR3H	Holding Register for the Most Significant Byte of the 16-bit TMR3 Register								xxxx xxxx	uuuu uuuu
T1CON	RD16	_	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	0-00 0000	u-uu uuuu
T3CON	RD16	T3CCP2	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON	0000 0000	uuuu uuuu

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Timer1 module.

# PIC18FXX2

**NOTES:** 

# 14.0 CAPTURE/COMPARE/PWM (CCP) MODULES

Each CCP (Capture/Compare/PWM) module contains a 16-bit register which can operate as a 16-bit Capture register, as a 16-bit Compare register or as a PWM Master/Slave Duty Cycle register. Table 14-1 shows the timer resources of the CCP Module modes.

The operation of CCP1 is identical to that of CCP2, with the exception of the special event trigger. Therefore, operation of a CCP module in the following sections is described with respect to CCP1.

Table 14-2 shows the interaction of the CCP modules.

#### REGISTER 14-1: CCP1CON REGISTER/CCP2CON REGISTER

U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	_	DCxB1	DCxB0	CCPxM3	CCPxM2	CCPxM1	CCPxM0
bit 7							bit 0

bit 7-6 Unimplemented: Read as '0'

bit 5-4 DCxB1:DCxB0: PWM Duty Cycle bit1 and bit0

Capture mode:

Unused

Compare mode:

Unused

PWM mode:

These bits are the two LSbs (bit1 and bit0) of the 10-bit PWM duty cycle. The upper eight bits (DCx9:DCx2) of the duty cycle are found in CCPRxL.

bit 3-0 CCPxM3:CCPxM0: CCPx Mode Select bits

0000 = Capture/Compare/PWM disabled (resets CCPx module)

0001 = Reserved

0010 = Compare mode, toggle output on match (CCPxIF bit is set)

0011 = Reserved

0100 = Capture mode, every falling edge

0101 = Capture mode, every rising edge

0110 = Capture mode, every 4th rising edge

0111 = Capture mode, every 16th rising edge

1000 = Compare mode,

Initialize CCP pin Low, on compare match force CCP pin High (CCPIF bit is set)

1001 = Compare mode,

Initialize CCP pin High, on compare match force CCP pin Low (CCPIF bit is set)

1010 = Compare mode,

Generate software interrupt on compare match (CCPIF bit is set, CCP pin is unaffected)

1011 = Compare mode,

Trigger special event (CCPIF bit is set)

11xx = PWM mode

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### 14.1 CCP1 Module

Capture/Compare/PWM Register 1 (CCPR1) is comprised of two 8-bit registers: CCPR1L (low byte) and CCPR1H (high byte). The CCP1CON register controls the operation of CCP1. All are readable and writable.

TABLE 14-1: CCP MODE - TIMER RESOURCE

CCP Mode	Timer Resource
Capture	Timer1 or Timer3
Compare	Timer1 or Timer3
PWM	Timer2

#### 14.2 CCP2 Module

Capture/Compare/PWM Register2 (CCPR2) is comprised of two 8-bit registers: CCPR2L (low byte) and CCPR2H (high byte). The CCP2CON register controls the operation of CCP2. All are readable and writable.

TABLE 14-2: INTERACTION OF TWO CCP MODULES

CCPx Mode	CCPy Mode	Interaction
Capture	Capture	TMR1 or TMR3 time-base. Time-base can be different for each CCP.
Capture	Compare	The compare could be configured for the special event trigger, which clears either TMR1 or TMR3 depending upon which time-base is used.
Compare	Compare	The compare(s) could be configured for the special event trigger, which clears TMR1 or TMR3 depending upon which time-base is used.
PWM	PWM	The PWMs will have the same frequency and update rate (TMR2 interrupt).
PWM	Capture	None
PWM	Compare	None

## 14.3 Capture Mode

In Capture mode, CCPR1H:CCPR1L captures the 16-bit value of the TMR1 or TMR3 registers when an event occurs on pin RC2/CCP1. An event is defined as one of the following:

- · every falling edge
- · every rising edge
- · every 4th rising edge
- · every 16th rising edge

The event is selected by control bits CCP1M3:CCP1M0 (CCP1CON<3:0>). When a capture is made, the interrupt request flag bit CCP1IF (PIR1<2>) is set; it must be cleared in software. If another capture occurs before the value in register CCPR1 is read, the old captured value is overwritten by the new captured value.

#### 14.3.1 CCP PIN CONFIGURATION

In Capture mode, the RC2/CCP1 pin should be configured as an input by setting the TRISC<2> bit.

**Note:** If the RC2/CCP1 is configured as an output, a write to the port can cause a capture condition.

#### 14.3.2 TIMER1/TIMER3 MODE SELECTION

The timers that are to be used with the capture feature (either Timer1 and/or Timer3) must be running in Timer mode or Synchronized Counter mode. In Asynchronous Counter mode, the capture operation may not work. The timer to be used with each CCP module is selected in the T3CON register.

#### 14.3.3 SOFTWARE INTERRUPT

When the Capture mode is changed, a false capture interrupt may be generated. The user should keep bit CCP1IE (PIE1<2>) clear to avoid false interrupts and should clear the flag bit, CCP1IF, following any such change in Operating mode.

#### 14.3.4 CCP PRESCALER


There are four prescaler settings, specified by bits CCP1M3:CCP1M0. Whenever the CCP module is turned off or the CCP module is not in Capture mode, the prescaler counter is cleared. This means that any RESET will clear the prescaler counter.

Switching from one capture prescaler to another may generate an interrupt. Also, the prescaler counter will not be cleared, therefore, the first capture may be from a non-zero prescaler. Example 14-1 shows the recommended method for switching between capture prescalers. This example also clears the prescaler counter and will not generate the "false" interrupt.

## EXAMPLE 14-1: CHANGING BETWEEN CAPTURE PRESCALERS

```
CLRF CCP1CON, F; Turn CCP module off
MOVLW NEW_CAPT_PS; Load WREG with the
; new prescaler mode
; value and CCP ON
MOVWF CCP1CON ; Load CCP1CON with
; this value
```

FIGURE 14-1: CAPTURE MODE OPERATION BLOCK DIAGRAM



#### 14.4 Compare Mode

In Compare mode, the 16-bit CCPR1 (CCPR2) register value is constantly compared against either the TMR1 register pair value, or the TMR3 register pair value. When a match occurs, the RC2/CCP1 (RC1/CCP2) pin is:

- · driven High
- · driven Low
- · toggle output (High to Low or Low to High)
- · remains unchanged

The action on the pin is based on the value of control bits CCP1M3:CCP1M0 (CCP2M3:CCP2M0). At the same time, interrupt flag bit CCP1IF (CCP2IF) is set.

#### 14.4.1 CCP PIN CONFIGURATION

The user must configure the CCPx pin as an output by clearing the appropriate TRISC bit.

Note:

Clearing the CCP1CON register will force the RC2/CCP1 compare output latch to the default low level. This is not the PORTC I/O data latch.

#### 14.4.2 TIMER1/TIMER3 MODE SELECTION

Timer1 and/or Timer3 must be running in Timer mode or Synchronized Counter mode if the CCP module is using the compare feature. In Asynchronous Counter mode, the compare operation may not work.

#### 14.4.3 SOFTWARE INTERRUPT MODE

When generate software interrupt is chosen, the CCP1 pin is not affected. Only a CCP interrupt is generated (if enabled).

#### 14.4.4 SPECIAL EVENT TRIGGER

In this mode, an internal hardware trigger is generated, which may be used to initiate an action.

The special event trigger output of CCP1 resets the TMR1 register pair. This allows the CCPR1 register to effectively be a 16-bit programmable period register for Timer1.

The special trigger output of CCPx resets either the TMR1 or TMR3 register pair. Additionally, the CCP2 Special Event Trigger will start an A/D conversion if the A/D module is enabled.

Note: The special event trigger from the CCP2 module will not set the Timer1 or Timer3 interrupt flag bits.

#### FIGURE 14-2: COMPARE MODE OPERATION BLOCK DIAGRAM




TABLE 14-3: REGISTERS ASSOCIATED WITH CAPTURE, COMPARE, TIMER1 AND TIMER3

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000 0000	0000 0000
TRISC	PORTC D	ata Direction	Register						1111 1111	1111 1111
TMR1L	Holding Re	egister for the	e Least Sigr	nificant Byte	of the 16-bit	tTMR1 Reg	gister		xxxx xxxx	uuuu uuuu
TMR1H	Holding Re	egister for the	e Most Sign	ificant Byte	of the 16-bit	TMR1 Reg	ister		xxxx xxxx	uuuu uuuu
T1CON	RD16	_	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	0-00 0000	u-uu uuuu
CCPR1L	Capture/C	ompare/PWI	M Register1	(LSB)					xxxx xxxx	uuuu uuuu
CCPR1H	Capture/C	ompare/PWI	M Register1	(MSB)					xxxx xxxx	uuuu uuuu
CCP1CON	_	_	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00 0000	00 0000
CCPR2L	Capture/C	ompare/PWI	M Register2	(LSB)					xxxx xxxx	uuuu uuuu
CCPR2H	Capture/C	ompare/PWI	M Register2	(MSB)					xxxx xxxx	uuuu uuuu
CCP2CON	_		DC2B1	DC2B0	CCP2M3	CCP2M2	CCP2M1	CCP2M0	00 0000	00 0000
PIR2	_	1	1	EEIE	BCLIF	LVDIF	TMR3IF	CCP2IF	0 0000	0 0000
PIE2	_	_	_	EEIF	BCLIE	LVDIE	TMR3IE	CCP2IE	0 0000	0 0000
IPR2	_	1	l	EEIP	BCLIP	LVDIP	TMR3IP	CCP2IP	1 1111	1 1111
TMR3L	Holding Register for the Least Significant Byte of the 16-bit TMR3 Register							xxxx xxxx	uuuu uuuu	
TMR3H	Holding Register for the Most Significant Byte of the 16-bit TMR3 Register							xxxx xxxx	uuuu uuuu	
T3CON	RD16	T3CCP2	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON	0000 0000	uuuu uuuu

 $\label{eq:local_$ 

Note 1: The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18F2x2 devices; always maintain these bits clear.

#### 14.5 PWM Mode


In Pulse Width Modulation (PWM) mode, the CCP1 pin produces up to a 10-bit resolution PWM output. Since the CCP1 pin is multiplexed with the PORTC data latch, the TRISC<2> bit must be cleared to make the CCP1 pin an output.

Note: Clearing the CCP1CON register will force the CCP1 PWM output latch to the default low level. This is not the PORTC I/O data latch.

Figure 14-3 shows a simplified block diagram of the CCP module in PWM mode.


For a step-by-step procedure on how to set up the CCP module for PWM operation, see Section 14.5.3.

## FIGURE 14-3: SIMPLIFIED PWM BLOCK DIAGRAM



A PWM output (Figure 14-4) has a time-base (period) and a time that the output stays high (duty cycle). The frequency of the PWM is the inverse of the period (1/period).

FIGURE 14-4: PWM OUTPUT



#### 14.5.1 PWM PERIOD

The PWM period is specified by writing to the PR2 register. The PWM period can be calculated using the following formula:

PWM frequency is defined as 1 / [PWM period].

When TMR2 is equal to PR2, the following three events occur on the next increment cycle:

- · TMR2 is cleared
- The CCP1 pin is set (exception: if PWM duty cycle = 0%, the CCP1 pin will not be set)
- The PWM duty cycle is latched from CCPR1L into CCPR1H

Note: The Timer2 postscaler (see Section 12.0) is not used in the determination of the PWM frequency. The postscaler could be used to have a servo update rate at a different frequency than the PWM output.

#### 14.5.2 PWM DUTY CYCLE

The PWM duty cycle is specified by writing to the CCPR1L register and to the CCP1CON<5:4> bits. Up to 10-bit resolution is available. The CCPR1L contains the eight MSbs and the CCP1CON<5:4> contains the two LSbs. This 10-bit value is represented by CCPR1L:CCP1CON<5:4>. The following equation is used to calculate the PWM duty cycle in time:

CCPR1L and CCP1CON<5:4> can be written to at any time, but the duty cycle value is not latched into CCPR1H until after a match between PR2 and TMR2 occurs (i.e., the period is complete). In PWM mode, CCPR1H is a read only register.

The CCPR1H register and a 2-bit internal latch are used to double buffer the PWM duty cycle. This double buffering is essential for glitchless PWM operation.

When the CCPR1H and 2-bit latch match TMR2 concatenated with an internal 2-bit Q clock or 2 bits of the TMR2 prescaler, the CCP1 pin is cleared.

The maximum PWM resolution (bits) for a given PWM frequency is given by the equation:

PWM Resolution (max) = 
$$\frac{\log(\frac{FOSC}{FPWM})}{\log(2)}$$
bits

Note: If the PWM duty cycle value is longer than the PWM period, the CCP1 pin will not be cleared.

#### 14.5.3 SETUP FOR PWM OPERATION

The following steps should be taken when configuring the CCP module for PWM operation:

- 1. Set the PWM period by writing to the PR2 register.
- 2. Set the PWM duty cycle by writing to the CCPR1L register and CCP1CON<5:4> bits.
- Make the CCP1 pin an output by clearing the TRISC<2> bit.
- 4. Set the TMR2 prescale value and enable Timer2 by writing to T2CON.
- 5. Configure the CCP1 module for PWM operation.

TABLE 14-4: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS AT 40 MHz

PWM Frequency	2.44 kHz	9.77 kHz	39.06 kHz	156.25 kHz	312.50 kHz	416.67 kHz
Timer Prescaler (1, 4, 16)	16	4	1	1	1	1
PR2 Value	0xFF	0xFF	0xFF	0x3F	0x1F	0x17
Maximum Resolution (bits)	14	12	10	8	7	6.58

TABLE 14-5: REGISTERS ASSOCIATED WITH PWM AND TIMER2

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0		e on BOR	All C	e on Other ETS
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PIR1	PSPIF <sup>(1)</sup> ADIF RCIF TXIF SSPIF CCP1IF TMR2IF TMR1IF					0000	0000	0000	0000			
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000	0000	0000	0000
TRISC	PORTC Da	PORTC Data Direction Register								1111	1111	1111
TMR2	Timer2 Mo	dule Registe	er						0000	0000	0000	0000
PR2	Timer2 Mo	dule Period	Register						1111	1111	1111	1111
T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000	0000	-000	0000
CCPR1L	Capture/Co	ompare/PWI	M Register1	(LSB)					xxxx	xxxx	uuuu	uuuu
CCPR1H	Capture/Co	ompare/PWI	M Register1	(MSB)					xxxx	xxxx	uuuu	uuuu
CCP1CON	_	_	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00	0000	00	0000
CCPR2L	Capture/Compare/PWM Register2 (LSB)								xxxx	xxxx	uuuu	uuuu
CCPR2H	Capture/Compare/PWM Register2 (MSB)								xxxx	xxxx	uuuu	uuuu
CCP2CON	_	_	DC2B1	DC2B0	ССР2М3	CCP2M2	CCP2M1	ССР2М0	00	0000	00	0000

 $\label{eq:local_equation} \textbf{Legend:} \quad \textbf{x} = \textbf{unknown}, \textbf{u} = \textbf{unchanged}, \textbf{-} = \textbf{unimplemented}, \textbf{read as '0'}. \textbf{Shaded cells are not used by PWM and Timer2}.$ 

Note 1: The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18F2X2 devices; always maintain these bits clear.

# PIC18FXX2

**NOTES:** 

## 15.0 MASTER SYNCHRONOUS SERIAL PORT (MSSP) MODULE

## 15.1 Master SSP (MSSP) Module Overview

The Master Synchronous Serial Port (MSSP) module is a serial interface useful for communicating with other peripheral or microcontroller devices. These peripheral devices may be serial EEPROMs, shift registers, display drivers, A/D converters, etc. The MSSP module can operate in one of two modes:

- · Serial Peripheral Interface (SPI)
- Inter-Integrated Circuit (I<sup>2</sup>C)
  - Full Master mode
  - Slave mode (with general address call)

The I<sup>2</sup>C interface supports the following modes in hardware:

- · Master mode
- · Multi-Master mode
- · Slave mode

## 15.2 Control Registers

The MSSP module has three associated registers. These include a status register (SSPSTAT) and two control registers (SSPCON1 and SSPCON2). The use of these registers and their individual configuration bits differ significantly, depending on whether the MSSP module is operated in SPI or I<sup>2</sup>C mode.

Additional details are provided under the individual sections.

#### 15.3 SPI Mode

The SPI mode allows 8-bits of data to be synchronously transmitted and received, simultaneously. All four modes of SPI are supported. To accomplish communication, typically three pins are used:


- · Serial Data Out (SDO) RC5/SDO
- · Serial Data In (SDI) RC4/SDI/SDA
- · Serial Clock (SCK) RC3/SCK/SCL/LVDIN

Additionally, a fourth pin may be used when in a Slave mode of operation:

Slave Select (SS) - RA5/SS/AN4

Figure 15-1 shows the block diagram of the MSSP module when operating in SPI mode.

FIGURE 15-1: MSSP BLOCK DIAGRAM (SPI MODE)



#### 15.3.1 REGISTERS

The MSSP module has four registers for SPI mode operation. These are:

- MSSP Control Register1 (SSPCON1)
- · MSSP Status Register (SSPSTAT)
- Serial Receive/Transmit Buffer (SSPBUF)
- MSSP Shift Register (SSPSR) Not directly accessible

SSPCON1 and SSPSTAT are the control and status registers in SPI mode operation. The SSPCON1 register is readable and writable. The lower 6 bits of the SSPSTAT are read only. The upper two bits of the SSPSTAT are read/write.

SSPSR is the shift register used for shifting data in or out. SSPBUF is the buffer register to which data bytes are written to or read from.

In receive operations, SSPSR and SSPBUF together create a double buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPBUF and the SSPIF interrupt is set.

During transmission, the SSPBUF is not double buffered. A write to SSPBUF will write to both SSPBUF and SSPSR.

### REGISTER 15-1: SSPSTAT: MSSP STATUS REGISTER (SPI MODE)

R/W-0	R/W-0	R-0	R-0	R-0	R-0	R-0	R-0
SMP	CKE	D/Ā	Р	S	R/W	UA	BF
bit 7							bit 0

#### bit 7 SMP: Sample bit

#### SPI Master mode:

- 1 = Input data sampled at end of data output time
- 0 = Input data sampled at middle of data output time

#### SPI Slave mode:

SMP must be cleared when SPI is used in Slave mode

bit 6 CKE: SPI Clock Edge Select

#### When CKP = 0:

- 1 = Data transmitted on rising edge of SCK
- 0 = Data transmitted on falling edge of SCK

#### When CKP = 1:

- 1 = Data transmitted on falling edge of SCK
- 0 = Data transmitted on rising edge of SCK
- bit 5 D/A: Data/Address bit

Used in I<sup>2</sup>C mode only

bit 4 P: STOP bit

Used in I<sup>2</sup>C mode only. This bit is cleared when the MSSP module is disabled, SSPEN is cleared.

bit 3 S: START bit

Used in I<sup>2</sup>C mode only

bit 2 R/W: Read/Write bit information

Used in I<sup>2</sup>C mode only

bit 1 UA: Update Address

Used in I<sup>2</sup>C mode only

bit 0 **BF:** Buffer Full Status bit (Receive mode only)

- 1 = Receive complete, SSPBUF is full
- 0 = Receive not complete, SSPBUF is empty

Legend	:
--------	---

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

- n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### REGISTER 15-2: SSPCON1: MSSP CONTROL REGISTER1 (SPI MODE)

| R/W-0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| WCOL  | SSPOV | SSPEN | CKP   | SSPM3 | SSPM2 | SSPM1 | SSPM0 |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 7 **WCOL:** Write Collision Detect bit (Transmit mode only)

- 1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)
- 0 = No collision
- bit 6 SSPOV: Receive Overflow Indicator bit

SPI Slave mode:

- 1 = A new byte is received while the SSPBUF register is still holding the previous data. In case of overflow, the data in SSPSR is lost. Overflow can only occur in Slave mode. The user must read the SSPBUF, even if only transmitting data, to avoid setting overflow (must be cleared in software).
- 0 = No overflow

**Note:** In Master mode, the overflow bit is not set since each new reception (and transmission) is initiated by writing to the SSPBUF register.

- bit 5 SSPEN: Synchronous Serial Port Enable bit
  - 1 = Enables serial port and configures SCK, SDO, SDI, and  $\overline{SS}$  as serial port pins
  - 0 = Disables serial port and configures these pins as I/O port pins

**Note:** When enabled, these pins must be properly configured as input or output.

- bit 4 **CKP:** Clock Polarity Select bit
  - 1 = IDLE state for clock is a high level
  - 0 = IDLE state for clock is a low level
- bit 3-0 SSPM3:SSPM0: Synchronous Serial Port Mode Select bits
  - $0101 = SPI Slave mode, clock = SCK pin, <math>\overline{SS}$  pin control disabled,  $\overline{SS}$  can be used as I/O pin
  - 0100 = SPI Slave mode, clock = SCK pin, SS pin control enabled
  - 0011 = SPI Master mode, clock = TMR2 output/2
  - 0010 = SPI Master mode, clock = Fosc/64
  - 0001 = SPI Master mode, clock = Fosc/16
  - 0000 = SPI Master mode, clock = Fosc/4

**Note:** Bit combinations not specifically listed here are either reserved, or implemented in I<sup>2</sup>C mode only.

## Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

- n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## PIC18FXX2

#### 15.3.2 OPERATION

When initializing the SPI, several options need to be specified. This is done by programming the appropriate control bits (SSPCON1<5:0>) and SSPSTAT<7:6>. These control bits allow the following to be specified:

- Master mode (SCK is the clock output)
- · Slave mode (SCK is the clock input)
- · Clock Polarity (IDLE state of SCK)
- Data input sample phase (middle or end of data output time)
- Clock edge (output data on rising/falling edge of SCK)
- Clock Rate (Master mode only)
- Slave Select mode (Slave mode only)

The MSSP consists of a transmit/receive Shift Register (SSPSR) and a buffer register (SSPBUF). The SSPSR shifts the data in and out of the device, MSb first. The SSPBUF holds the data that was written to the SSPSR, until the received data is ready. Once the 8 bits of data have been received, that byte is moved to the SSPBUF register. Then the buffer full detect bit, BF (SSPSTAT<0>), and the interrupt flag bit, SSPIF, are set. This double buffering of the received data (SSPBUF) allows the next byte to start reception before reading the data that was just received. Any write to the

SSPBUF register during transmission/reception of data will be ignored, and the write collision detect bit, WCOL (SSPCON1<7>), will be set. User software must clear the WCOL bit so that it can be determined if the following write(s) to the SSPBUF register completed successfully.

When the application software is expecting to receive valid data, the SSPBUF should be read before the next byte of data to transfer is written to the SSPBUF. Buffer full bit, BF (SSPSTAT<0>), indicates when SSPBUF has been loaded with the received data (transmission is complete). When the SSPBUF is read, the BF bit is cleared. This data may be irrelevant if the SPI is only a transmitter. Generally, the MSSP Interrupt is used to determine when the transmission/reception has completed. The SSPBUF must be read and/or written. If the interrupt method is not going to be used, then software polling can be done to ensure that a write collision does not occur. Example 15-1 shows the loading of the SSPBUF (SSPSR) for data transmission.

The SSPSR is not directly readable or writable, and can only be accessed by addressing the SSPBUF register. Additionally, the MSSP status register (SSPSTAT) indicates the various status conditions.

## **EXAMPLE 15-1: LOADING THE SSPBUF (SSPSR) REGISTER**

```
LOOP BTFSS SSPSTAT, BF ;Has data been received(transmit complete)?

BRA LOOP ;No

MOVF SSPBUF, W ;WREG reg = contents of SSPBUF

MOVWF RXDATA ;Save in user RAM, if data is meaningful

MOVF TXDATA, W ;W reg = contents of TXDATA

MOVWF SSPBUF ;New data to xmit
```

#### 15.3.3 ENABLING SPI I/O

To enable the serial port, SSP Enable bit, SSPEN (SSPCON1<5>), must be set. To reset or reconfigure SPI mode, clear the SSPEN bit, re-initialize the SSPCON registers, and then set the SSPEN bit. This configures the SDI, SDO, SCK, and SS pins as serial port pins. For the pins to behave as the serial port function, some must have their data direction bits (in the TRIS register) appropriately programmed. That is:

- · SDI is automatically controlled by the SPI module
- · SDO must have TRISC<5> bit cleared
- SCK (Master mode) must have TRISC<3> bit cleared
- SCK (Slave mode) must have TRISC<3> bit set
- SS must have TRISC<4> bit set


Any serial port function that is not desired may be overridden by programming the corresponding data direction (TRIS) register to the opposite value.

#### 15.3.4 TYPICAL CONNECTION

Figure 15-2 shows a typical connection between two microcontrollers. The master controller (Processor 1) initiates the data transfer by sending the SCK signal. Data is shifted out of both shift registers on their programmed clock edge, and latched on the opposite edge of the clock. Both processors should be programmed to the same Clock Polarity (CKP), then both controllers would send and receive data at the same time. Whether the data is meaningful (or dummy data) depends on the application software. This leads to three scenarios for data transmission:

- · Master sends data Slave sends dummy data
- · Master sends data Slave sends data
- Master sends dummy data Slave sends data





#### 15.3.5 MASTER MODE

The master can initiate the data transfer at any time because it controls the SCK. The master determines when the slave (Processor 2, Figure 15-2) is to broadcast data by the software protocol.

In Master mode, the data is transmitted/received as soon as the SSPBUF register is written to. If the SPI is only going to receive, the SDO output could be disabled (programmed as an input). The SSPSR register will continue to shift in the signal present on the SDI pin at the programmed clock rate. As each byte is received, it will be loaded into the SSPBUF register as if a normal received byte (interrupts and status bits appropriately set). This could be useful in receiver applications as a "Line Activity Monitor" mode.

The clock polarity is selected by appropriately programming the CKP bit (SSPCON1<4>). This then, would give waveforms for SPI communication as shown in


Figure 15-3, Figure 15-5, and Figure 15-6, where the MSB is transmitted first. In Master mode, the SPI clock rate (bit rate) is user programmable to be one of the following:

- Fosc/4 (or Tcy)
- Fosc/16 (or 4 Tcy)
- Fosc/64 (or 16 Tcy)
- · Timer2 output/2

This allows a maximum data rate (at 40 MHz) of 10.00 Mbps.

Figure 15-3 shows the waveforms for Master mode. When the CKE bit is set, the SDO data is valid before there is a clock edge on SCK. The change of the input sample is shown based on the state of the SMP bit. The time when the SSPBUF is loaded with the received data is shown.

FIGURE 15-3: SPI MODE WAVEFORM (MASTER MODE)



#### 15.3.6 SLAVE MODE

In Slave mode, the data is transmitted and received as the external clock pulses appear on SCK. When the last bit is latched, the SSPIF interrupt flag bit is set.

While in Slave mode, the external clock is supplied by the external clock source on the SCK pin. This external clock must meet the minimum high and low times as specified in the electrical specifications.

While in SLEEP mode, the slave can transmit/receive data. When a byte is received, the device will wake-up from sleep.

## 15.3.7 SLAVE SELECT SYNCHRONIZATION

The  $\overline{SS}$  pin allows a Synchronous Slave mode. The SPI must be in Slave mode with  $\overline{SS}$  pin control enabled (SSPCON1<3:0> = 04h). The pin must not be driven low for the  $\overline{SS}$  pin to function as an input. The Data Latch must be high. When the  $\overline{SS}$  pin is low, transmission and reception are enabled and the SDO pin is driven. When the  $\overline{SS}$  pin goes high, the SDO pin is no

longer driven, even if in the middle of a transmitted byte, and becomes a floating output. External pull-up/ pull-down resistors may be desirable, depending on the application.

- Note 1: When the SPI is in Slave mode with \$\overline{SS}\$ pin control enabled (SSPCON<3:0> = 0100), the SPI module will reset if the \$\overline{SS}\$ pin is set to VDD.
  - 2: If the SPI is used in Slave mode with CKE set, then the SS pin control must be enabled.

When the SPI module resets, the bit counter is forced to 0. This can be done by either forcing the  $\overline{SS}$  pin to a high level or clearing the SSPEN bit.

To emulate two-wire communication, the SDO pin can be connected to the SDI pin. When the SPI needs to operate as a receiver the SDO pin can be configured as an input. This disables transmissions from the SDO. The SDI can always be left as an input (SDI function), since it cannot create a bus conflict.






FIGURE 15-5: SPI MODE WAVEFORM (SLAVE MODE WITH CKE = 0)





FIGURE 15-6: SPI MODE WAVEFORM (SLAVE MODE WITH CKE = 1)



#### 15.3.8 SLEEP OPERATION

In Master mode, all module clocks are halted and the transmission/reception will remain in that state until the device wakes from SLEEP. After the device returns to Normal mode, the module will continue to transmit/receive data.

In Slave mode, the SPI transmit/receive shift register operates asynchronously to the device. This allows the device to be placed in SLEEP mode and data to be shifted into the SPI transmit/receive shift register. When all 8 bits have been received, the MSSP interrupt flag bit will be set and if enabled, will wake the device from SLEEP.

#### 15.3.9 EFFECTS OF A RESET

A RESET disables the MSSP module and terminates the current transfer.

#### 15.3.10 BUS MODE COMPATIBILITY

Table 15-1 shows the compatibility between the standard SPI modes and the states the CKP and CKE control bits.

TABLE 15-1: SPI BUS MODES

Standard SPI Mode	Control E	Bits State
Terminology	СКР	CKE
0, 0	0	1
0, 1	0	0
1, 0	1	1
1, 1	1	0

There is also a SMP bit which controls when the data is sampled.

TABLE 15-2: REGISTERS ASSOCIATED WITH SPI OPERATION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value of POR, BO		Valu All C RES	ther
INTCON	GIE/GIEH	PEIE/ GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 00	0x	0000	000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 00	00	0000	0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 00	00	0000	0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000 00	00	0000	0000
TRISC	PORTC Da	ta Directior	n Register						1111 11	11	1111	1111
SSPBUF	Synchronou	us Serial Po	ort Receive	Buffer/Tra	nsmit Regist	ter			xxxx xx	xx	uuuu	uuuu
SSPCON	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0	0000 00	00	0000	0000
TRISA	_	PORTA Data Direction Register						-111 11	11	-111	1111	
SSPSTAT	SMP	CKE	D/Ā	Р	S	R/W	UA	BF	0000 00	00	0000	0000

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the MSSP in SPI mode.

Note 1: The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18C2X2 devices; always maintain these bits clear.

## 15.4 I<sup>2</sup>C Mode


The MSSP module in I<sup>2</sup>C mode fully implements all master and slave functions (including general call support) and provides interrupts on START and STOP bits in hardware to determine a free bus (multi-master function). The MSSP module implements the Standard mode specifications, as well as 7-bit and 10-bit addressing.

Two pins are used for data transfer:

- · Serial clock (SCL) RC3/SCK/SCL
- · Serial data (SDA) RC4/SDI/SDA

The user must configure these pins as inputs or outputs through the TRISC<4:3> bits.

FIGURE 15-7: MSSP BLOCK DIAGRAM (I<sup>2</sup>C MODE)



#### 15.4.1 REGISTERS

The MSSP module has six registers for I<sup>2</sup>C operation. These are:

- MSSP Control Register1 (SSPCON1)
- MSSP Control Register2 (SSPCON2)
- · MSSP Status Register (SSPSTAT)
- Serial Receive/Transmit Buffer (SSPBUF)
- MSSP Shift Register (SSPSR) Not directly accessible
- MSSP Address Register (SSPADD)

SSPCON, SSPCON2 and SSPSTAT are the control and status registers in I<sup>2</sup>C mode operation. The SSPCON and SSPCON2 registers are readable and writable. The lower 6 bits of the SSPSTAT are read only. The upper two bits of the SSPSTAT are read/write.

SSPSR is the shift register used for shifting data in or out. SSPBUF is the buffer register to which data bytes are written to or read from.

SSPADD register holds the slave device address when the SSP is configured in I<sup>2</sup>C Slave mode. When the SSP is configured in Master mode, the lower seven bits of SSPADD act as the baud rate generator reload value.

In receive operations, SSPSR and SSPBUF together, create a double buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPBUF and the SSPIF interrupt is set.

During transmission, the SSPBUF is not double buffered. A write to SSPBUF will write to both SSPBUF and SSPSR.

## REGISTER 15-3: SSPSTAT: MSSP STATUS REGISTER (I<sup>2</sup>C MODE)

R/W-0	R/W-0	R-0	R-0	R-0	R-0	R-0	R-0
SMP	CKE	D/Ā	Р	S	R/W	UA	BF
bit 7							bit 0

bit 7 SMP: Slew Rate Control bit

In Master or Slave mode:

- 1 = Slew rate control disabled for Standard Speed mode (100 kHz and 1 MHz)
- 0 = Slew rate control enabled for High Speed mode (400 kHz)
- bit 6 CKE: SMBus Select bit

in Master or Slave mode:

- 1 = Enable SMBus specific inputs
- 0 = Disable SMBus specific inputs
- bit 5 D/A: Data/Address bit

In Master mode:

Reserved

In Slave mode:

- 1 = Indicates that the last byte received or transmitted was data
- 0 = Indicates that the last byte received or transmitted was address
- bit 4 P: STOP bit
  - 1 = Indicates that a STOP bit has been detected last
  - 0 = STOP bit was not detected last

**Note:** This bit is cleared on RESET and when SSPEN is cleared.

- bit 3 S: START bit
  - 1 = Indicates that a start bit has been detected last
  - 0 = START bit was not detected last

**Note:** This bit is cleared on RESET and when SSPEN is cleared.

bit 2 **R/W**: Read/Write bit Information (I<sup>2</sup>C mode only)

In Slave mode:

- 1 = Read
- 0 = Write

**Note:** This bit holds the R/W bit information following the last address match. This bit is only valid from the address match to the next START bit, STOP bit, or not ACK bit.

#### In Master mode:

- 1 = Transmit is in progress
- 0 = Transmit is not in progress

**Note:** ORing this bit with SEN, RSEN, PEN, RCEN, or ACKEN will indicate if the MSSP is in IDLE mode.

- bit 1 **UA:** Update Address (10-bit Slave mode only)
  - 1 = Indicates that the user needs to update the address in the SSPADD register
  - 0 = Address does not need to be updated
- bit 0 BF: Buffer Full Status bit

#### In Transmit mode:

- 1 = Receive complete, SSPBUF is full
- 0 = Receive not complete, SSPBUF is empty

#### In Receive mode:

- 1 = Data transmit in progress (does not include the ACK and STOP bits), SSPBUF is full
- 0 = Data transmit complete (does not include the ACK and STOP bits), SSPBUF is empty

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

- n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## REGISTER 15-4: SSPCON1: MSSP CONTROL REGISTER1 (I<sup>2</sup>C MODE)

| R/W-0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| WCOL  | SSPOV | SSPEN | CKP   | SSPM3 | SSPM2 | SSPM1 | SSPM0 |
| bit 7 | •     |       |       |       | •     |       | bit 0 |

#### bit 7 WCOL: Write Collision Detect bit

#### In Master Transmit mode:

- 1 = A write to the SSPBUF register was attempted while the  $I^2C$  conditions were not valid for a transmission to be started (must be cleared in software)
- 0 = No collision

#### In Slave Transmit mode:

- 1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)
- 0 = No collision

## In Receive mode (Master or Slave modes):

This is a "don't care" bit

#### bit 6 SSPOV: Receive Overflow Indicator bit

#### In Receive mode:

- 1 = A byte is received while the SSPBUF register is still holding the previous byte (must be cleared in software)
- 0 = No overflow

#### In Transmit mode:

This is a "don't care" bit in Transmit mode

- bit 5 SSPEN: Synchronous Serial Port Enable bit
  - 1 = Enables the serial port and configures the SDA and SCL pins as the serial port pins
  - 0 = Disables serial port and configures these pins as I/O port pins

Note: When enabled, the SDA and SCL pins must be properly configured as input or output.

#### bit 4 CKP: SCK Release Control bit

#### In Slave mode:

- 1 = Release clock
- 0 = Holds clock low (clock stretch), used to ensure data setup time

#### In Master mode:

Unused in this mode

#### bit 3-0 SSPM3:SSPM0: Synchronous Serial Port Mode Select bits

- 1111 = I<sup>2</sup>C Slave mode, 10-bit address with START and STOP bit interrupts enabled
- 1110 = I<sup>2</sup>C Slave mode, 7-bit address with START and STOP bit interrupts enabled
- 1011 = I<sup>2</sup>C Firmware Controlled Master mode (Slave IDLE)
- 1000 = I<sup>2</sup>C Master mode, clock = Fosc / (4 \* (SSPADD+1))
- $0111 = I^2C$  Slave mode, 10-bit address
- 0110 = I2C Slave mode, 7-bit address

**Note:** Bit combinations not specifically listed here are either reserved, or implemented in SPI mode only.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	, read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

## REGISTER 15-5: SSPCON2: MSSP CONTROL REGISTER 2 (I<sup>2</sup>C MODE)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN
bit 7							bit 0

- bit 7 GCEN: General Call Enable bit (Slave mode only)
  - 1 = Enable interrupt when a general call address (0000h) is received in the SSPSR
  - 0 = General call address disabled
- bit 6 ACKSTAT: Acknowledge Status bit (Master Transmit mode only)
  - 1 = Acknowledge was not received from slave
  - 0 = Acknowledge was received from slave
- bit 5 ACKDT: Acknowledge Data bit (Master Receive mode only)
  - 1 = Not Acknowledge
  - 0 = Acknowledge

**Note:** Value that will be transmitted when the user initiates an Acknowledge sequence at the end of a receive.

- bit 4 ACKEN: Acknowledge Sequence Enable bit (Master Receive mode only)
  - 1 = Initiate Acknowledge sequence on SDA and SCL pins, and transmit ACKDT data bit. Automatically cleared by hardware.
  - 0 = Acknowledge sequence IDLE
- bit 3 RCEN: Receive Enable bit (Master mode only)
  - 1 = Enables Receive mode for I2C
  - 0 = Receive IDLE
- bit 2 **PEN:** STOP Condition Enable bit (Master mode only)
  - 1 = Initiate STOP condition on SDA and SCL pins. Automatically cleared by hardware.
  - 0 = STOP condition IDLE
- bit 1 RSEN: Repeated START Condition Enabled bit (Master mode only)
  - 1 = Initiate Repeated START condition on SDA and SCL pins. Automatically cleared by hardware.
  - 0 = Repeated START condition IDLE
- bit 0 SEN: START Condition Enabled/Stretch Enabled bit

#### In Master mode:

- 1 = Initiate START condition on SDA and SCL pins. Automatically cleared by hardware.
- 0 = START condition IDLE

#### In Slave mode:

- 1 = Clock stretching is enabled for both Slave Transmit and Slave Receive (stretch enabled)
- 0 = Clock stretching is enabled for slave transmit only (Legacy mode)

**Note:** For bits ACKEN, RCEN, PEN, RSEN, SEN: If the I<sup>2</sup>C module is not in the IDLE mode, this bit may not be set (no spooling) and the SSPBUF may not be written (or writes to the SSPBUF are disabled).

Legend:				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'		
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

## PIC18FXX2

#### 15.4.2 OPERATION

The MSSP module functions are enabled by setting MSSP Enable bit, SSPEN (SSPCON<5>).

The SSPCON1 register allows control of the I<sup>2</sup>C operation. Four mode selection bits (SSPCON<3:0>) allow one of the following I<sup>2</sup>C modes to be selected:

- I<sup>2</sup>C Master mode, clock = OSC/4 (SSPADD +1)
- I<sup>2</sup>C Slave mode (7-bit address)
- I<sup>2</sup>C Slave mode (10-bit address)
- I<sup>2</sup>C Slave mode (7-bit address), with START and STOP bit interrupts enabled
- I<sup>2</sup>C Slave mode (10-bit address), with START and STOP bit interrupts enabled
- I<sup>2</sup>C Firmware controlled master operation, slave is IDLE

Selection of any I<sup>2</sup>C mode, with the SSPEN bit set, forces the SCL and SDA pins to be open drain, provided these pins are programmed to inputs by setting the appropriate TRISC bits. To guarantee proper operation of the module, pull-up resistors must be provided externally to the SCL and SDA pins.

#### 15.4.3 SLAVE MODE

In Slave mode, the SCL and SDA pins must be configured as inputs (TRISC<4:3> set). The MSSP module will override the input state with the output data when required (slave-transmitter).

The I<sup>2</sup>C Slave mode hardware will always generate an interrupt on an address match. Through the mode select bits, the user can also choose to interrupt on START and STOP bits

When an address is matched or the data transfer after an address match is received, the hardware automatically will generate the Acknowledge  $(\overline{ACK})$  pulse and load the SSPBUF register with the received value currently in the SSPSR register.

Any combination of the following conditions will cause the MSSP module not to give this  $\overline{\text{ACK}}$  pulse:

- The buffer full bit BF (SSPSTAT<0>) was set before the transfer was received.
- The overflow bit SSPOV (SSPCON<6>) was set before the transfer was received.

In this case, the SSPSR register value is not loaded into the SSPBUF, but bit SSPIF (PIR1<3>) is set. The BF bit is cleared by reading the SSPBUF register, while bit SSPOV is cleared through software.

The SCL clock input must have a minimum high and low for proper operation. The high and low times of the  $I^2C$  specification, as well as the requirement of the MSSP module, are shown in timing parameter 100 and parameter 101.

#### 15.4.3.1 Addressing

Once the MSSP module has been enabled, it waits for a START condition to occur. Following the START condition, the 8-bits are shifted into the SSPSR register. All incoming bits are sampled with the rising edge of the clock (SCL) line. The value of register SSPSR<7:1> is compared to the value of the SSPADD register. The address is compared on the falling edge of the eighth clock (SCL) pulse. If the addresses match, and the BF and SSPOV bits are clear, the following events occur:

- The SSPSR register value is loaded into the SSPBUF register.
- 2. The buffer full bit BF is set.
- 3. An ACK pulse is generated.
- MSSP interrupt flag bit, SSPIF (PIR1<3>) is set (interrupt is generated if enabled) on the falling edge of the ninth SCL pulse.

In 10-bit Address mode, two address bytes need to be received by the slave. The five Most Significant bits (MSbs) of the first address byte specify if this is a 10-bit address. Bit  $R/\overline{W}$  (SSPSTAT<2>) must specify a write so the slave device will receive the second address byte. For a 10-bit address, the first byte would equal '11110 A9 A8 0', where 'A9' and 'A8' are the two MSbs of the address. The sequence of events for 10-bit address is as follows, with steps 7 through 9 for the slave-transmitter:

- Receive first (high) byte of Address (bits SSPIF, BF and bit UA (SSPSTAT<1>) are set).
- Update the SSPADD register with second (low) byte of Address (clears bit UA and releases the SCL line).
- Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- Receive second (low) byte of Address (bits SSPIF, BF, and UA are set).
- Update the SSPADD register with the first (high) byte of Address. If match releases SCL line, this will clear bit UA.
- Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- 7. Receive Repeated START condition.
- Receive first (high) byte of Address (bits SSPIF and BF are set).
- Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.

#### 15.4.3.2 Reception

When the  $R/\overline{W}$  bit of the address byte is clear and an address match occurs, the  $R/\overline{W}$  bit of the SSPSTAT register is cleared. The received address is loaded into the SSPBUF register and the SDA line is held low  $(\overline{ACK})$ .

When the address byte overflow condition exists, then the no Acknowledge (ACK) pulse is given. An overflow condition is defined as either bit BF (SSPSTAT<0>) is set, or bit SSPOV (SSPCON1<6>) is set.

An MSSP interrupt is generated for each data transfer byte. Flag bit SSPIF (PIR1<3>) must be cleared in software. The SSPSTAT register is used to determine the status of the byte.


If SEN is enabled (SSPCON1<0>=1), RC3/SCK/SCL will be held low (clock stretch) following each data transfer. The clock must be released by setting bit CKP (SSPCON<4>). See Section 15.4.4 ("Clock Stretching"), for more detail.


#### 15.4.3.3 Transmission


When the R/W bit of the incoming address byte is set and an address match occurs, the R/W bit of the SSPSTAT register is set. The received address is loaded into the SSPBUF register. The ACK pulse will be sent on the ninth bit and pin RC3/SCK/SCL is held low, regardless of SEN (see "Clock Stretching", Section 15.4.4, for more detail). By stretching the clock, the master will be unable to assert another clock pulse until the slave is done preparing the transmit data. The transmit data must be loaded into the SSPBUF register, which also loads the SSPSR register. Then pin RC3/ SCK/SCL should be enabled by setting bit CKP (SSPCON1<4>). The eight data bits are shifted out on the falling edge of the SCL input. This ensures that the SDA signal is valid during the SCL high time (Figure 15-9).


The  $\overline{ACK}$  pulse from the master-receiver is latched on the rising edge of the ninth SCL input pulse. If the SDA line is high (not  $\overline{ACK}$ ), then the data transfer is complete. In this case, when the  $\overline{ACK}$  is latched by the slave, the slave logic is reset (resets SSPSTAT register) and the slave monitors for another occurrence of the START bit. If the SDA line was low  $(\overline{ACK})$ , the next transmit data must be loaded into the SSPBUF register. Again, pin RC3/SCK/SCL must be enabled by setting bit CKP.

An MSSP interrupt is generated for each data transfer byte. The SSPIF bit must be cleared in software and the SSPSTAT register is used to determine the status of the byte. The SSPIF bit is set on the falling edge of the ninth clock pulse.









#### 15.4.4 CLOCK STRETCHING

Both 7- and 10-bit Slave modes implement automatic clock stretching during a transmit sequence.

The SEN bit (SSPCON2<0>) allows clock stretching to be enabled during receives. Setting SEN will cause the SCL pin to be held low at the end of each data receive sequence.

## 15.4.4.1 Clock Stretching for 7-bit Slave Receive Mode (SEN = 1)

In 7-bit Slave Receive mode, on the falling edge of the ninth clock at the end of the  $\overline{ACK}$  sequence, if the BF bit is set, the CKP bit in the SSPCON1 register is automatically cleared, forcing the SCL output to be held low. The CKP being cleared to '0' will assert the SCL line low. The CKP bit must be set in the user's ISR before reception is allowed to continue. By holding the SCL line low, the user has time to service the ISR and read the contents of the SSPBUF before the master device can initiate another receive sequence. This will prevent buffer overruns from occurring (see Figure 15-13).

- Note 1: If the user reads the contents of the SSPBUF before the falling edge of the ninth clock, thus clearing the BF bit, the CKP bit will not be cleared and clock stretching will not occur.
  - 2: The CKP bit can be set in software, regardless of the state of the BF bit. The user should be careful to clear the BF bit in the ISR before the next receive sequence, in order to prevent an overflow condition.

#### 15.4.4.2 Clock Stretching for 10-bit Slave Receive Mode (SEN = 1)

In 10-bit Slave Receive mode, during the address sequence, clock stretching automatically takes place but CKP is not cleared. During this time, if the UA bit is set after the ninth clock, clock stretching is initiated. The UA bit is set after receiving the upper byte of the 10-bit address, and following the receive of the second byte of the 10-bit address with the  $R/\overline{W}$  bit cleared to '0'. The release of the clock line occurs upon updating SSPADD. Clock stretching will occur on each data receive sequence as described in 7-bit mode.

Note: If the user polls the UA bit and clears it by updating the SSPADD register before the falling edge of the ninth clock occurs, and if the user hasn't cleared the BF bit by reading the SSPBUF register before that time, then the CKP bit will still NOT be asserted low. Clock stretching on the basis of the state of the BF bit only occurs during a data sequence, not an address sequence.

#### 15.4.4.3 Clock Stretching for 7-bit Slave Transmit Mode

7-bit Slave Transmit mode implements clock stretching by clearing the CKP bit after the falling edge of the ninth clock, if the BF bit is clear. This occurs, regardless of the state of the SEN bit.

The user's ISR must set the CKP bit before transmission is allowed to continue. By holding the SCL line low, the user has time to service the ISR and load the contents of the SSPBUF before the master device can initiate another transmit sequence (see Figure 15-9).

- Note 1: If the user loads the contents of SSPBUF, setting the BF bit before the falling edge of the ninth clock, the CKP bit will not be cleared and clock stretching will not occur.
  - **2:** The CKP bit can be set in software, regardless of the state of the BF bit.


#### 15.4.4.4 Clock Stretching for 10-bit Slave Transmit Mode


In 10-bit Slave Transmit mode, clock stretching is controlled during the first two address sequences by the state of the UA bit, just as it is in 10-bit Slave Receive mode. The first two addresses are followed by a third address sequence, which contains the high order bits of the 10-bit address and the R/W bit set to '1'. After the third address sequence is performed, the UA bit is not set, the module is now configured in Transmit mode, and clock stretching is controlled by the BF flag, as in 7-bit Slave Transmit mode (see Figure 15-11).


# 15.4.4.5 Clock Synchronization and the CKP bit

If a user clears the CKP bit, the SCL output is forced to '0'. Setting the CKP bit will not assert the SCL output low until the SCL output is already sampled low. If the user attempts to drive SCL low, the CKP bit will not assert the SCL line until an external I<sup>2</sup>C master device has already asserted the SCL line. The SCL output will remain low until the CKP bit is set, and all other devices on the I<sup>2</sup>C bus have de-asserted SCL. This ensures that a write to the CKP bit will not violate the minimum high time requirement for SCL (see Figure 15-12).

FIGURE 15-12: CLOCK SYNCHRONIZATION TIMING







## 15.4.5 GENERAL CALL ADDRESS SUPPORT

The addressing procedure for the I<sup>2</sup>C bus is such that the first byte after the START condition usually determines which device will be the slave addressed by the master. The exception is the general call address, which can address all devices. When this address is used, all devices should, in theory, respond with an Acknowledge.

The general call address is one of eight addresses reserved for specific purposes by the  $I^2C$  protocol. It consists of all 0's with  $R/\overline{W} = 0$ .


The general call address is recognized when the General Call Enable bit (GCEN) is enabled (SSPCON2<7> set). Following a START bit detect, 8-bits are shifted into the SSPSR and the address is compared against the SSPADD. It is also compared to the general call address and fixed in hardware.

If the general call address matches, the SSPSR is transferred to the SSPBUF, the BF flag bit is set (eighth bit), and on the falling edge of the ninth bit ( $\overline{ACK}$  bit), the SSPIF interrupt flag bit is set.

When the interrupt is serviced, the source for the interrupt can be checked by reading the contents of the SSPBUF. The value can be used to determine if the address was device specific or a general call address.

In 10-bit mode, the SSPADD is required to be updated for the second half of the address to match, and the UA bit is set (SSPSTAT<1>). If the general call address is sampled when the GCEN bit is set, while the slave is configured in 10-bit Address mode, then the second half of the address is not necessary, the UA bit will not be set, and the slave will begin receiving data after the Acknowledge (Figure 15-15).

FIGURE 15-15: SLAVE MODE GENERAL CALL ADDRESS SEQUENCE (7 OR 10-BIT ADDRESS MODE)



#### 15.4.6 MASTER MODE

Master mode is enabled by setting and clearing the appropriate SSPM bits in SSPCON1 and by setting the SSPEN bit. In Master mode, the SCL and SDA lines are manipulated by the MSSP hardware.

Master mode of operation is supported by interrupt generation on the detection of the START and STOP conditions. The STOP (P) and START (S) bits are cleared from a RESET or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit is set or the bus is IDLE, with both the S and P bits clear

In Firmware Controlled Master mode, user code conducts all I<sup>2</sup>C bus operations based on START and STOP bit conditions.

Once Master mode is enabled, the user has six options.

- 1. Assert a START condition on SDA and SCL.
- Assert a Repeated START condition on SDA and SCL.
- Write to the SSPBUF register initiating transmission of data/address.
- 4. Configure the I<sup>2</sup>C port to receive data.
- 5. Generate an Acknowledge condition at the end of a received byte of data.
- 6. Generate a STOP condition on SDA and SCL.

The MSSP Module, when configured in I<sup>2</sup>C Master mode, does not allow queueing of events. For instance, the user is not allowed to initiate a START condition and immediately write the SSPBUF register to initiate transmission before the START condition is complete. In this case, the SSPBUF will not be written to and the WCOL bit will be set, indicating that a write to the SSPBUF did not occur.


The following events will cause SSP interrupt flag bit, SSPIF, to be set (SSP interrupt if enabled):

START condition

Note:

- · STOP condition
- Data transfer byte transmitted/received
- · Acknowledge Transmit
- · Repeated START

FIGURE 15-16: MSSP BLOCK DIAGRAM (I<sup>2</sup>C MASTER MODE)



## PIC18FXX2

## 15.4.6.1 I<sup>2</sup>C Master Mode Operation

The master device generates all of the serial clock pulses and the START and STOP conditions. A transfer is ended with a STOP condition or with a Repeated START condition. Since the Repeated START condition is also the beginning of the next serial transfer, the  $I^2$ C bus will not be released.

In Master Transmitter mode, serial data is output through SDA, while SCL outputs the serial clock. The first byte transmitted contains the slave address of the receiving device (7 bits) and the Read/Write (R/W) bit. In this case, the R/W bit will be logic '0'. Serial data is transmitted 8 bits at a time. After each byte is transmitted, an Acknowledge bit is received. START and STOP conditions are output to indicate the beginning and the end of a serial transfer.

In Master Receive mode, the first byte transmitted contains the slave address of the transmitting device (7 bits) and the  $R/\overline{W}$  bit. In this case, the  $R/\overline{W}$  bit will be logic '1'. Thus, the first byte transmitted is a 7-bit slave address followed by a '1' to indicate receive bit. Serial data is received via SDA, while SCL outputs the serial clock. Serial data is received 8 bits at a time. After each byte is received, an Acknowledge bit is transmitted. START and STOP conditions indicate the beginning and end of transmission.

The baud rate generator used for the SPI mode operation is used to set the SCL clock frequency for either 100 kHz, 400 kHz or 1 MHz I<sup>2</sup>C operation. See Section 15.4.7 ("Baud Rate Generator"), for more detail.

A typical transmit sequence would go as follows:

- The user generates a START condition by setting the START enable bit, SEN (SSPCON2<0>).
- SSPIF is set. The MSSP module will wait the required start time before any other operation takes place.
- The user loads the SSPBUF with the slave address to transmit.
- Address is shifted out the SDA pin until all 8 bits are transmitted.
- The MSSP Module shifts in the ACK bit from the slave device and writes its value into the SSPCON2 register (SSPCON2<6>).
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF bit.
- The user loads the SSPBUF with eight bits of data.
- Data is shifted out the SDA pin until all 8 bits are transmitted.
- The MSSP Module shifts in the ACK bit from the slave device and writes its value into the SSPCON2 register (SSPCON2<6>).
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF bit
- 11. The user generates a STOP condition by setting the STOP enable bit PEN (SSPCON2<2>).
- Interrupt is generated once the STOP condition is complete.

#### 15.4.7 BAUD RATE GENERATOR

In I<sup>2</sup>C Master mode, the baud rate generator (BRG) reload value is placed in the lower 7 bits of the SSPADD register (Figure 15-17). When a write occurs to SSPBUF, the baud rate generator will automatically begin counting. The BRG counts down to 0 and stops until another reload has taken place. The BRG count is decremented twice per instruction cycle (TCY) on the Q2 and Q4 clocks. In I<sup>2</sup>C Master mode, the BRG is reloaded automatically.

Once the given operation is complete (i.e., transmission of the last data bit is followed by  $\overline{ACK}$ ), the internal clock will automatically stop counting and the SCL pin will remain in its last state.

Table 15-3 demonstrates clock rates based on instruction cycles and the BRG value loaded into SSPADD.

FIGURE 15-17: BAUD RATE GENERATOR BLOCK DIAGRAM




TABLE 15-3: I<sup>2</sup>C CLOCK RATE W/BRG

Fcy	Fcy*2	BRG Value	F <sub>SCL</sub> <sup>(2)</sup> (2 Rollovers of BRG)
10 MHz	20 MHz	19h	400 kHz <sup>(1)</sup>
10 MHz	20 MHz	20h	312.5 kHz
10 MHz	20 MHz	3Fh	100 kHz
4 MHz	8 MHz	0Ah	400 kHz <sup>(1)</sup>
4 MHz	8 MHz	0Dh	308 kHz
4 MHz	8 MHz	28h	100 kHz
1 MHz	2 MHz	03h	333 kHz <sup>(1)</sup>
1 MHz	2 MHz	0Ah	100kHz
1 MHz	2 MHz	00h	1 MHz <sup>(1)</sup>

**Note 1:** The I<sup>2</sup>C interface does not conform to the 400 kHz I<sup>2</sup>C specification (which applies to rates greater than 100 kHz) in all details, but may be used with care where higher rates are required by the application.


2: Actual frequency will depend on bus conditions. Theoretically, bus conditions will add rise time and extend low time of clock period, producing the effective frequency.

#### 15.4.7.1 Clock Arbitration

Clock arbitration occurs when the master, during any receive, transmit or Repeated START/STOP condition, de-asserts the SCL pin (SCL allowed to float high). When the SCL pin is allowed to float high, the baud rate generator (BRG) is suspended from counting until the SCL pin is actually sampled high. When the SCL pin is

sampled high, the baud rate generator is reloaded with the contents of SSPADD<6:0> and begins counting. This ensures that the SCL high time will always be at least one BRG rollover count, in the event that the clock is held low by an external device (Figure 15-18).

FIGURE 15-18: BAUD RATE GENERATOR TIMING WITH CLOCK ARBITRATION



# 15.4.8 I<sup>2</sup>C MASTER MODE START CONDITION TIMING

To initiate a START condition, the user sets the START condition enable bit, SEN (SSPCON2<0>). If the SDA and SCL pins are sampled high, the baud rate generator is reloaded with the contents of SSPADD<6:0> and starts its count. If SCL and SDA are both sampled high when the baud rate generator times out (TBRG), the SDA pin is driven low. The action of the SDA being driven low, while SCL is high, is the START condition and causes the S bit (SSPSTAT<3>) to be set. Following this, the baud rate generator is reloaded with the contents of SSPADD<6:0> and resumes its count. When the baud rate generator times out (TBRG), the SEN bit (SSPCON2<0>) will be automatically cleared by hardware, the baud rate generator is suspended, leaving the SDA line held low and the START condition is complete.

Note:


If at the beginning of the START condition, the SDA and SCL pins are already sampled low, or if during the START condition the SCL line is sampled low before the SDA line is driven low, a bus collision occurs, the Bus Collision Interrupt Flag, BCLIF is set, the START condition is aborted, and the I<sup>2</sup>C module is reset into its IDLE state.

#### 15.4.8.1 WCOL Status Flag

If the user writes the SSPBUF when a START sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

**Note:** Because queueing of events is not allowed, writing to the lower 5 bits of SSPCON2 is disabled until the START condition is complete.

#### FIGURE 15-19: FIRST START BIT TIMING



## 15.4.9 I<sup>2</sup>C MASTER MODE REPEATED START CONDITION TIMING

A Repeated START condition occurs when the RSEN bit (SSPCON2<1>) is programmed high and the I2C logic module is in the IDLE state. When the RSEN bit is set, the SCL pin is asserted low. When the SCL pin is sampled low, the baud rate generator is loaded with the contents of SSPADD<5:0> and begins counting. The SDA pin is released (brought high) for one baud rate generator count (TBRG). When the baud rate generator times out, if SDA is sampled high, the SCL pin will be de-asserted (brought high). When SCL is sampled high, the baud rate generator is reloaded with the contents of SSPADD<6:0> and begins counting. SDA and SCL must be sampled high for one TBRG. This action is then followed by assertion of the SDA pin (SDA = 0) for one TBRG while SCL is high. Following this, the RSEN bit (SSPCON2<1>) will be automatically cleared and the baud rate generator will not be reloaded, leaving the SDA pin held low. As soon as a START condition is detected on the SDA and SCL pins, the S bit (SSPSTAT<3>) will be set. The SSPIF bit will not be set until the baud rate generator has timed out.

Note 1: If RSEN is programmed while any other event is in progress, it will not take effect.

- 2: A bus collision during the Repeated START condition occurs if:
  - SDA is sampled low when SCL goes from low to high.
  - SCL goes low before SDA is asserted low. This may indicate that another master is attempting to transmit a data "1".

Immediately following the SSPIF bit getting set, the user may write the SSPBUF with the 7-bit address in 7-bit mode, or the default first address in 10-bit mode. After the first eight bits are transmitted and an ACK is received, the user may then transmit an additional eight bits of address (10-bit mode) or eight bits of data (7-bit mode).


#### 15.4.9.1 WCOL Status Flag

Note:

If the user writes the SSPBUF when a Repeated START sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

Because queueing of events is not allowed, writing of the lower 5 bits of SSPCON2 is disabled until the Repeated START condition is complete.

#### FIGURE 15-20: REPEAT START CONDITION WAVEFORM



## 15.4.10 I<sup>2</sup>C MASTER MODE TRANSMISSION

Transmission of a data byte, a 7-bit address, or the other half of a 10-bit address is accomplished by simply writing a value to the SSPBUF register. This action will set the buffer full flag bit, BF, and allow the baud rate generator to begin counting and start the next transmission. Each bit of address/data will be shifted out onto the SDA pin after the falling edge of SCL is asserted (see data hold time specification parameter 106). SCL is held low for one baud rate generator rollover count (TBRG). Data should be valid before SCL is released high (see data setup time specification parameter 107). When the SCL pin is released high, it is held that way for TBRG. The data on the SDA pin must remain stable for that duration and some hold time after the next falling edge of SCL. After the eighth bit is shifted out (the falling edge of the eighth clock), the BF flag is cleared and the master releases SDA. This allows the slave device being addressed to respond with an ACK bit during the ninth bit time if an address match occurred or if data was received properly. The status of ACK is written into the ACKDT bit on the falling edge of the ninth clock. If the master receives an Acknowledge, the Acknowledge status bit. ACKSTAT, is cleared. If not. the bit is set. After the ninth clock, the SSPIF bit is set and the master clock (baud rate generator) is suspended until the next data byte is loaded into the SSPBUF, leaving SCL low and SDA unchanged (Figure 15-21).

After the write to the SSPBUF, each bit of address will be shifted out on the falling edge of SCL until all seven address bits and the R/W bit are completed. On the falling edge of the eighth clock, the master will de-assert the SDA pin, allowing the slave to respond with an Acknowledge. On the falling edge of the ninth clock, the master will sample the SDA pin to see if the address was recognized by a slave. The status of the ACK bit is loaded into the ACKSTAT status bit (SSPCON2<6>). Following the falling edge of the ninth clock transmission of the address, the SSPIF is set, the BF flag is cleared and the baud rate generator is turned off until another write to the SSPBUF takes place, holding SCL low and allowing SDA to float.

#### 15.4.10.1 BF Status Flag

In Transmit mode, the BF bit (SSPSTAT<0>) is set when the CPU writes to SSPBUF and is cleared when all 8 bits are shifted out.

#### 15.4.10.2 WCOL Status Flag

If the user writes the SSPBUF when a transmit is already in progress (i.e., SSPSR is still shifting out a data byte), the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

WCOL must be cleared in software.

#### 15.4.10.3 ACKSTAT Status Flag

In Transmit mode, the ACKSTAT bit (SSPCON2<6>) is cleared when the slave has sent an Acknowledge ( $\overline{ACK} = 0$ ), and is set when the slave does not Acknowledge ( $\overline{ACK} = 1$ ). A slave sends an Acknowledge when it has recognized its address (including a general call) or when the slave has properly received its data.

#### 15.4.11 I<sup>2</sup>C MASTER MODE RECEPTION

Master mode reception is enabled by programming the receive enable bit, RCEN (SSPCON2<3>).

**Note:** In the MSSP module, the RCEN bit must be set after the ACK sequence or the RCEN bit will be disregarded.

The baud rate generator begins counting, and on each rollover, the state of the SCL pin changes (high to low/ low to high) and data is shifted into the SSPSR. After the falling edge of the eighth clock, the receive enable flag is automatically cleared, the contents of the SSPSR are loaded into the SSPBUF, the BF flag bit is set, the SSPIF flag bit is set and the baud rate generator is suspended from counting, holding SCL low. The MSSP is now in IDLE state, awaiting the next command. When the buffer is read by the CPU, the BF flag bit is automatically cleared. The user can then send an Acknowledge bit at the end of reception, by setting the Acknowledge sequence enable bit, **ACKEN** (SSPCON2<4>).

#### 15.4.11.1 BF Status Flag


In receive operation, the BF bit is set when an address or data byte is loaded into SSPBUF from SSPSR. It is cleared when the SSPBUF register is read.


#### 15.4.11.2 SSPOV Status Flag

In receive operation, the SSPOV bit is set when 8 bits are received into the SSPSR and the BF flag bit is already set from a previous reception.

#### 15.4.11.3 WCOL Status Flag

If the user writes the SSPBUF when a receive is already in progress (i.e., SSPSR is still shifting in a data byte), the WCOL bit is set and the contents of the buffer are unchanged (the write doesn't occur).





## 15.4.12 ACKNOWLEDGE SEQUENCE TIMING

An Acknowledge sequence is enabled by setting the Acknowledge sequence enable bit. **ACKEN** (SSPCON2<4>). When this bit is set, the SCL pin is pulled low and the contents of the Acknowledge data bit are presented on the SDA pin. If the user wishes to generate an Acknowledge, then the ACKDT bit should be cleared. If not, the user should set the ACKDT bit before starting an Acknowledge sequence. The baud rate generator then counts for one rollover period (TBRG) and the SCL pin is de-asserted (pulled high). When the SCL pin is sampled high (clock arbitration), the baud rate generator counts for TBRG. The SCL pin is then pulled low. Following this, the ACKEN bit is automatically cleared, the baud rate generator is turned off and the MSSP module then goes into IDLE mode (Figure 15-23).

#### 15.4.12.1 WCOL Status Flag

If the user writes the SSPBUF when an Acknowledge sequence is in progress, then WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).


#### 15.4.13 STOP CONDITION TIMING

A STOP bit is asserted on the SDA pin at the end of a receive/transmit by setting the STOP sequence enable bit, PEN (SSPCON2<2>). At the end of a receive/transmit the SCL line is held low after the falling edge of the ninth clock. When the PEN bit is set, the master will assert the SDA line low. When the SDA line is sampled low, the baud rate generator is reloaded and counts down to 0. When the baud rate generator times out, the SCL pin will be brought high, and one TBRG (baud rate generator rollover count) later, the SDA pin will be de-asserted. When the SDA pin is sampled high while SCL is high, the P bit (SSPSTAT<4>) is set. A TBRG later, the PEN bit is cleared and the SSPIF bit is set (Figure 15-24).


#### 15.4.13.1 WCOL Status Flag

If the user writes the SSPBUF when a STOP sequence is in progress, then the WCOL bit is set and the contents of the buffer are unchanged (the write doesn't occur).

#### FIGURE 15-23: ACKNOWLEDGE SEQUENCE WAVEFORM



#### FIGURE 15-24: STOP CONDITION RECEIVE OR TRANSMIT MODE



#### 15.4.14 SLEEP OPERATION

While in SLEEP mode, the I<sup>2</sup>C module can receive addresses or data, and when an address match or complete byte transfer occurs, wake the processor from SLEEP (if the MSSP interrupt is enabled).

#### 15.4.15 EFFECT OF A RESET

A RESET disables the MSSP module and terminates the current transfer.

#### 15.4.16 MULTI-MASTER MODE

In Multi-Master mode, the interrupt generation on the detection of the START and STOP conditions allows the determination of when the bus is free. The STOP (P) and START (S) bits are cleared from a RESET or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit (SSPSTAT<4>) is set, or the bus is idle with both the S and P bits clear. When the bus is busy, enabling the SSP interrupt will generate the interrupt when the STOP condition occurs.

In multi-master operation, the SDA line must be monitored for arbitration, to see if the signal level is the expected output level. This check is performed in hardware, with the result placed in the BCLIF bit.

The states where arbitration can be lost are:

- · Address Transfer
- Data Transfer
- · A START Condition
- · A Repeated START Condition
- · An Acknowledge Condition

#### 15.4.17 MULTI -MASTER COMMUNICATION, BUS COLLISION, AND BUS ARBITRATION

Multi-Master mode support is achieved by bus arbitration. When the master outputs address/data bits onto the SDA pin, arbitration takes place when the master outputs a '1' on SDA, by letting SDA float high and another master asserts a '0'. When the SCL pin floats high, data should be stable. If the expected data on SDA is a '1' and the data sampled on the SDA pin = '0', then a bus collision has taken place. The master will set the Bus Collision Interrupt Flag BCLIF and reset the I<sup>2</sup>C port to its IDLE state (Figure 15-25).

If a transmit was in progress when the bus collision occurred, the transmission is halted, the BF flag is cleared, the SDA and SCL lines are de-asserted, and the SSPBUF can be written to. When the user services the bus collision Interrupt Service Routine, and if the I<sup>2</sup>C bus is free, the user can resume communication by asserting a START condition.


If a START, Repeated START, STOP, or Acknowledge condition was in progress when the bus collision occurred, the condition is aborted, the SDA and SCL lines are de-asserted, and the respective control bits in the SSPCON2 register are cleared. When the user services the bus collision Interrupt Service Routine, and if the I<sup>2</sup>C bus is free, the user can resume communication by asserting a START condition.

The master will continue to monitor the SDA and SCL pins. If a STOP condition occurs, the SSPIF bit will be set.

A write to the SSPBUF will start the transmission of data at the first data bit, regardless of where the transmitter left off when the bus collision occurred.

In Multi-Master mode, the interrupt generation on the detection of START and STOP conditions allows the determination of when the bus is free. Control of the I<sup>2</sup>C bus can be taken when the P bit is set in the SSPSTAT register, or the bus is IDLE and the S and P bits are cleared.

FIGURE 15-25: BUS COLLISION TIMING FOR TRANSMIT AND ACKNOWLEDGE



## 15.4.17.1 Bus Collision During a START Condition

During a START condition, a bus collision occurs if:

- a) SDA or SCL are sampled low at the beginning of the START condition (Figure 15-26).
- SCL is sampled low before SDA is asserted low (Figure 15-27).

During a START condition, both the SDA and the SCL pins are monitored.

If the SDA pin is already low, or the SCL pin is already low, then all of the following occur:

- · the START condition is aborted,
- · the BCLIF flag is set, and
- the MSSP module is reset to its IDLE state (Figure 15-26).

The START condition begins with the SDA and SCL pins de-asserted. When the SDA pin is sampled high, the baud rate generator is loaded from SSPADD<6:0> and counts down to 0. If the SCL pin is sampled low while SDA is high, a bus collision occurs, because it is assumed that another master is attempting to drive a data '1' during the START condition.

If the SDA pin is sampled low during this count, the BRG is reset and the SDA line is asserted early (Figure 15-28). If, however, a '1' is sampled on the SDA pin, the SDA pin is asserted low at the end of the BRG count. The baud rate generator is then reloaded and counts down to 0, and during this time, if the SCL pins are sampled as '0', a bus collision does not occur. At the end of the BRG count, the SCL pin is asserted low.

Note:

The reason that bus collision is not a factor during a START condition is that no two bus masters can assert a START condition at the exact same time. Therefore, one master will always assert SDA before the other. This condition does not cause a bus collision, because the two masters must be allowed to arbitrate the first address following the START condition. If the address is the same, arbitration must be allowed to continue into the data portion, Repeated START or STOP conditions.

#### FIGURE 15-26: BUS COLLISION DURING START CONDITION (SDA ONLY)




FIGURE 15-27: BUS COLLISION DURING START CONDITION (SCL = 0)





FIGURE 15-28: BRG RESET DUE TO SDA ARBITRATION DURING START CONDITION



## PIC18FXX2

## 15.4.17.2 Bus Collision During a Repeated START Condition

During a Repeated START condition, a bus collision occurs if:

- a) A low level is sampled on SDA when SCL goes from low level to high level.
- SCL goes low before SDA is asserted low, indicating that another master is attempting to transmit a data '1'.

When the user de-asserts SDA and the pin is allowed to float high, the BRG is loaded with SSPADD<6:0> and counts down to 0. The SCL pin is then de-asserted, and when sampled high, the SDA pin is sampled.

If SDA is low, a bus collision has occurred (i.e., another master is attempting to transmit a data '0', Figure 15-29). If SDA is sampled high, the BRG is

reloaded and begins counting. If SDA goes from high to low before the BRG times out, no bus collision occurs because no two masters can assert SDA at exactly the same time.

If SCL goes from high to low before the BRG times out and SDA has not already been asserted, a bus collision occurs. In this case, another master is attempting to transmit a data '1' during the Repeated START condition, Figure 15-30.

If, at the end of the BRG time-out both SCL and SDA are still high, the SDA pin is driven low and the BRG is reloaded and begins counting. At the end of the count, regardless of the status of the SCL pin, the SCL pin is driven low and the Repeated START condition is complete.

FIGURE 15-29: BUS COLLISION DURING A REPEATED START CONDITION (CASE 1)





FIGURE 15-30: BUS COLLISION DURING REPEATED START CONDITION (CASE 2)



## 15.4.17.3 Bus Collision During a STOP Condition

Bus collision occurs during a STOP condition if:

- After the SDA pin has been de-asserted and allowed to float high, SDA is sampled low after the BRG has timed out.
- b) After the SCL pin is de-asserted, SCL is sampled low before SDA goes high.

The STOP condition begins with SDA asserted low. When SDA is sampled low, the SCL pin is allowed to float. When the pin is sampled high (clock arbitration), the baud rate generator is loaded with SSPADD<6:0> and counts down to 0. After the BRG times out, SDA is sampled. If SDA is sampled low, a bus collision has occurred. This is due to another master attempting to drive a data '0' (Figure 15-31). If the SCL pin is sampled low before SDA is allowed to float high, a bus collision occurs. This is another case of another master attempting to drive a data '0' (Figure 15-32).

FIGURE 15-31: BUS COLLISION DURING A STOP CONDITION (CASE 1)





FIGURE 15-32: BUS COLLISION DURING A STOP CONDITION (CASE 2)



# PIC18FXX2

**NOTES:** 

# 16.0 ADDRESSABLE UNIVERSAL SYNCHRONOUS ASYNCHRONOUS RECEIVER TRANSMITTER (USART)

The Universal Synchronous Asynchronous Receiver Transmitter (USART) module is one of the two serial I/O modules. (USART is also known as a Serial Communications Interface or SCI.) The USART can be configured as a full duplex asynchronous system that can communicate with peripheral devices, such as CRT terminals and personal computers, or it can be configured as a half-duplex synchronous system that can communicate with peripheral devices, such as A/D or D/A integrated circuits, serial EEPROMs, etc.

The USART can be configured in the following modes:

- Asynchronous (full-duplex)
- Synchronous Master (half-duplex)
- Synchronous Slave (half-duplex)

In order to configure pins RC6/TX/CK and RC7/RX/DT as the Universal Synchronous Asynchronous Receiver Transmitter:

- bit SPEN (RCSTA<7>) must be set (= 1),
- bit TRISC<6> must be cleared (= 0), and
- bit TRISC<7> must be set (=1).

Register 16-1 shows the Transmit Status and Control Register (TXSTA) and Register 16-2 shows the Receive Status and Control Register (RCSTA).

#### REGISTER 16-1: TXSTA: TRANSMIT STATUS AND CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0	R-1	R/W-0
CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D
bit 7							bit 0

bit 7 CSRC: Clock Source Select bit

Asynchronous mode:

Don't care

Synchronous mode:

1 = Master mode (clock generated internally from BRG)

0 = Slave mode (clock from external source)

bit 6 TX9: 9-bit Transmit Enable bit

1 = Selects 9-bit transmission

0 = Selects 8-bit transmission

bit 5 TXEN: Transmit Enable bit

1 = Transmit enabled

0 = Transmit disabled

Note: SREN/CREN overrides TXEN in SYNC mode.

bit 4 SYNC: USART Mode Select bit

1 = Synchronous mode

0 = Asynchronous mode

bit 3 Unimplemented: Read as '0'

bit 2 BRGH: High Baud Rate Select bit

Asynchronous mode:

1 = High speed

0 = Low speed

Synchronous mode:

Unused in this mode

bit 1 TRMT: Transmit Shift Register Status bit

1 = TSR empty

0 = TSR full

bit 0 **TX9D:** 9th bit of Transmit Data

Can be Address/Data bit or a parity bit.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

- n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### REGISTER 16-2: RCSTA: RECEIVE STATUS AND CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-0	R-0	R-x
SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D
bit 7							bit 0

bit 7 SPEN: Serial Port Enable bit

1 = Serial port enabled (configures RX/DT and TX/CK pins as serial port pins)

0 = Serial port disabled

bit 6 RX9: 9-bit Receive Enable bit

1 = Selects 9-bit reception

0 = Selects 8-bit reception

bit 5 SREN: Single Receive Enable bit

Asynchronous mode:

Don't care

Synchronous mode - Master:

1 = Enables single receive

0 = Disables single receive

This bit is cleared after reception is complete.

Synchronous mode - Slave:

Don't care

bit 4 CREN: Continuous Receive Enable bit

Asynchronous mode:

1 = Enables receiver

0 = Disables receiver

Synchronous mode:

1 = Enables continuous receive until enable bit CREN is cleared (CREN overrides SREN)

0 = Disables continuous receive

bit 3 ADDEN: Address Detect Enable bit

Asynchronous mode 9-bit (RX9 = 1):

1 = Enables address detection, enable interrupt and load of the receive buffer when RSR<8> is set

0 = Disables address detection, all bytes are received, and ninth bit can be used as parity bit

bit 2 **FERR**: Framing Error bit

1 = Framing error (can be updated by reading RCREG register and receive next valid byte)

0 = No framing error

bit 1 **OERR**: Overrun Error bit

1 = Overrun error (can be cleared by clearing bit CREN)

0 = No overrun error

bit 0 RX9D: 9th bit of Received Data

This can be Address/Data bit or a parity bit, and must be calculated by user firmware.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

# 16.1 USART Baud Rate Generator (BRG)

The BRG supports both the Asynchronous and Synchronous modes of the USART. It is a dedicated 8-bit baud rate generator. The SPBRG register controls the period of a free running 8-bit timer. In Asynchronous mode, bit BRGH (TXSTA<2>) also controls the baud rate. In Synchronous mode, bit BRGH is ignored. Table 16-1 shows the formula for computation of the baud rate for different USART modes, which only apply in Master mode (internal clock).

Given the desired baud rate and Fosc, the nearest integer value for the SPBRG register can be calculated using the formula in Table 16-1. From this, the error in baud rate can be determined.

Example 16-1 shows the calculation of the baud rate error for the following conditions:

- Fosc = 16 MHz
- Desired Baud Rate = 9600
- BRGH = 0
- SYNC = 0

It may be advantageous to use the high baud rate (BRGH = 1) even for slower baud clocks. This is because the Fosc/(16(X + 1)) equation can reduce the baud rate error in some cases.

Writing a new value to the SPBRG register causes the BRG timer to be reset (or cleared). This ensures the BRG does not wait for a timer overflow before outputting the new baud rate.

#### 16.1.1 SAMPLING

The data on the RC7/RX/DT pin is sampled three times by a majority detect circuit to determine if a high or a low level is present at the RX pin.

#### **EXAMPLE 16-1: CALCULATING BAUD RATE ERROR**

EXAMPLE 16-1:	CALCULATING BAUD RATE ERROR
Desired Baud Rate	= Fosc / (64 (X + 1))
Solving for X:	
X X X	= ((Fosc / Desired Baud Rate) / 64) - 1 = ((16000000 / 9600) / 64) - 1 = [25.042] = 25
Calculated Baud Rate	= 16000000 / (64 (25 + 1)) = 9615
Error	= (Calculated Baud Rate – Desired Baud Rate) Desired Baud Rate = (9615 – 9600) / 9600 = 0.16%

#### TABLE 16-1: BAUD RATE FORMULA

SYNC	BRGH = 0 (Low Speed)	BRGH = 1 (High Speed)
0	(Asynchronous) Baud Rate = Fosc/(64(X+1))	Baud Rate = Fosc/(16(X+1))
1	(Synchronous) Baud Rate = FOSC/(4(X+1))	N/A

Legend: X = value in SPBRG (0 to 255)

#### TABLE 16-2: REGISTERS ASSOCIATED WITH BAUD RATE GENERATOR

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 -00x	0000 -00x
SPBRG	Baud Ra		0000 0000	0000 0000						

Legend: x = unknown, - = unimplemented, read as '0'. Shaded cells are not used by the BRG.

TABLE 16-3: BAUD RATES FOR SYNCHRONOUS MODE

BAUD	Fosc =	40 MHz	SPBRG	33 MHz SPBRG		25	ИHz	SPBRG	20 MHz		SPBRG	
(Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-
2.4	NA	-	-	NA	-	-	NA	-	-	NA	-	-
9.6	NA	-	-	NA	-	-	NA	-	-	NA	-	-
19.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-
76.8	76.92	+0.16	129	77.10	+0.39	106	77.16	+0.47	80	76.92	+0.16	64
96	96.15	+0.16	103	95.93	-0.07	85	96.15	+0.16	64	96.15	+0.16	51
300	303.03	+1.01	32	294.64	-1.79	27	297.62	-0.79	20	294.12	-1.96	16
500	500	0	19	485.30	-2.94	16	480.77	-3.85	12	500	0	9
HIGH	10000	-	0	8250	-	0	6250	-	0	5000	-	0
LOW	39.06	-	255	32.23	-	255	24.41	-	255	19.53	-	255

BAUD	Fosc =	16 MHz	SPBRG	10 MHz		SPBRG	7.1590	9 MHz	SPBRG	5.0688 MHz		SPBRG
(Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-
2.4	NA	-	-	NA	-	-	NA	-	-	NA	-	-
9.6	NA	-	-	NA	-	-	9.62	+0.23	185	9.60	0	131
19.2	19.23	+0.16	207	19.23	+0.16	129	19.24	+0.23	92	19.20	0	65
76.8	76.92	+0.16	51	75.76	-1.36	32	77.82	+1.32	22	74.54	-2.94	16
96	95.24	-0.79	41	96.15	+0.16	25	94.20	-1.88	18	97.48	+1.54	12
300	307.70	+2.56	12	312.50	+4.17	7	298.35	-0.57	5	316.80	+5.60	3
500	500	0	7	500	0	4	447.44	-10.51	3	422.40	-15.52	2
HIGH	4000	-	0	2500	-	0	1789.80	-	0	1267.20	-	0
LOW	15.63	-	255	9.77	-	255	6.99	-	255	4.95	-	255

BAUD	Fosc =	4 MHz	SPBRG	3.579545 MHz		SPBRG	1 N	MHz	SPBRG	32.768 kHz		SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	0.30	+1.14	26
1.2	NA	-	-	NA	-	-	1.20	+0.16	207	1.17	-2.48	6
2.4	NA	-	-	NA	-	-	2.40	+0.16	103	2.73	+13.78	2
9.6	9.62	+0.16	103	9.62	+0.23	92	9.62	+0.16	25	8.20	-14.67	0
19.2	19.23	+0.16	51	19.04	-0.83	46	19.23	+0.16	12	NA	-	-
76.8	76.92	+0.16	12	74.57	-2.90	11	83.33	+8.51	2	NA	-	-
96	1000	+4.17	9	99.43	+3.57	8	83.33	-13.19	2	NA	-	-
300	333.33	+11.11	2	298.30	-0.57	2	250	-16.67	0	NA	-	-
500	500	0	1	447.44	-10.51	1	NA	-	-	NA	-	-
HIGH	1000	-	0	894.89	-	0	250	-	0	8.20	-	0
LOW	3.91	-	255	3.50	-	255	0.98	-	255	0.03	-	255

TABLE 16-4: BAUD RATES FOR ASYNCHRONOUS MODE (BRGH = 0)

BAUD	_		SPBRG	SPBRG 33 MHz		dz SPBRG		MHz	SPBRG	20 MHz		SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-
2.4	NA	-	-	2.40	-0.07	214	2.40	-0.15	162	2.40	+0.16	129
9.6	9.62	+0.16	64	9.55	-0.54	53	9.53	-0.76	40	9.47	-1.36	32
19.2	18.94	-1.36	32	19.10	-0.54	26	19.53	+1.73	19	19.53	+1.73	15
76.8	78.13	+1.73	7	73.66	-4.09	6	78.13	+1.73	4	78.13	+1.73	3
96	89.29	-6.99	6	103.13	+7.42	4	97.66	+1.73	3	104.17	+8.51	2
300	312.50	+4.17	1	257.81	-14.06	1	NA	-	-	312.50	+4.17	0
500	625	+25.00	0	NA	-	-	NA	-	-	NA	-	-
HIGH	625	-	0	515.63	-	0	390.63	-	0	312.50	-	0
LOW	2.44	-	255	2.01	-	255	1.53	-	255	1.22	-	255

BAUD	Fosc =	16 MHz	SPBRG	10	MHz	SPBRG	7.1590	9 MHz	SPBRG	5.068	8 MHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	1.20	+0.16	207	1.20	+0.16	129	1.20	+0.23	92	1.20	0	65
2.4	2.40	+0.16	103	2.40	+0.16	64	2.38	-0.83	46	2.40	0	32
9.6	9.62	+0.16	25	9.77	+1.73	15	9.32	-2.90	11	9.90	+3.13	7
19.2	19.23	+0.16	12	19.53	+1.73	7	18.64	-2.90	5	19.80	+3.13	3
76.8	83.33	+8.51	2	78.13	+1.73	1	111.86	+45.65	0	79.20	+3.13	0
96	83.33	-13.19	2	78.13	-18.62	1	NA	-	-	NA	-	-
300	250	-16.67	0	156.25	-47.92	0	NA	-	-	NA	-	-
500	NA	-	-	NA	-	-	NA	-	-	NA	-	-
HIGH	250	-	0	156.25	-	0	111.86	-	0	79.20	-	0
LOW	0.98	-	255	0.61	-	255	0.44	-	255	0.31	-	255

BAUD	Fosc = 4 MHz		SPBRG	3.5795	45 MHz	SPBRG	1 N	ИHz	SPBRG	32.76	8 kHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	decimal) //o /decimal)		KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	
0.3	0.30	-0.16	207	0.30	+0.23	185	0.30	+0.16	51	0.26	-14.67	1
1.2	1.20	+1.67	51	1.19	-0.83	46	1.20	+0.16	12	NA	-	-
2.4	2.40	+1.67	25	2.43	+1.32	22	2.23	-6.99	6	NA	-	-
9.6	8.93	-6.99	6	9.32	-2.90	5	7.81	-18.62	1	NA	-	-
19.2	20.83	+8.51	2	18.64	-2.90	2	15.63	-18.62	0	NA	-	-
76.8	62.50	-18.62	0	55.93	-27.17	0	NA	-	-	NA	-	-
96	NA	-	-	NA	-	-	NA	-	-	NA	-	-
300	NA	-	-	NA	-	-	NA	-	-	NA	-	-
500	NA	-	-	NA	-	-	NA	-	-	NA	-	-
HIGH	62.50	-	0	55.93	-	0	15.63	-	0	0.51	-	0
LOW	0.24	_	255	0.22	-	255	0.06	-	255	0.002	_	255

TABLE 16-5: BAUD RATES FOR ASYNCHRONOUS MODE (BRGH = 1)

BAUD	Fosc = 40 MHz		SPBRG	33 1	MHz	SPBRG	25	MHz	SPBRG	20 I	VIHz	SPBRG value
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% value ERROR (decimal) K	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-
2.4	NA	-	-	NA	-	-	NA	-	-	NA	-	-
9.6	NA	-	-	9.60	-0.07	214	9.59	-0.15	162	9.62	+0.16	129
19.2	19.23	+0 16	129	19.28	+0.39	106	19.30	+0.47	80	19.23	+0 16	64
76.8	75.76	-1.36	32	76.39	-0.54	26	78.13	+1.73	19	78.13	+1.73	15
96	96.15	+0 16	25	98.21	+2.31	20	97.66	+1.73	15	96.15	+0 16	12
300	312.50	+4.17	7	294.64	-1.79	6	312.50	+4.17	4	312.50	+4.17	3
500	500	0	4	515.63	+3.13	3	520.83	+4.17	2	416.67	-16.67	2
HIGH	2500	-	0	2062.50	-	0	1562.50	-	0	1250	-	0
LOW	9.77	-	255	8,06	-	255	6.10	-	255	4.88	-	255

BAUD	Fosc = 16 MHz		SPBRG	10 MHz		SPBRG	7.1590	9 MHz	SPBRG	5.068	8 MHz	SPBRG
RATE (Kbps)	KBAUD	% (decimal)	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)			
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-
2.4	NA	-	-	NA	-	-	2.41	+0.23	185	2.40	0	131
9.6	9.62	+0.16	103	9.62	+0.16	64	9.52	-0.83	46	9.60	0	32
19.2	19.23	+0.16	51	18.94	-1.36	32	19.45	+1.32	22	18.64	-2.94	16
76.8	76.92	+0.16	12	78.13	+1.73	7	74.57	-2.90	5	79.20	+3.13	3
96	100	+4.17	9	89.29	-6.99	6	89.49	-6.78	4	105.60	+10.00	2
300	333.33	+11.11	2	312.50	+4.17	1	447.44	+49.15	0	316.80	+5.60	0
500	500	0	1	625	+25.00	0	447.44	-10.51	0	NA	-	-
HIGH	1000	-	0	625	-	0	447.44	-	0	316.80	-	0
LOW	3.91	-	255	2.44	-	255	1.75	-	255	1.24	-	255

BAUD	Fosc = 4 MHz		SPBRG	3.5795	45 MHz	SPBRG	1 N	1Hz	SPBRG	32.76	8 kHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	0.30	+0.16	207	0.29	-2.48	6
1.2	1.20	+0.16	207	1.20	+0.23	185	1.20	+0.16	51	1.02	-14.67	1
2.4	2.40	+0.16	103	2.41	+0.23	92	2.40	+0.16	25	2.05	-14.67	0
9.6	9.62	+0.16	25	9.73	+1.32	22	8.93	-6.99	6	NA	-	-
19.2	19.23	+0.16	12	18.64	-2.90	11	20.83	+8.51	2	NA	-	-
76.8	NA	-	-	74.57	-2.90	2	62.50	-18.62	0	NA	-	-
96	NA	-	-	111.86	+16.52	1	NA	-	-	NA	-	-
300	NA	-	-	223.72	-25.43	0	NA	-	-	NA	-	-
500	NA	-	-	NA	-	-	NA	-	-	NA	-	-
HIGH	250	-	0	55.93	-	0	62.50	-	0	2.05	-	0
LOW	0.98	-	255	0.22	-	255	0.24	-	255	0.008	-	255

#### 16.2 USART Asynchronous Mode

In this mode, the USART uses standard non-return-to-zero (NRZ) format (one START bit, eight or nine data bits and one STOP bit). The most common data format is 8-bits. An on-chip dedicated 8-bit baud rate generator can be used to derive standard baud rate frequencies from the oscillator. The USART transmits and receives the LSb first. The USART's transmitter and receiver are functionally independent, but use the same data format and baud rate. The baud rate generator produces a clock, either x16 or x64 of the bit shift rate, depending on bit BRGH (TXSTA<2>). Parity is not supported by the hardware, but can be implemented in software (and stored as the ninth data bit). Asynchronous mode is stopped during SLEEP.

Asynchronous mode is selected by clearing bit SYNC (TXSTA<4>).

The USART Asynchronous module consists of the following important elements:

- · Baud Rate Generator
- · Sampling Circuit
- · Asynchronous Transmitter
- · Asynchronous Receiver

## 16.2.1 USART ASYNCHRONOUS TRANSMITTER

The USART transmitter block diagram is shown in Figure 16-1. The heart of the transmitter is the Transmit (serial) Shift Register (TSR). The shift register obtains its data from the read/write transmit buffer, TXREG. The TXREG register is loaded with data in software. The TSR register is not loaded until the STOP bit has been transmitted from the previous load. As soon as the STOP bit is transmitted, the TSR is loaded with new data from the TXREG register (if available). Once the TXREG register transfers the data to the TSR register (occurs in one TCY), the TXREG register is empty and

flag bit TXIF (PIR1<4>) is set. This interrupt can be enabled/disabled by setting/clearing enable bit TXIE (PIE1<4>). Flag bit TXIF will be set, regardless of the state of enable bit TXIE and cannot be cleared in software. It will reset only when new data is loaded into the TXREG register. While flag bit TXIF indicated the status of the TXREG register, another bit, TRMT (TXSTA<1>), shows the status of the TSR register. Status bit TRMT is a read-only bit, which is set when the TSR register is empty. No interrupt logic is tied to this bit, so the user has to poll this bit in order to determine if the TSR register is empty.

- **Note 1:** The TSR register is not mapped in data memory, so it is not available to the user.
  - 2: Flag bit TXIF is set when enable bit TXEN is set.

To set up an asynchronous transmission:

- Initialize the SPBRG register for the appropriate baud rate. If a high speed baud rate is desired, set bit BRGH (Section 16.1).
- Enable the asynchronous serial port by clearing bit SYNC and setting bit SPEN.
- 3. If interrupts are desired, set enable bit TXIE.
- If 9-bit transmission is desired, set transmit bit TX9. Can be used as address/data bit.
- Enable the transmission by setting bit TXEN, which will also set bit TXIF.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- Load data to the TXREG register (starts transmission).

Note: TXIF is not cleared immediately upon loading data into the transmit buffer TXREG.

The flag bit becomes valid in the second instruction cycle following the load instruction.

FIGURE 16-1: USART TRANSMIT BLOCK DIAGRAM




FIGURE 16-2: ASYNCHRONOUS TRANSMISSION




FIGURE 16-3: ASYNCHRONOUS TRANSMISSION (BACK TO BACK)




TABLE 16-6: REGISTERS ASSOCIATED WITH ASYNCHRONOUS TRANSMISSION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR		Value on All Other RESETS	
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000	0000	0000	0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000	0000	0000	0000
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000	-00x	0000	-00x
TXREG	USART Tra	nsmit Regis	ter						0000	0000	0000	0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000	-010	0000	-010
SPBRG	Baud Rate	Generator F	Register						0000	0000	0000	0000

Legend: x = unknown, - = unimplemented locations read as '0'.

Shaded cells are not used for Asynchronous Transmission.

Note 1: The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18F2X2 devices; always maintain these bits clear.

## 16.2.2 USART ASYNCHRONOUS RECEIVER

The receiver block diagram is shown in Figure 16-4. The data is received on the RC7/RX/DT pin and drives the data recovery block. The data recovery block is actually a high speed shifter operating at x16 times the baud rate, whereas the main receive serial shifter operates at the bit rate or at Fosc. This mode would typically be used in RS-232 systems.

To set up an Asynchronous Reception:

- Initialize the SPBRG register for the appropriate baud rate. If a high speed baud rate is desired, set bit BRGH (Section 16.1).
- Enable the asynchronous serial port by clearing bit SYNC and setting bit SPEN.
- 3. If interrupts are desired, set enable bit RCIE.
- 4. If 9-bit reception is desired, set bit RX9.
- 5. Enable the reception by setting bit CREN.
- Flag bit RCIF will be set when reception is complete and an interrupt will be generated if enable bit RCIE was set.
- Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREG register.
- If any error occurred, clear the error by clearing enable bit CREN.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

## 16.2.3 SETTING UP 9-BIT MODE WITH ADDRESS DETECT

This mode would typically be used in RS-485 systems. To set up an Asynchronous Reception with Address Detect Enable:

- Initialize the SPBRG register for the appropriate baud rate. If a high speed baud rate is required, set the BRGH bit.
- Enable the asynchronous serial port by clearing the SYNC bit and setting the SPEN bit.
- If interrupts are required, set the RCEN bit and select the desired priority level with the RCIP bit.
- 4. Set the RX9 bit to enable 9-bit reception.
- 5. Set the ADDEN bit to enable address detect.
- 6. Enable reception by setting the CREN bit.
- The RCIF bit will be set when reception is complete. The interrupt will be acknowledged if the RCIE and GIE bits are set.
- 8. Read the RCSTA register to determine if any error occurred during reception, as well as read bit 9 of data (if applicable).
- Read RCREG to determine if the device is being addressed.
- 10. If any error occurred, clear the CREN bit.
- If the device has been addressed, clear the ADDEN bit to allow all received data into the receive buffer and interrupt the CPU.






FIGURE 16-5: ASYNCHRONOUS RECEPTION




TABLE 16-7: REGISTERS ASSOCIATED WITH ASYNCHRONOUS RECEPTION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
INTCON	GIE/GIEH	PEIE/ GIEL	TMR0IE	INT0IE	RBIE	TMR01F	INT01F	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000 0000	0000 0000
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 -00x	0000 -00x
RCREG	USART Re	ceive Re	gister						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate	Generato	0000 0000	0000 0000						

Legend: x = unknown, - = unimplemented locations read as '0'.

Shaded cells are not used for Asynchronous Reception.

**Note 1:** The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18F2X2 devices; always maintain these bits clear.

#### 16.3 USART Synchronous Master Mode

In Synchronous Master mode, the data is transmitted in a half-duplex manner (i.e., transmission and reception do not occur at the same time). When transmitting data, the reception is inhibited and vice versa. Synchronous mode is entered by setting bit SYNC (TXSTA<4>). In addition, enable bit SPEN (RCSTA<7>) is set in order to configure the RC6/TX/CK and RC7/RX/DT I/O pins to CK (clock) and DT (data) lines, respectively. The Master mode indicates that the processor transmits the master clock on the CK line. The Master mode is entered by setting bit CSRC (TXSTA<7>).

## 16.3.1 USART SYNCHRONOUS MASTER TRANSMISSION

The USART transmitter block diagram is shown in Figure 16-1. The heart of the transmitter is the Transmit (serial) Shift Register (TSR). The shift register obtains its data from the read/write transmit buffer register TXREG. The TXREG register is loaded with data in software. The TSR register is not loaded until the last bit has been transmitted from the previous load. As soon as the last bit is transmitted, the TSR is loaded with new data from the TXREG (if available). Once the TXREG register transfers the data to the TSR register (occurs in one TCYCLE), the TXREG is empty and interrupt bit TXIF (PIR1<4>) is set. The interrupt can be enabled/disabled by setting/clearing enable bit TXIE

(PIE1<4>). Flag bit TXIF will be set, regardless of the state of enable bit TXIE, and cannot be cleared in software. It will reset only when new data is loaded into the TXREG register. While flag bit TXIF indicates the status of the TXREG register, another bit TRMT (TXSTA<1>) shows the status of the TSR register. TRMT is a read only bit, which is set when the TSR is empty. No interrupt logic is tied to this bit, so the user has to poll this bit in order to determine if the TSR register is empty. The TSR is not mapped in data memory, so it is not available to the user.

To set up a Synchronous Master Transmission:

- 1. Initialize the SPBRG register for the appropriate baud rate (Section 16.1).
- Enable the synchronous master serial port by setting bits SYNC, SPEN, and CSRC.
- 3. If interrupts are desired, set enable bit TXIE.
- 4. If 9-bit transmission is desired, set bit TX9.
- Enable the transmission by setting bit TXEN.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- 7. Start transmission by loading data to the TXREG register.

Note: TXIF is not cleared immediately upon loading data into the transmit buffer TXREG.

The flag bit becomes valid in the second instruction cycle following the load instruction.

TABLE 16-8: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER TRANSMISSION


Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
	GILIT	GILL								
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000 0000	0000 0000
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 -00x	0000 -00x
TXREG	USART Transmit Register								0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate	e Genera	0000 0000	0000 0000						

Legend: x = unknown, - = unimplemented, read as '0'.


Shaded cells are not used for Synchronous Master Transmission.

Note 1: The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18F2X2 devices; always maintain these bits clear.

#### FIGURE 16-6: SYNCHRONOUS TRANSMISSION



## FIGURE 16-7: SYNCHRONOUS TRANSMISSION (THROUGH TXEN)



## 16.3.2 USART SYNCHRONOUS MASTER RECEPTION

Once Synchronous mode is selected, reception is enabled by setting either enable bit SREN (RCSTA<5>), or enable bit CREN (RCSTA<4>). Data is sampled on the RC7/RX/DT pin on the falling edge of the clock. If enable bit SREN is set, only a single word is received. If enable bit CREN is set, the reception is continuous until CREN is cleared. If both bits are set, then CREN takes precedence.

To set up a Synchronous Master Reception:

- Initialize the SPBRG register for the appropriate baud rate (Section 16.1).
- Enable the synchronous master serial port by setting bits SYNC, SPEN and CSRC.
- 3. Ensure bits CREN and SREN are clear.


- 4. If interrupts are desired, set enable bit RCIE.
- 5. If 9-bit reception is desired, set bit RX9.
- If a single reception is required, set bit SREN. For continuous reception, set bit CREN.
- Interrupt flag bit RCIF will be set when reception is complete and an interrupt will be generated if the enable bit RCIE was set.
- 8. Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREG register.
- If any error occurred, clear the error by clearing bit CREN.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

TABLE 16-9: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER RECEPTION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000 0000	0000 0000
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 -00x	0000 -00x
RCREG	USART R	eceive R	egister						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate	e Genera	0000 0000	0000 0000						

Legend: x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for Synchronous Master Reception. **Note 1:** The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18F2X2 devices; always maintain these bits clear.

FIGURE 16-8: SYNCHRONOUS RECEPTION (MASTER MODE, SREN)



# 16.4 USART Synchronous Slave Mode

Synchronous Slave mode differs from the Master mode in the fact that the shift clock is supplied externally at the RC6/TX/CK pin (instead of being supplied internally in Master mode). This allows the device to transfer or receive data while in SLEEP mode. Slave mode is entered by clearing bit CSRC (TXSTA<7>).

# 16.4.1 USART SYNCHRONOUS SLAVE TRANSMIT

The operation of the Synchronous Master and Slave modes are identical, except in the case of the SLEEP mode.

If two words are written to the TXREG and then the SLEEP instruction is executed, the following will occur:

- The first word will immediately transfer to the TSR register and transmit.
- b) The second word will remain in TXREG register.
- c) Flag bit TXIF will not be set.
- d) When the first word has been shifted out of TSR, the TXREG register will transfer the second word to the TSR and flag bit TXIF will now be set.
- e) If enable bit TXIE is set, the interrupt will wake the chip from SLEEP. If the global interrupt is enabled, the program will branch to the interrupt vector.

To set up a Synchronous Slave Transmission:

- Enable the synchronous slave serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- 2. Clear bits CREN and SREN.
- If interrupts are desired, set enable bit TXIE.
- 4. If 9-bit transmission is desired, set bit TX9.
- Enable the transmission by setting enable bit TXEN.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- Start transmission by loading data to the TXREG register.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

TABLE 16-10: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE TRANSMISSION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 0002	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000 0000	0000 0000
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 -002	x000 -00x
TXREG	USART T	ransmit F	Register						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate Generator Register									0000 0000

Legend: x = unknown, - = unimplemented, read as '0'.

Shaded cells are not used for Synchronous Slave Transmission.

**Note 1:** The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18F2X2 devices; always maintain these bits clear.

# 16.4.2 USART SYNCHRONOUS SLAVE RECEPTION

The operation of the Synchronous Master and Slave modes is identical, except in the case of the SLEEP mode and bit SREN, which is a "don't care" in Slave mode.

If receive is enabled by setting bit CREN prior to the SLEEP instruction, then a word may be received during SLEEP. On completely receiving the word, the RSR register will transfer the data to the RCREG register, and if enable bit RCIE bit is set, the interrupt generated will wake the chip from SLEEP. If the global interrupt is enabled, the program will branch to the interrupt vector.

To set up a Synchronous Slave Reception:

- Enable the synchronous master serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- If interrupts are desired, set enable bit RCIE.
- 3. If 9-bit reception is desired, set bit RX9.
- 4. To enable reception, set enable bit CREN.
- Flag bit RCIF will be set when reception is complete. An interrupt will be generated if enable bit RCIE was set.
- Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREG register.
- If any error occurred, clear the error by clearing bit CREN.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set

TABLE 16-11: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE RECEPTION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0		e on BOR	Valu All C RES	ther
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INTOIF	RBIF	0000	000x	0000	000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000	0000	0000	0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000	0000	0000	0000
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000	-00x	0000	-00x
RCREG	USART R	eceive Re	egister						0000	0000	0000	0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000	-010	0000	-010
SPBRG	Baud Rate	0000	0000	0000	0000							

Legend: x = unknown, - = unimplemented, read as '0'.

Shaded cells are not used for Synchronous Slave Reception.

Note 1: The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18F2X2 devices; always maintain these bits clear.

# 17.0 COMPATIBLE 10-BIT ANALOG-TO-DIGITAL CONVERTER (A/D) MODULE

The Analog-to-Digital (A/D) converter module has five inputs for the PIC18F2X2 devices and eight for the PIC18F4X2 devices. This module has the ADCON0 and ADCON1 register definitions that are compatible with the mid-range A/D module.

The A/D allows conversion of an analog input signal to a corresponding 10-bit digital number.

The A/D module has four registers. These registers are:

- · A/D Result High Register (ADRESH)
- A/D Result Low Register (ADRESL)
- A/D Control Register 0 (ADCON0)
- A/D Control Register 1 (ADCON1)

The ADCON0 register, shown in Register 17-1, controls the operation of the A/D module. The ADCON1 register, shown in Register 17-2, configures the functions of the port pins.

#### REGISTER 17-1: ADCONO REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0
ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE	_	ADON
bit 7							bit 0

#### bit 7-6 ADCS1:ADCS0: A/D Conversion Clock Select bits (ADCON0 bits in bold)

ADCON1 <adcs2></adcs2>	ADCON0 <adcs1:adcs0></adcs1:adcs0>	Clock Conversion
0	00	Fosc/2
0	01	Fosc/8
0	10	Fosc/32
0	11	FRC (clock derived from the internal A/D RC oscillator)
1	00	Fosc/4
1	01	Fosc/16
1	10	Fosc/64
1	11	FRC (clock derived from the internal A/D RC oscillator)

### bit 5-3 CHS2:CHS0: Analog Channel Select bits

000 = channel 0, (AN0)

001 = channel 1, (AN1)

010 = channel 2, (AN2)

011 = channel 3, (AN3)

100 = channel 4, (AN4)

101 = channel 5, (AN5)

110 = channel 6, (AN6)

111 = channel 7, (AN7)

**Note:** The PIC18F2X2 devices do not implement the full 8 A/D channels; the unimplemented selections are reserved. Do not select any unimplemented channel.

# bit 2 GO/DONE: A/D Conversion Status bit

When ADON = 1:

- 1 = A/D conversion in progress (setting this bit starts the A/D conversion which is automatically cleared by hardware when the A/D conversion is complete)
- 0 = A/D conversion not in progress

#### bit 1 Unimplemented: Read as '0'

bit 0 ADON: A/D On bit

- 1 = A/D converter module is powered up
- 0 = A/D converter module is shut-off and consumes no operating current

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	l bit, read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### **REGISTER 17-2: ADCON1 REGISTER**

R/W-0	R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0
ADFM	ADCS2	_	_	PCFG3	PCFG2	PCFG1	PCFG0
bit 7							bit 0

bit 7 ADFM: A/D Result Format Select bit

1 = Right justified. Six (6) Most Significant bits of ADRESH are read as '0'.

0 = Left justified. Six (6) Least Significant bits of ADRESL are read as '0'.

bit 6 ADCS2: A/D Conversion Clock Select bit (ADCON1 bits in **bold**)

ADCON1 <adcs2></adcs2>	ADCON0 <adcs1:adcs0></adcs1:adcs0>	Clock Conversion
0	00	Fosc/2
0	01	Fosc/8
0	10	Fosc/32
0	11	FRC (clock derived from the internal A/D RC oscillator)
1	00	Fosc/4
1	01	Fosc/16
1	10	Fosc/64
1	11	FRC (clock derived from the internal A/D RC oscillator)

bit 5-4 Unimplemented: Read as '0'

bit 3-0 PCFG3:PCFG0: A/D Port Configuration Control bits

PCFG <3:0>	AN7	AN6	AN5	AN4	AN3	AN2	AN1	AN0	VREF+	VREF-	C/R
0000	Α	Α	Α	Α	Α	Α	Α	Α	VDD	Vss	8/0
0001	Α	Α	Α	Α	VREF+	Α	Α	Α	AN3	Vss	7/1
0010	D	D	D	Α	Α	Α	Α	Α	VDD	Vss	5/0
0011	D	D	D	Α	VREF+	Α	Α	Α	AN3	Vss	4/1
0100	D	D	D	D	Α	D	Α	Α	VDD	Vss	3/0
0101	D	D	D	D	VREF+	D	Α	Α	AN3	Vss	2/1
011x	D	D	D	D	D	D	D	D	_	_	0/0
1000	Α	Α	Α	Α	VREF+	VREF-	Α	Α	AN3	AN2	6/2
1001	D	D	Α	Α	Α	Α	Α	Α	VDD	Vss	6/0
1010	D	D	Α	Α	VREF+	Α	Α	Α	AN3	Vss	5/1
1011	D	D	Α	Α	VREF+	VREF-	Α	Α	AN3	AN2	4/2
1100	D	D	D	Α	VREF+	VREF-	Α	Α	AN3	AN2	3/2
1101	D	D	D	D	VREF+	VREF-	Α	Α	AN3	AN2	2/2
1110	D	D	D	D	D	D	D	Α	VDD	Vss	1/0
1111	D	D	D	D	VREF+	VREF-	D	Α	AN3	AN2	1/2

A = Analog input D = Digital I/O

C/R = # of analog input channels / # of A/D voltage references

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

- n = Value at POR 1' = Bit is set 0' = Bit is cleared 0' = Bit is cleared 0' = Bit is unknown

**Note:** On any device RESET, the port pins that are multiplexed with analog functions (ANx) are forced to be an analog input.

The analog reference voltage is software selectable to either the device's positive and negative supply voltage (VDD and Vss), or the voltage level on the RA3/AN3/ VREF+ pin and RA2/AN2/VREF- pin.

The A/D converter has a unique feature of being able to operate while the device is in SLEEP mode. To operate in SLEEP, the A/D conversion clock must be derived from the A/D's internal RC oscillator.


The output of the sample and hold is the input into the converter, which generates the result via successive approximation.

A device RESET forces all registers to their RESET state. This forces the A/D module to be turned off and any conversion is aborted.

Each port pin associated with the A/D converter can be configured as an analog input (RA3 can also be a voltage reference) or as a digital I/O.

The ADRESH and ADRESL registers contain the result of the A/D conversion. When the A/D conversion is complete, the result is loaded into the ADRESH/ ADRESL registers, the GO/DONE bit (ADCON0<2>) is cleared, and A/D interrupt flag bit, ADIF is set. The block diagram of the A/D module is shown in Figure 17-1.

**FIGURE 17-1:** A/D BLOCK DIAGRAM



# PIC18FXX2

The value that is in the ADRESH/ADRESL registers is not modified for a Power-on Reset. The ADRESH/ADRESL registers will contain unknown data after a Power-on Reset.

After the A/D module has been configured as desired, the selected channel must be acquired before the conversion is started. The analog input channels must have their corresponding TRIS bits selected as an input. To determine acquisition time, see Section 17.1. After this acquisition time has elapsed, the A/D conversion can be started. The following steps should be followed for doing an A/D conversion:

- 1. Configure the A/D module:
  - Configure analog pins, voltage reference and digital I/O (ADCON1)
  - Select A/D input channel (ADCON0)
  - Select A/D conversion clock (ADCON0)
  - Turn on A/D module (ADCON0)
- 2. Configure A/D interrupt (if desired):
  - · Clear ADIF bit
  - · Set ADIE bit
  - · Set GIE bit
  - · Set PEIE bit
- 3. Wait the required acquisition time.
- 4. Start conversion:
  - Set GO/DONE bit (ADCON0)

- 5. Wait for A/D conversion to complete, by either:
  - Polling for the GO/DONE bit to be cleared (interrupts disabled)

OR


- · Waiting for the A/D interrupt
- Read A/D Result registers (ADRESH/ADRESL); clear bit ADIF if required.
- For next conversion, go to step 1 or step 2 as required. The A/D conversion time per bit is defined as TAD. A minimum wait of 2 TAD is required before the next acquisition starts.

# 17.1 A/D Acquisition Requirements

For the A/D converter to meet its specified accuracy, the charge holding capacitor (CHOLD) must be allowed to fully charge to the input channel voltage level. The analog input model is shown in Figure 17-2. The source impedance (Rs) and the internal sampling switch (Rss) impedance directly affect the time required to charge the capacitor CHOLD. The sampling switch (Rss) impedance varies over the device voltage (VDD). The source impedance affects the offset voltage at the analog input (due to pin leakage current). The maximum recommended impedance for analog sources is  $2.5~{\rm k}\Omega$ . After the analog input channel is selected (changed), this acquisition must be done before the conversion can be started.

**Note:** When the conversion is started, the holding capacitor is disconnected from the input pin.

# FIGURE 17-2: ANALOG INPUT MODEL



To calculate the minimum acquisition time, Equation 17-1 may be used. This equation assumes that 1/2 LSb error is used (1024 steps for the A/D). The 1/2 LSb error is the maximum error allowed for the A/D to meet its specified resolution.

### **EQUATION 17-1: ACQUISITION TIME**

```
TACQ = Amplifier Settling Time + Holding Capacitor Charging Time + Temperature Coefficient

= TAMP + TC + TCOFF
```

#### **EQUATION 17-2: A/D MINIMUM CHARGING TIME**

```
VHOLD = (V_{REF} - (V_{REF}/2048)) \cdot (1 - e^{(-T_C/C_{HOLD}(R_{IC} + R_{SS} + R_S))})

or

T_C = -(120 \text{ pF})(1 \text{ k}\Omega + R_{SS} + R_S) \ln(1/2048)
```

Example 17-1 shows the calculation of the minimum required acquisition time, TACQ. This calculation is based on the following application system assumptions:

120 pF

CHOLD

Temperature = 50°C (system max)
 VHOLD = 0V @ time = 0

### **EXAMPLE 17-1: CALCULATING THE MINIMUM REQUIRED ACQUISITION TIME**

```
Tacq = Tamp + Tc + Tcoff

Temperature coefficient is only required for temperatures > 25°C.

Tacq = 2 \mu s + Tc + [(Temp - 25^{\circ}C)(0.05 \mu s/°C)]

Tc = -Chold (Ric + Rss + Rs) ln(1/2048)
-120 pF (1 kΩ + 7 kΩ + 2.5 kΩ) ln(0.0004883)
-120 pF (10.5 kΩ) ln(0.0004883)
-1.26 \mu s (-7.6246)
9.61 \mu s

Tacq = 2 \mu s + 9.61 \mu s + [(50^{\circ}C - 25^{\circ}C)(0.05 \mu s/°C)]
11.61 \mu s + 1.25 \mu s
12.86 \mu s
```

# 17.2 Selecting the A/D Conversion Clock

The A/D conversion time per bit is defined as TAD. The A/D conversion requires 12 TAD per 10-bit conversion. The source of the A/D conversion clock is software selectable. The seven possible options for TAD are:

- · 2 Tosc
- 4 Tosc
- 8 Tosc
- 16 Tosc
- 32 Tosc
- 64 Tosc
- Internal A/D module RC oscillator (2-6 μs)

For correct A/D conversions, the A/D conversion clock (TAD) must be selected to ensure a minimum TAD time of 1.6  $\mu$ s.

Table 17-1 shows the resultant TAD times derived from the device operating frequencies and the A/D clock source selected.

# 17.3 Configuring Analog Port Pins

The ADCON1, TRISA and TRISE registers control the operation of the A/D port pins. The port pins that are desired as analog inputs, must have their corresponding TRIS bits set (input). If the TRIS bit is cleared (output), the digital output level (VOH or VOL) will be converted.

The A/D operation is independent of the state of the CHS2:CHS0 bits and the TRIS bits.

- Note 1: When reading the port register, all pins configured as analog input channels will read as cleared (a low level). Pins configured as digital inputs will convert an analog input. Analog levels on a digitally configured input will not affect the conversion accuracy.
  - 2: Analog levels on any pin that is defined as a digital input (including the AN4:AN0 pins) may cause the input buffer to consume current that is out of the device's specification.

TABLE 17-1: TAD VS. DEVICE OPERATING FREQUENCIES

AD Clock	Source (TAD)	Maximum Device Frequency				
Operation	ADCS2:ADCS0	PIC18FXX2	PIC18LFXX2			
2 Tosc	000	1.25 MHz	666 kHz			
4 Tosc	100	2.50 MHz	1.33 MHz			
8 Tosc	001	5.00 MHz	2.67 MHz			
16 Tosc	101	10.00 MHz	5.33 MHz			
32 Tosc	010	20.00 MHz	10.67 MHz			
64 Tosc	110	40.00 MHz	21.33 MHz			
RC	011	_	_			


#### 17.4 A/D Conversions

Figure 17-3 shows the operation of the A/D converter after the GO bit has been set. Clearing the GO/DONE bit during a conversion will abort the current conversion. The A/D result register pair will NOT be updated with the partially completed A/D conversion sample. That is, the ADRESH:ADRESL registers will continue to contain the value of the last completed conversion

(or the last value written to the ADRESH:ADRESL registers). After the A/D conversion is aborted, a 2 TAD wait is required before the next acquisition is started. After this 2 TAD wait, acquisition on the selected channel is automatically started. The  $GO/\overline{DONE}$  bit can then be set to start the conversion.

**Note:** The GO/DONE bit should **NOT** be set in the same instruction that turns on the A/D.

#### FIGURE 17-3: A/D CONVERSION TAD CYCLES




### 17.4.1 A/D RESULT REGISTERS

The ADRESH:ADRESL register pair is the location where the 10-bit A/D result is loaded at the completion of the A/D conversion. This register pair is 16-bits wide. The A/D module gives the flexibility to left or right justify the 10-bit result in the 16-bit result register. The A/D

Format Select bit (ADFM) controls this justification. Figure 17-4 shows the operation of the A/D result justification. The extra bits are loaded with '0's. When an A/D result will not overwrite these locations (A/D disable), these registers may be used as two general purpose 8-bit registers.

FIGURE 17-4: A/D RESULT JUSTIFICATION



# 17.5 Use of the CCP2 Trigger

An A/D conversion can be started by the "special event trigger" of the CCP2 module. This requires that the CCP2M3:CCP2M0 bits (CCP2CON<3:0>) be programmed as 1011 and that the A/D module is enabled (ADON bit is set). When the trigger occurs, the GO/DONE bit will be set, starting the A/D conversion, and the Timer1 (or Timer3) counter will be reset to zero. Timer1 (or Timer3) is reset to automatically repeat the A/D acquisition period with minimal software overhead

(moving ADRESH/ADRESL to the desired location). The appropriate analog input channel must be selected and the minimum acquisition done before the "special event trigger" sets the GO/DONE bit (starts a conversion).

If the A/D module is not enabled (ADON is cleared), the "special event trigger" will be ignored by the A/D module, but will still reset the Timer1 (or Timer3) counter.

TABLE 17-2: SUMMARY OF A/D REGISTERS

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on All Other RESETS
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	0000 0000	0000 0000
PIR2	_	_	_	EEIF	BCLIF	LVDIF	TMR3IF	CCP2IF	0 0000	0 0000
PIE2	_	_	_	EEIE	BCLIE	LVDIE	TMR3IE	CCP2IE	0 0000	0 0000
IPR2	_	_	_	EEIP	BCLIP	LVDIP	TMR3IP	CCP2IP	1 1111	1 0000
ADRESH	A/D Resul	t Register							xxxx xxxx	uuuu uuuu
ADRESL	A/D Resul	t Register							xxxx xxxx	uuuu uuuu
ADCON0	ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE	_	ADON	0000 00-0	0000 00-0
ADCON1	ADFM	ADCS2	_	_	PCFG3	PCFG2	PCFG1	PCFG0	000	000
PORTA	_	RA6	RA5	RA4	RA3	RA2	RA1	RA0	0x 0000	0u 0000
TRISA	_	PORTA Data Direction Register						11 1111	11 1111	
PORTE	_		_	_	_	RE2	RE1	RE0	000	000
LATE	_	_	_	_	_	LATE2	LATE1	LATE0	xxx	uuu
TRISE	IBF	OBF	IBOV	PSPMODE	_	PORTE Data	a Direction	bits	0000 -111	0000 -111

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used for A/D conversion.

Note 1: The PSPIF, PSPIE and PSPIP bits are reserved on the PIC18F2X2 devices; always maintain these bits clear.

#### 18.0 LOW VOLTAGE DETECT


In many applications, the ability to determine if the device voltage (VDD) is below a specified voltage level is a desirable feature. A window of operation for the application can be created, where the application software can do "housekeeping tasks" before the device voltage exits the valid operating range. This can be done using the Low Voltage Detect module.

This module is a software programmable circuitry, where a device voltage trip point can be specified. When the voltage of the device becomes lower then the specified point, an interrupt flag is set. If the interrupt is enabled, the program execution will branch to the interrupt vector address and the software can then respond to that interrupt source.

The Low Voltage Detect circuitry is completely under software control. This allows the circuitry to be "turned off" by the software, which minimizes the current consumption for the device.

Figure 18-1 shows a possible application voltage curve (typically for batteries). Over time, the device voltage decreases. When the device voltage equals voltage VA, the LVD logic generates an interrupt. This occurs at time TA. The application software then has the time, until the device voltage is no longer in valid operating range, to shutdown the system. Voltage point VB is the minimum valid operating voltage specification. This occurs at time TB. The difference TB - TA is the total time for shutdown.

FIGURE 18-1: TYPICAL LOW VOLTAGE DETECT APPLICATION




The block diagram for the LVD module is shown in Figure 18-2. A comparator uses an internally generated reference voltage as the set point. When the selected tap output of the device voltage crosses the set point (is lower than), the LVDIF bit is set.

Each node in the resistor divider represents a "trip point" voltage. The "trip point" voltage is the minimum supply voltage level at which the device can operate before the LVD module asserts an interrupt. When the

supply voltage is equal to the trip point, the voltage tapped off of the resistor array is equal to the 1.2V internal reference voltage generated by the voltage reference module. The comparator then generates an interrupt signal setting the LVDIF bit. This voltage is software programmable to any one of 16 values (see Figure 18-2). The trip point is selected by programming the LVDL3:LVDL0 bits (LVDCON<3:0>).


FIGURE 18-2: LOW VOLTAGE DETECT (LVD) BLOCK DIAGRAM



The LVD module has an additional feature that allows the user to supply the trip voltage to the module from an external source. This mode is enabled when bits LVDL3:LVDL0 are set to 1111. In this state, the comparator input is multiplexed from the external input pin,

LVDIN (Figure 18-3). This gives users flexibility, because it allows them to configure the Low Voltage Detect interrupt to occur at any voltage in the valid operating range.

FIGURE 18-3: LOW VOLTAGE DETECT (LVD) WITH EXTERNAL INPUT BLOCK DIAGRAM



# 18.1 Control Register

The Low Voltage Detect Control register controls the operation of the Low Voltage Detect circuitry.

#### **REGISTER 18-1: LVDCON REGISTER**

U-0	U-0	R-0	R/W-0	R/W-0	R/W-1	R/W-0	R/W-1
_	_	IRVST	LVDEN	LVDL3	LVDL2	LVDL1	LVDL0
bit 7							bit 0

bit 7-6 Unimplemented: Read as '0'

bit 5 IRVST: Internal Reference Voltage Stable Flag bit

- 1 = Indicates that the Low Voltage Detect logic will generate the interrupt flag at the specified voltage range
- 0 = Indicates that the Low Voltage Detect logic will not generate the interrupt flag at the specified voltage range and the LVD interrupt should not be enabled
- bit 4 LVDEN: Low Voltage Detect Power Enable bit
  - 1 = Enables LVD, powers up LVD circuit
  - 0 = Disables LVD, powers down LVD circuit
- bit 3-0 LVDL3:LVDL0: Low Voltage Detection Limit bits
  - 1111 = External analog input is used (input comes from the LVDIN pin)
  - 1110 = 4.5V 4.77V
  - 1101 = 4.2V 4.45V
  - 1100 = 4.0V 4.24V
  - 1011 = 3.8V 4.03V
  - 1010 = 3.6V 3.82V1001 = 3.5V - 3.71V
  - 1001 = 3.3V 3.71V1000 = 3.3V - 3.50V
  - 0111 = 3.0V 3.18V
  - 0110 = 2.8V 2.97V
  - 0101 = 2.7V 2.86V
  - 0100 = 2.5V 2.65V
  - 0011 = 2.4V 2.54V
  - 0010 = 2.2V 2.33V
  - 0001 = 2.0V 2.12V
  - 0000 = Reserved

**Note:** LVDL3:LVDL0 modes which result in a trip point below the valid operating voltage of the device are not tested.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

- n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

# 18.2 Operation

Depending on the power source for the device voltage, the voltage normally decreases relatively slowly. This means that the LVD module does not need to be constantly operating. To decrease the current requirements, the LVD circuitry only needs to be enabled for short periods, where the voltage is checked. After doing the check, the LVD module may be disabled.


Each time that the LVD module is enabled, the circuitry requires some time to stabilize. After the circuitry has stabilized, all status flags may be cleared. The module will then indicate the proper state of the system.

The following steps are needed to set up the LVD module:

- Write the value to the LVDL3:LVDL0 bits (LVDCON register), which selects the desired LVD Trip Point.
- Ensure that LVD interrupts are disabled (the LVDIE bit is cleared or the GIE bit is cleared).
- Enable the LVD module (set the LVDEN bit in the LVDCON register).
- Wait for the LVD module to stabilize (the IRVST bit to become set).
- Clear the LVD interrupt flag, which may have falsely become set until the LVD module has stabilized (clear the LVDIF bit).
- Enable the LVD interrupt (set the LVDIE and the GIE bits).

Figure 18-4 shows typical waveforms that the LVD module may be used to detect.

FIGURE 18-4: LOW VOLTAGE DETECT WAVEFORMS



#### 18.2.1 REFERENCE VOLTAGE SET POINT

The Internal Reference Voltage of the LVD module may be used by other internal circuitry (the Programmable Brown-out Reset). If these circuits are disabled (lower current consumption), the reference voltage circuit requires a time to become stable before a low voltage condition can be reliably detected. This time is invariant of system clock speed. This start-up time is specified in electrical specification parameter 36. The low voltage interrupt flag will not be enabled until a stable reference voltage is reached. Refer to the waveform in Figure 18-4.

#### 18.2.2 CURRENT CONSUMPTION

When the module is enabled, the LVD comparator and voltage divider are enabled and will consume static current. The voltage divider can be tapped from multiple places in the resistor array. Total current consumption, when enabled, is specified in electrical specification parameter #D022B.

### 18.3 Operation During SLEEP

When enabled, the LVD circuitry continues to operate during SLEEP. If the device voltage crosses the trip point, the LVDIF bit will be set and the device will wake-up from SLEEP. Device execution will continue from the interrupt vector address if interrupts have been globally enabled.

#### 18.4 Effects of a RESET

A device RESET forces all registers to their RESET state. This forces the LVD module to be turned off.

# PIC18FXX2

**NOTES:** 

# 19.0 SPECIAL FEATURES OF THE CPU

There are several features intended to maximize system reliability, minimize cost through elimination of external components, provide power saving Operating modes and offer code protection. These are:

- · OSC Selection
- RESET
  - Power-on Reset (POR)
  - Power-up Timer (PWRT)
  - Oscillator Start-up Timer (OST)
  - Brown-out Reset (BOR)
- Interrupts
- · Watchdog Timer (WDT)
- SLEEP
- · Code Protection
- ID Locations
- · In-Circuit Serial Programming

All PIC18FXX2 devices have a Watchdog Timer, which is permanently enabled via the configuration bits or software controlled. It runs off its own RC oscillator for added reliability. There are two timers that offer necessary delays on power-up. One is the Oscillator Start-up Timer (OST), intended to keep the chip in RESET until the crystal oscillator is stable. The other is the Power-up Timer (PWRT), which provides a fixed delay on power-up only, designed to keep the part in RESET while the power supply stabilizes. With these two timers on-chip, most applications need no external RESET circuitry.

SLEEP mode is designed to offer a very low current Power-down mode. The user can wake-up from SLEEP through external RESET, Watchdog Timer Wake-up or through an interrupt. Several oscillator options are also made available to allow the part to fit the application. The RC oscillator option saves system cost, while the LP crystal option saves power. A set of configuration bits are used to select various options.

# 19.1 Configuration Bits

The configuration bits can be programmed (read as '0'), or left unprogrammed (read as '1'), to select various device configurations. These bits are mapped starting at program memory location 300000h.

The user will note that address 300000h is beyond the user program memory space. In fact, it belongs to the configuration memory space (300000h - 3FFFFFh), which can only be accessed using Table Reads and Table Writes.

Programming the configuration registers is done in a manner similar to programming the FLASH memory (see Section 5.5.1). The only difference is the configuration registers are written a byte at a time. The sequence of events for programming configuration registers is:

- 1. Load table pointer with address of configuration register being written.
- Write a single byte using the TBLWT instruction.
- 3. Set EEPGD to point to program memory, set the CFGS bit to access configuration registers, and set WREN to enable byte writes.
- Disable interrupts.
- 5. Write 55h to EECON2.
- 6. Write AAh to EECON2.
- 7. Set the WR bit. This will begin the write cycle.
- 8. CPU will stall for duration of write (approximately 2 ms using internal timer).
- 9. Execute a NOP.
- 10. Re-enable interrupts.

TABLE 19-1: CONFIGURATION BITS AND DEVICE IDS

File	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Default/ Unprogrammed Value
300001h	CONFIG1H	-	-	OSCSEN	_	_	FOSC2	FOSC1	FOSC0	1111
300002h	CONFIG2L	_	_	_	_	BORV1	BORV0	BOREN	PWRTEN	1111
300003h	CONFIG2H	_	_	_	_	WDTPS2	WDTPS1	WDTPS0	WDTEN	1111
300005h	CONFIG3H	_	_	_	_	_	_	_	CCP2MX	1
300006h	CONFIG4L	DEBUG	_	_	_	_	LVP	_	STVREN	11-1
300008h	CONFIG5L	_	_	_	_	CP3	CP2	CP1	CP0	1111
300009h	CONFIG5H	CPD	СРВ	_	_	_	_	_	_	11
30000Ah	CONFIG6L	_	_	_	_	WRT3	WRT2	WRT1	WRT0	1111
30000Bh	CONFIG6H	WRTD	WRTB	WRTC	_	_	_	_	_	111
30000Ch	CONFIG7L	_	_	_	_	EBTR3	EBTR2	EBTR1	EBTR0	1111
30000Dh	CONFIG7H	_	EBTRB	_	_	_	_	_	_	-1
3FFFFEh	DEVID1	DEV2	DEV1	DEV0	REV4	REV3	REV2	REV1	REV0	(1)
3FFFFFh	DEVID2	DEV10	DEV9	DEV8	DEV7	DEV6	DEV5	DEV4	DEV3	0000 0100

 $\mbox{Legend:} \ \ \, \mbox{$x=$ unknown, $u=$ unchanged, $-=$ unimplemented, $q=$ value depends on condition.} \label{eq:condition}$  Shaded cells are unimplemented, read as '0'.

Note 1: See Register 19-12 for DEVID1 values.

# REGISTER 19-1: CONFIGURATION REGISTER 1 HIGH (CONFIG1H: BYTE ADDRESS 300001h)

U-0	U-0	R/P-1	U-0	U-0	R/P-1	R/P-1	R/P-1
_	_	OSCSEN	_	_	FOSC2	FOSC1	FOSC0
bit 7							bit 0

bit 7-6 Unimplemented: Read as '0'

bit 5 OSCSEN: Oscillator System Clock Switch Enable bit

1 = Oscillator system clock switch option is disabled (main oscillator is source)

o = Oscillator system clock switch option is enabled (oscillator switching is enabled)

bit 4-3 Unimplemented: Read as '0'

bit 2-0 FOSC2:FOSC0: Oscillator Selection bits

111 = RC oscillator w/ OSC2 configured as RA6

110 = HS oscillator with PLL enabled/Clock frequency = (4 x Fosc)

101 = EC oscillator w/ OSC2 configured as RA6

100 = EC oscillator w/ OSC2 configured as divide-by-4 clock output

011 = RC oscillator

010 = HS oscillator

001 = XT oscillator

000 = LP oscillator

Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'

# REGISTER 19-2: CONFIGURATION REGISTER 2 LOW (CONFIG2L: BYTE ADDRESS 300002h)

U-0	U-0	U-0	U-0	R/P-1	R/P-1	R/P-1	R/P-1
_	_	_	_	BORV1	BORV0	BOREN	PWRTEN
bit 7							bit 0

bit 7-4 Unimplemented: Read as '0'

bit 3-2 BORV1:BORV0: Brown-out Reset Voltage bits

11 = VBOR set to 2.5V

10 = VBOR set to 2.7V

01 = VBOR set to 4.2V

00 = VBOR set to 4.5V

bit 1 BOREN: Brown-out Reset Enable bit

1 = Brown-out Reset enabled

0 = Brown-out Reset disabled

bit 0 **PWRTEN:** Power-up Timer Enable bit

1 = PWRT disabled

0 = PWRT enabled

Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'

- n = Value when device is unprogrammed u = Unchanged from programmed state

# REGISTER 19-3: CONFIGURATION REGISTER 2 HIGH (CONFIG2H: BYTE ADDRESS 300003h)

U-0	U-0	U-0	U-0	R/P-1	R/P-1	R/P-1	R/P-1
_	_	_	_	WDTPS2	WDTPS1	WDTPS0	WDTEN
bit 7							hit ∩

bit 7-4 Unimplemented: Read as '0'

bit 3-1 WDTPS2:WDTPS0: Watchdog Timer Postscale Select bits

111 = 1:128

110 = 1:64

101 = 1:32

100 = 1:16

011 = 1:8

010 = 1:4

010 = 1.4001 = 1:2

000 = 1:1

bit 0 WDTEN: Watchdog Timer Enable bit

1 = WDT enabled

0 = WDT disabled (control is placed on the SWDTEN bit)

Legend:

 $R = Readable \ bit$   $P = Programmable \ bit$   $U = Unimplemented \ bit$ , read as '0'

# REGISTER 19-4: CONFIGURATION REGISTER 3 HIGH (CONFIG3H: BYTE ADDRESS 300005h)

U-0	U-0	U-0	U-0	U-0	U-0	U-0	R/P-1
_	_	_	_	_	_	_	CCP2MX
bit 7							bit 0

bit 7-1 Unimplemented: Read as '0'

bit 0 CCP2MX: CCP2 Mux bit

1 = CCP2 input/output is multiplexed with RC1

0 = CCP2 input/output is multiplexed with RB3

Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'

n = Value when device is unprogrammed
 u = Unchanged from programmed state

# REGISTER 19-5: CONFIGURATION REGISTER 4 LOW (CONFIG4L: BYTE ADDRESS 300006h)

R/P-1	U-0	U-0	U-0	U-0	R/P-1	U-0	R/P-1
BKBUG	_	_	_	_	LVP	_	STVREN
bit 7							bit 0

bit 7 **DEBUG:** Background Debugger Enable bit

1 = Background Debugger disabled. RB6 and RB7 configured as general purpose I/O pins.

0 = Background Debugger enabled. RB6 and RB7 are dedicated to In-Circuit Debug.

bit 6-3 Unimplemented: Read as '0'

bit 2 LVP: Low Voltage ICSP Enable bit

1 = Low Voltage ICSP enabled

0 = Low Voltage ICSP disabled

bit 1 Unimplemented: Read as '0'

bit 0 STVREN: Stack Full/Underflow Reset Enable bit

1 = Stack Full/Underflow will cause RESET

0 = Stack Full/Underflow will not cause RESET

Legend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0'

#### REGISTER 19-6: CONFIGURATION REGISTER 5 LOW (CONFIG5L: BYTE ADDRESS 300008h)

U-0	U-0	U-0	U-0	R/C-1	R/C-1	R/C-1	R/C-1
_	_	_	_	CP3 <sup>(1)</sup>	CP2 <sup>(1)</sup>	CP1	CP0
bit 7							bit 0

bit 7-4 Unimplemented: Read as '0'

bit 3 CP3: Code Protection bit<sup>(1)</sup>

1 = Block 3 (006000-007FFFh) not code protected 0 = Block 3 (006000-007FFFh) code protected

bit 2 CP2: Code Protection bit<sup>(1)</sup>

1 = Block 2 (004000-005FFFh) not code protected 0 = Block 2 (004000-005FFFh) code protected

bit 1 CP1: Code Protection bit

1 = Block 1 (002000-003FFFh) not code protected 0 = Block 1 (002000-003FFFh) code protected

bit 0 CP0: Code Protection bit

1 = Block 0 (000200-001FFFh) not code protected 0 = Block 0 (000200-001FFFh) code protected

Note 1: Unimplemented in PIC18FX42 devices; maintain this bit set.

Legend:

 $R = Readable \ bit$   $C = Clearable \ bit$   $U = Unimplemented \ bit, \ read \ as '0'$ 

- n = Value when device is unprogrammed u = Unchanged from programmed state

# REGISTER 19-7: CONFIGURATION REGISTER 5 HIGH (CONFIG5H: BYTE ADDRESS 300009h)

R/C-1	R/C-1	U-0	U-0	U-0	U-0	U-0	U-0
CPD	CPB	_	_	_	_	_	_
bit 7							bit 0

bit 7 CPD: Data EEPROM Code Protection bit

1 = Data EEPROM not code protected

0 = Data EEPROM code protected

bit 6 CPB: Boot Block Code Protection bit

1 = Boot Block (000000-0001FFh) not code protected

0 = Boot Block (000000-0001FFh) code protected

bit 5-0 **Unimplemented:** Read as '0'

Legend:

 $R = Readable \ bit$   $C = Clearable \ bit$   $U = Unimplemented \ bit, \ read \ as '0'$ 

#### REGISTER 19-8: CONFIGURATION REGISTER 6 LOW (CONFIG6L: BYTE ADDRESS 30000Ah)

U-0	U-0	U-0	U-0	R/C-1	R/C-1	R/C-1	R/C-1
_	_	_	_	WRT3 <sup>(1)</sup>	WRT2 <sup>(1)</sup>	WRT1	WRT0
bit 7							bit 0

bit 7-4 **Unimplemented:** Read as '0'

bit 3 WRT3: Write Protection bit<sup>(1)</sup>

1 = Block 3 (006000-007FFFh) not write protected 0 = Block 3 (006000-007FFFh) write protected

bit 2 WRT2: Write Protection bit<sup>(1)</sup>

1 = Block 2 (004000-005FFFh) not write protected 0 = Block 2 (004000-005FFFh) write protected

bit 1 WRT1: Write Protection bit

1 = Block 1 (002000-003FFFh) not write protected 0 = Block 1 (002000-003FFFh) write protected

bit 0 WRT0: Write Protection bit

1 = Block 0 (000200h-001FFFh) not write protected

0 = Block 0 (000200h-001FFFh) write protected

**Note 1:** Unimplemented in PIC18FX42 devices; maintain this bit set.

Legend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0'
- n = Value when device is unprogrammed u = Unchanged from programmed state

# REGISTER 19-9: CONFIGURATION REGISTER 6 HIGH (CONFIG6H: BYTE ADDRESS 30000Bh)

R/C-1	R/C-1	C-1	U-0	U-0	U-0	U-0	U-0
WRTD	WRTB	WRTC	_	_	_		_
bit 7							bit 0

bit 7 WRTD: Data EEPROM Write Protection bit

1 = Data EEPROM not write protected

0 = Data EEPROM write protected

bit 6 WRTB: Boot Block Write Protection bit

1 = Boot Block (000000-0001FFh) not write protected

0 = Boot Block (000000-0001FFh) write protected

bit 5 WRTC: Configuration Register Write Protection bit

1 = Configuration registers (300000-3000FFh) not write protected

 $oldsymbol{0}$  = Configuration registers (300000-3000FFh) write protected

Note: This bit is read only, and cannot be changed in User mode.

bit 4-0 Unimplemented: Read as '0'

Legend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0'
- n = Value when device is unprogrammed u = Unchanged from programmed state

# REGISTER 19-10: CONFIGURATION REGISTER 7 LOW (CONFIG7L: BYTE ADDRESS 30000Ch)

U-0	U-0	U-0	U-0	R/C-1	R/C-1	R/C-1	R/C-1
_	_	_	_	EBTR3 <sup>(1)</sup>	EBTR2 <sup>(1)</sup>	EBTR1	EBTR0
bit 7							bit 0

#### bit 7-4 Unimplemented: Read as '0'

#### bit 3 **EBTR3:** Table Read Protection bit<sup>(1)</sup>

1 = Block 3 (006000-007FFFh) not protected from Table Reads executed in other blocks

0 = Block 3 (006000-007FFFh) protected from Table Reads executed in other blocks

# bit 2 **EBTR2:** Table Read Protection bit<sup>(1)</sup>

1 = Block 2 (004000-005FFFh) not protected from Table Reads executed in other blocks

0 = Block 2 (004000-005FFFh) protected from Table Reads executed in other blocks

#### bit 1 EBTR1: Table Read Protection bit

1 = Block 1 (002000-003FFFh) not protected from Table Reads executed in other blocks

0 = Block 1 (002000-003FFFh) protected from Table Reads executed in other blocks

#### bit 0 **EBTR0**: Table Read Protection bit

1 = Block 0 (000200h-001FFFh) not protected from Table Reads executed in other blocks

0 = Block 0 (000200h-001FFFh) protected from Table Reads executed in other blocks

Note 1: Unimplemented in PIC18FX42 devices; maintain this bit set.

# REGISTER 19-11: CONFIGURATION REGISTER 7 HIGH (CONFIG7H: BYTE ADDRESS 30000Dh)

U-0	R/C-1	U-0	U-0	U-0	U-0	U-0	U-0
_	EBTRB	_	_	_	_	_	_
bit 7							bit 0

#### bit 7 Unimplemented: Read as '0'

bit 6 EBTRB: Boot Block Table Read Protection bit

1 = Boot Block (000000-0001FFh) not protected from Table Reads executed in other blocks

0 = Boot Block (000000-0001FFh) protected from Table Reads executed in other blocks

bit 5-0 **Unimplemented:** Read as '0'

#### Legend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0'

# REGISTER 19-12: DEVICE ID REGISTER 1 FOR PIC18FXX2 (DEVID1: BYTE ADDRESS 3FFFFEh)

R	R	R	R	R	R	R	R
DEV2	DEV1	DEV0	REV4	REV3	REV2	REV1	REV0
bit 7							bit 0

bit 7-5 **DEV2:DEV0:** Device ID bits

000 = PIC18F252

001 = PIC18F452

100 = PIC18F242

101 = PIC18F442

bit 4-0 REV4:REV0: Revision ID bits

These bits are used to indicate the device revision.

Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'
- n = Value when device is unprogrammed u = Unchanged from programmed state

# REGISTER 19-13: DEVICEID REGISTER 2 FOR PIC18FXX2 (DEVID2: BYTE ADDRESS 3FFFFFh)

R	R	R	R	R	R	R	R
DEV10	DEV9	DEV8	DEV7	DEV6	DEV5	DEV4	DEV3
bit 7							bit 0

#### bit 7-0 **DEV10:DEV3:** Device ID bits

These bits are used with the DEV2:DEV0 bits in the Device ID Register 1 to identify the part number.

Legend:

 $R = Readable \ bit$   $P = Programmable \ bit$   $U = Unimplemented \ bit, read as '0'$  $- n = Value \ when \ device \ is \ unprogrammed$   $u = Unchanged \ from \ programmed \ state$ 

# 19.2 Watchdog Timer (WDT)

The Watchdog Timer is a free running on-chip RC oscillator, which does not require any external components. This RC oscillator is separate from the RC oscillator of the OSC1/CLKI pin. That means that the WDT will run, even if the clock on the OSC1/CLKI and OSC2/CLKO/RA6 pins of the device has been stopped, for example, by execution of a SLEEP instruction.

During normal operation, a WDT time-out generates a device RESET (Watchdog Timer Reset). If the device is in SLEEP mode, a WDT time-out causes the device to wake-up and continue with normal operation (Watchdog Timer Wake-up). The TO bit in the RCON register will be cleared upon a WDT time-out.

The Watchdog Timer is enabled/disabled by a device configuration bit. If the WDT is enabled, software execution may not disable this function. When the WDTEN configuration bit is cleared, the SWDTEN bit enables/disables the operation of the WDT.

The WDT time-out period values may be found in the Electrical Specifications (Section 22.0) under parameter D031. Values for the WDT postscaler may be assigned using the configuration bits.

Note: The CLRWDT and SLEEP instructions clear the WDT and the postscaler, if assigned to the WDT and prevent it from timing out and generating a device RESET condition.

Note: When a CLRWDT instruction is executed and the postscaler is assigned to the WDT, the postscaler count will be cleared, but the postscaler assignment is not changed.

#### 19.2.1 CONTROL REGISTER

Register 19-14 shows the WDTCON register. This is a readable and writable register, which contains a control bit that allows software to override the WDT enable configuration bit, only when the configuration bit has disabled the WDT.

#### **REGISTER 19-14: WDTCON REGISTER**

bit 0

U-0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-0
_	_	_	_	_	_	_	SWDTEN
bit 7							bit 0

#### bit 7-1 Unimplemented: Read as '0'

**SWDTEN:** Software Controlled Watchdog Timer Enable bit

- 1 = Watchdog Timer is on
- 0 = Watchdog Timer is turned off if the WDTEN configuration bit in the configuration register = '0'

Legend:

 $R = Readable \ bit$   $W = Writable \ bit$   $U = Unimplemented \ bit, \ read \ as \ '0'$   $- n = Value \ at \ POR$ 

#### 19.2.2 WDT POSTSCALER

The WDT has a postscaler that can extend the WDT Reset period. The postscaler is selected at the time of the device programming, by the value written to the CONFIG2H configuration register.

FIGURE 19-1: WATCHDOG TIMER BLOCK DIAGRAM




TABLE 19-2: SUMMARY OF WATCHDOG TIMER REGISTERS

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
CONFIG2H	_	_	_	_	WDTPS2	WDTPS2	WDTPS0	WDTEN
RCON	IPEN	_	_	RI	TO	PD	POR	BOR
WDTCON	_	_	_	_	_	_	_	SWDTEN

Legend: Shaded cells are not used by the Watchdog Timer.

# 19.3 Power-down Mode (SLEEP)

Power-down mode is entered by executing a SLEEP instruction.

If enabled, the Watchdog Timer will be cleared, but keeps running, the  $\overline{PD}$  bit (RCON<3>) is cleared, the  $\overline{TO}$  (RCON<4>) bit is set, and the oscillator driver is turned off. The I/O ports maintain the status they had before the SLEEP instruction was executed (driving high, low or hi-impedance).

For lowest current consumption in this mode, place all I/O pins at either VDD or Vss, ensure no external circuitry is drawing current from the I/O pin, power-down the A/D and disable external clocks. Pull all I/O pins that are hi-impedance inputs, high or low externally, to avoid switching currents caused by floating inputs. The TOCKI input should also be at VDD or Vss for lowest current consumption. The contribution from on-chip pull-ups on PORTB should be considered.

The MCLR pin must be at a logic high level (VIHMC).

#### 19.3.1 WAKE-UP FROM SLEEP

The device can wake-up from SLEEP through one of the following events:

- 1. External RESET input on  $\overline{MCLR}$  pin.
- 2. Watchdog Timer Wake-up (if WDT was enabled).
- Interrupt from INT pin, RB port change or a Peripheral Interrupt.

The following peripheral interrupts can wake the device from SLEEP:

- 1. PSP read or write.
- TMR1 interrupt. Timer1 must be operating as an asynchronous counter.
- TMR3 interrupt. Timer3 must be operating as an asynchronous counter.
- 4. CCP Capture mode interrupt.
- Special event trigger (Timer1 in Asynchronous mode using an external clock).
- 6. MSSP (START/STOP) bit detect interrupt.
- MSSP transmit or receive in Slave mode (SPI/I<sup>2</sup>C).
- 8. USART RX or TX (Synchronous Slave mode).
- 9. A/D conversion (when A/D clock source is RC).
- 10. EEPROM write operation complete.
- 11. LVD interrupt.

Other peripherals cannot generate interrupts, since during SLEEP, no on-chip clocks are present.

External MCLR Reset will cause a device RESET. All other events are considered a continuation of program execution and will cause a "wake-up". The TO and PD bits in the RCON register can be used to determine the cause of the device RESET. The PD bit, which is set on power-up, is cleared when SLEEP is invoked. The TO bit is cleared, if a WDT time-out occurred (and caused wake-up).

When the SLEEP instruction is being executed, the next instruction (PC + 2) is pre-fetched. For the device to wake-up through an interrupt event, the corresponding interrupt enable bit must be set (enabled). Wake-up is regardless of the state of the GIE bit. If the GIE bit is clear (disabled), the device continues execution at the instruction after the SLEEP instruction. If the GIE bit is set (enabled), the device executes the instruction after the SLEEP instruction and then branches to the interrupt address. In cases where the execution of the instruction following SLEEP is not desirable, the user should have a NOP after the SLEEP instruction.

#### 19.3.2 WAKE-UP USING INTERRUPTS


When global interrupts are disabled (GIE cleared) and any interrupt source has both its interrupt enable bit and interrupt flag bit set, one of the following will occur:

- If an interrupt condition (interrupt flag bit and interrupt enable bits are set) occurs **before** the execution of a SLEEP instruction, the SLEEP instruction will complete as a NOP. Therefore, the WDT and WDT postscaler will not be cleared, the TO bit will not be set and PD bits will not be cleared.
- If the interrupt condition occurs during or after
  the execution of a SLEEP instruction, the device
  will immediately wake-up from SLEEP. The
  SLEEP instruction will be completely executed
  before the wake-up. Therefore, the WDT and
  WDT postscaler will be cleared, the TO bit will be
  set and the PD bit will be cleared.

Even if the flag bits were checked before executing a SLEEP instruction, it may be possible for flag bits to become set before the SLEEP instruction completes. To determine whether a SLEEP instruction executed, test the  $\overline{PD}$  bit. If the  $\overline{PD}$  bit is set, the SLEEP instruction was executed as a NOP.

To ensure that the WDT is cleared, a CLRWDT instruction should be executed before a SLEEP instruction.

# FIGURE 19-2: WAKE-UP FROM SLEEP THROUGH INTERRUPT<sup>(1,2)</sup>



Note 1: XT, HS or LP Oscillator mode assumed.

2: GIE = '1' assumed. In this case, after wake-up, the processor jumps to the interrupt routine. If GIE = '0', execution will continue in-line.

3: Tost = 1024 Tosc (drawing not to scale). This delay will not occur for RC and EC Osc modes.

4: CLKO is not available in these Osc modes, but shown here for timing reference.

# 19.4 Program Verification and Code Protection

The overall structure of the code protection on the PIC18 FLASH devices differs significantly from other PICmicro devices.

The user program memory is divided into five blocks. One of these is a boot block of 512 bytes. The remainder of the memory is divided into four blocks on binary boundaries.

Each of the five blocks has three code protection bits associated with them. They are:

- · Code Protect bit (CPn)
- · Write Protect bit (WRTn)
- External Block Table Read bit (EBTRn)

Figure 19-3 shows the program memory organization for 16- and 32-Kbyte devices, and the specific code protection bit associated with each block. The actual locations of the bits are summarized in Table 19-3.

FIGURE 19-3: CODE PROTECTED PROGRAM MEMORY FOR PIC18F2XX/4XX

MEMORY S	IZE/DEVICE		Black Oads Bustonting
16 Kbytes (PIC18FX42)	32 Kbytes (PIC18FX52)	Address Range	Block Code Protection Controlled By:
Boot Block	Boot Block	000000h 0001FFh	CPB, WRTB, EBTRB
Block 0	Block 0	000200h 001FFFh	CP0, WRT0, EBTR0
Block 1	Block 1	002000h 003FFFh	CP1, WRT1, EBTR1
Unimplemented Read 0's	Block 2	004000h 005FFFh	CP2, WRT2, EBTR2
Unimplemented Read 0's	Block 3	006000h 007FFFh	CP3, WRT3, EBTR3
Unimplemented Read 0's	Unimplemented Read 0's	008000h	(Unimplemented Memory Space)

TABLE 19-3: SUMMARY OF CODE PROTECTION REGISTERS

File Name		Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	
300008h	CONFIG5L	_	_	_	_	CP3	CP2	CP1	CP0	
300009h	CONFIG5H	CPD	СРВ	_	_	_	_	_	_	
30000Ah	CONFIG6L	_	_	_	_	WRT3	WRT2	WRT1	WRT0	
30000Bh	CONFIG6H	WRTD	WRTB	WRTC	_	_	_	_	_	
30000Ch	CONFIG7L	_	_	_	_	EBTR3	EBTR2	EBTR1	EBTR0	
30000Dh	CONFIG7H	_	EBTRB	_	_	_	_	_	_	

Legend: Shaded cells are unimplemented.

# 19.4.1 PROGRAM MEMORY CODE PROTECTION


The user memory may be read to or written from any location using the Table Read and Table Write instructions. The device ID may be read with Table Reads. The configuration registers may be read and written with the Table Read and Table Write instructions.

In User mode, the CPn bits have no direct effect. CPn bits inhibit external reads and writes. A block of user memory may be protected from Table Writes if the WRTn configuration bit is '0'. The EBTRn bits control Table Reads. For a block of user memory with the EBTRn bit set to '0', a Table Read instruction that executes from within that block is allowed to read. A Table Read instruction that executes from a location

outside of that block is not allowed to read, and will result in reading '0's. Figures 19-4 through 19-6 illustrate Table Write and Table Read protection.

Note: Code protection bits may only be written to a '0' from a '1' state. It is not possible to write a '1' to a bit in the '0' state. Code protection bits are only set to '1' by a full chip erase or block erase function. The full chip erase and block erase functions can only be initiated via ICSP or an external programmer.


FIGURE 19-4: TABLE WRITE (WRTn) DISALLOWED



**Register Values Program Memory Configuration Bit Settings** 000000h WRTB, EBTRB = 11 0001FFh 000200h TBLPTR = 000FFF WRT0,EBTR0 = 10 001FFFh 002000h PC = 002FFETBLRD \* WRT1,EBTR1 = 11 003FFFh 004000h WRT2,EBTR2 = 11 005FFFh 006000h WRT3,EBTR3 = 11 007FFFh Results: All Table Reads from external blocks to Blockn are disabled whenever EBTRn = '0'. TABLAT register returns a value of "0".

FIGURE 19-5: EXTERNAL BLOCK TABLE READ (EBTRn) DISALLOWED

FIGURE 19-6: EXTERNAL BLOCK TABLE READ (EBTRn) ALLOWED



# 19.4.2 DATA EEPROM CODE PROTECTION

The entire Data EEPROM is protected from external reads and writes by two bits: CPD and WRTD. CPD inhibits external reads and writes of Data EEPROM. WRTD inhibits external writes to Data EEPROM. The CPU can continue to read and write Data EEPROM regardless of the protection bit settings.

# 19.4.3 CONFIGURATION REGISTER PROTECTION

The configuration registers can be write protected. The WRTC bit controls protection of the configuration registers. In User mode, the WRTC bit is readable only. WRTC can only be written via ICSP or an external programmer.

#### 19.5 ID Locations

Eight memory locations (200000h - 200007h) are designated as ID locations, where the user can store checksum or other code identification numbers. These locations are accessible during normal execution through the TBLRD and TBLWT instructions, or during program/verify. The ID locations can be read when the device is code protected.

The sequence for programming the ID locations is similar to programming the FLASH memory (see Section 5.5.1).

# 19.6 In-Circuit Serial Programming

PIC18FXXX microcontrollers can be serially programmed while in the end application circuit. This is simply done with two lines for clock and data, and three other lines for power, ground and the programming voltage. This allows customers to manufacture boards with unprogrammed devices, and then program the microcontroller just before shipping the product. This also allows the most recent firmware or a custom firmware to be programmed.

### 19.7 In-Circuit Debugger

When the DEBUG bit in configuration register CONFIG4L is programmed to a '0', the In-Circuit Debugger functionality is enabled. This function allows simple debugging functions when used with MPLAB® IDE. When the microcontroller has this feature enabled, some of the resources are not available for general use. Table 19-4 shows which features are consumed by the background debugger.

TABLE 19-4: DEBUGGER RESOURCES

I/O pins	RB6, RB7
Stack	2 levels
Program Memory	512 bytes
Data Memory	10 bytes

To use the In-Circuit Debugger function of the microcontroller, the design must implement In-Circuit Serial Programming connections to  $\overline{\text{MCLR}}/\text{VPP}$ , VDD, GND, RB7 and RB6. This will interface to the In-Circuit Debugger module available from Microchip or one of the third party development tool companies.

# 19.8 Low Voltage ICSP Programming

The LVP bit configuration register CONFIG4L enables low voltage ICSP programming. This mode allows the microcontroller to be programmed via ICSP using a VDD source in the operating voltage range. This only means that VPP does not have to be brought to VIHH, but can instead be left at the normal operating voltage. In this mode, the RB5/PGM pin is dedicated to the programming function and ceases to be a general purpose I/O pin. During programming, VDD is applied to the MCLR/VPP pin. To enter Programming mode, VDD must be applied to the RB5/PGM, provided the LVP bit is set. The LVP bit defaults to a ('1') from the factory.

- Note 1: The High Voltage Programming mode is always available, regardless of the state of the LVP bit, by applying VIHH to the MCLR pin.
  - 2: While in low voltage ICSP mode, the RB5 pin can no longer be used as a general purpose I/O pin, and should be held low during normal operation to protect against inadvertent ICSP mode entry.
  - 3: When using low voltage ICSP programming (LVP), the pull-up on RB5 becomes disabled. If TRISB bit 5 is cleared, thereby setting RB5 as an output, LATB bit 5 must also be cleared for proper operation.

If Low Voltage Programming mode is not used, the LVP bit can be programmed to a '0' and RB5/PGM becomes a digital I/O pin. However, the LVP bit may only be programmed when programming is entered with VIHH on MCLR/VPP.

It should be noted that once the LVP bit is programmed to 0, only the High Voltage Programming mode is available and only High Voltage Programming mode can be used to program the device.

When using low voltage ICSP, the part must be supplied 4.5V to 5.5V, if a bulk erase will be executed. This includes reprogramming of the code protect bits from an on-state to off-state. For all other cases of low voltage ICSP, the part may be programmed at the normal operating voltage. This means unique user IDs, or user code can be reprogrammed or added.

### 20.0 INSTRUCTION SET SUMMARY

The PIC18FXXX instruction set adds many enhancements to the previous PICmicro instruction sets, while maintaining an easy migration from these PICmicro instruction sets.

Most instructions are a single program memory word (16-bits), but there are three instructions that require two program memory locations.

Each single word instruction is a 16-bit word divided into an OPCODE, which specifies the instruction type and one or more operands, which further specify the operation of the instruction.

The instruction set is highly orthogonal and is grouped into four basic categories:

- · Byte-oriented operations
- · Bit-oriented operations
- · Literal operations
- · Control operations

The PIC18FXXX instruction set summary in Table 20-2 lists **byte-oriented**, **bit-oriented**, **literal** and **control** operations. Table 20-1 shows the opcode field descriptions.

Most byte-oriented instructions have three operands:

- The file register (specified by 'f')
- The destination of the result (specified by 'd')
- 3. The accessed memory (specified by 'a')

The file register designator 'f' specifies which file register is to be used by the instruction.

The destination designator 'd' specifies where the result of the operation is to be placed. If 'd' is zero, the result is placed in the WREG register. If 'd' is one, the result is placed in the file register specified in the instruction.

All bit-oriented instructions have three operands:

- 1. The file register (specified by 'f')
- The bit in the file register (specified by 'b')
- 3. The accessed memory (specified by 'a')

The bit field designator 'b' selects the number of the bit affected by the operation, while the file register designator 'f' represents the number of the file in which the bit is located.

The **literal** instructions may use some of the following operands:

- A literal value to be loaded into a file register (specified by 'k')
- The desired FSR register to load the literal value into (specified by 'f')
- No operand required (specified by '—')

The **control** instructions may use some of the following operands:

- A program memory address (specified by 'n')
- The mode of the Call or Return instructions (specified by 's')
- The mode of the Table Read and Table Write instructions (specified by 'm')
- No operand required (specified by '—')

All instructions are a single word, except for three double-word instructions. These three instructions were made double-word instructions so that all the required information is available in these 32 bits. In the second word, the 4-MSbs are 1's. If this second word is executed as an instruction (by itself), it will execute as a NOP.

All single word instructions are executed in a single instruction cycle, unless a conditional test is true or the program counter is changed as a result of the instruction. In these cases, the execution takes two instruction cycles with the additional instruction cycle(s) executed as a NOP.

The double-word instructions execute in two instruction cycles.

One instruction cycle consists of four oscillator periods. Thus, for an oscillator frequency of 4 MHz, the normal instruction execution time is 1  $\mu$ s. If a conditional test is true or the program counter is changed as a result of an instruction, the instruction execution time is 2  $\mu$ s. Two-word branch instructions (if true) would take 3  $\mu$ s.

Figure 20-1 shows the general formats that the instructions can have.

All examples use the format 'nnh' to represent a hexadecimal number, where 'h' signifies a hexadecimal digit.

The Instruction Set Summary, shown in Table 20-2, lists the instructions recognized by the Microchip Assembler (MPASM $^{TM}$ ).

Section 20.1 provides a description of each instruction.

# PIC18FXX2

# TABLE 20-1: OPCODE FIELD DESCRIPTIONS

Field	Description
a	RAM access bit a = 0: RAM location in Access RAM (BSR register is ignored)
	a = 1: RAM bank is specified by BSR register
bbb	Bit address within an 8-bit file register (0 to 7)
BSR	Bank Select Register. Used to select the current RAM bank.
d	Destination select bit; d = 0: store result in WREG, d = 1: store result in file register f.
dest	Destination either the WREG register or the specified register file location
f	8-bit Register file address (0x00 to 0xFF)
fs	12-bit Register file address (0x000 to 0xFFF). This is the source address.
fd	12-bit Register file address (0x000 to 0xFFF). This is the destination address.
k	Literal field, constant data or label (may be either an 8-bit, 12-bit or a 20-bit value)
label	Label name
mm	The mode of the TBLPTR register for the Table Read and Table Write instructions. Only used with Table Read and Table Write instructions:
*	No Change to register (such as TBLPTR with Table reads and writes)
*+	Post-Increment register (such as TBLPTR with Table reads and writes)
*	Post-Decrement register (such as TBLPTR with Table reads and writes)
+*	Pre-Increment register (such as TBLPTR with Table reads and writes)
n	The relative address (2's complement number) for relative branch instructions, or the direct address for Call/Branch and Return instructions
PRODH	Product of Multiply high byte
PRODL	Product of Multiply low byte
s	Fast Call/Return mode select bit. s = 0: do not update into/from shadow registers s = 1: certain registers loaded into/from shadow registers (Fast mode)
u	Unused or Unchanged
WREG	Working register (accumulator)
x	Don't care (0 or 1) The assembler will generate code with x = 0. It is the recommended form of use for compatibility with all Microchip software tools.
TBLPTR	21-bit Table Pointer (points to a Program Memory location)
TABLAT	8-bit Table Latch
TOS	Top-of-Stack
PC	Program Counter
PCL	Program Counter Low Byte
PCH	Program Counter High Byte
PCLATH	Program Counter High Byte Latch
PCLATU	Program Counter Upper Byte Latch
GIE	Global Interrupt Enable bit
WDT	Watchdog Timer
TO	Time-out bit
PD	Power-down bit
C, DC, Z, OV, N	ALU status bits Carry, Digit Carry, Zero, Overflow, Negative
[ ]	Optional
( )	Contents
$\rightarrow$	Assigned to
< >	Register bit field
€	In the set of
italics	User defined term (font is courier)

# FIGURE 20-1: GENERAL FORMAT FOR INSTRUCTIONS

FIGURE 20-1:	GENERAL FORMAT FOR INSTRUCTIONS	
	Byte-oriented file register operations	Example Instruction
	OPCODE d a f (FILE #)  d = 0 for result destination to be WREG register d = 1 for result destination to be file register (f) a = 0 to force Access Bank a = 1 for BSR to select bank f = 8-bit file register address	ADDWF MYREG, W, B
	Byte to Byte move operations (2-word)  15 12 11 0	
	15 12 11 0 OPCODE   f (Source FILE #)	MOVFF MYREG1, MYREG2
	15 12 11 0	
	1111 f (Destination FILE #)	
	f = 12-bit file register address	
	Bit-oriented file register operations	
	15 12 11 9 8 7 0 OPCODE b (BIT #) a f (FILE #)	BSF MYREG, bit, B
	<ul> <li>b = 3-bit position of bit in file register (f)</li> <li>a = 0 to force Access Bank</li> <li>a = 1 for BSR to select bank</li> <li>f = 8-bit file register address</li> </ul>	
	Literal operations	
	15 8 7 0	
	OPCODE k (literal)	MOVLW 0x7F
	k = 8-bit immediate value	
	Control operations	
	CALL, GOTO and Branch operations	
	15 8 7 0 OPCODE n<7:0> (literal)	GOTO Label
	15 12 11 0	0010 2000
	1111 n<19:8> (literal)	
	n = 20-bit immediate value	
	15 8 7 0	
	OPCODE S n<7:0> (literal)	CALL MYFUNC
	15 12 11 0 n<19:8> (literal)	
	S = Fast bit	
	15 11 10 0	
	15 11 10 0 OPCODE n<10:0> (literal)	BRA MYFUNC
	15 8 7 0 OPCODE n<7:0> (literal)	BC MYFUNC

TABLE 20-2: PIC18FXXX INSTRUCTION SET

MSb	Mnemonic, Operands		Description	Cycles	16-	·Bit Instri	uction W	ord	Status	Notes
ADDWF f, d, a Add WREG and f ADDWFC f, d, a Add WREG and Carry bit to f ADDWFC f, d, a ADD WREG with f 1 0010 0da ffff ffff ffff C, DC, Z, OV, N 1, 2 CLRF f, d, a ADD WREG with f 1 0010 101a ffff ffff Z, N 1, 2 CLRF f, d, a Complement f 1 0010 101a ffff ffff Z, N 1, 2 CLRF f, d, a Compare f with WREG, skip = 1 (2 or 3) 0110 001a ffff ffff Z, N 1, 2 CPFSCG f, a Compare f with WREG, skip > 1 (2 or 3) 0110 001a ffff ffff None 4 4 COMPATE for the WAREG, skip > 1 (2 or 3) 0110 010a ffff ffff None 4 4 COMPATE for the WAREG, skip > 1 (2 or 3) 0110 010a ffff ffff None 4 4 COMPATE for the WAREG, skip > 1 (2 or 3) 0110 010a ffff ffff None 4 4 COMPATE for the WAREG, skip > 1 (2 or 3) 0110 010a ffff ffff None 4 4 COMPATE for the WAREG, skip > 1 (2 or 3) 0110 010a ffff ffff None 4 4 COMPATE for the WAREG, skip > 1 (2 or 3) 0110 010a ffff ffff None 5 (2 or 3) 0110 010a ffff ffff None 6 (3 or 3) 0100 01da ffff ffff None 7 (3 or 3) 0100 01da ffff ffff None 7 (4 or 3) 0100 01da ffff ffff None 7 (5 or 3) 0100 01da ffff ffff None 7 (5 or 3) 0100 01da ffff ffff None 8 (7 or 3) 0100 01da ffff ffff None 1 (2 or 3) 0100 01da ffff ffff None 1 (2 or 3) 0100 01da ffff ffff None 1 (2 or 3) 0100 01da ffff ffff None 1 (2 or 3) 0100 01da ffff ffff None 1 (2 or 3) 0100 01da ffff ffff None 1 (2 or 3) 0100 01da ffff ffff None 1 (2 or 3) 0100 01da ffff ffff None 1 (2 or 3) 0100 01da ffff ffff None 1 (2 or 3) 0100 01da ffff ffff ffff None 1 (2 or 3) 0100 01da ffff ffff ffff None 1 (2 or 3) 0100 01da ffff ffff ffff None 1 (2 or 3) 0100 01da ffff ffff ffff None None 1 (2 or 3) 0100 01da ffff ffff ffff None 1 (2 or 3) 0100 01da ffff ffff ffff None None 1 (2 or 3) 0100 01da ffff ffff ffff None None None None None None None None			Description	Cycles	MSb			LSb	Affected	Notes
ADDWFC f, d, a Add WREG and Carry bit to f ANDWF f, d, a CLRF f, d, a CLRF f, a CLRF f, a CLRF f, a CLRF f, a COMF f, d, a COMPLEM F, d, a CLRF f, a DECFSCT f, a DECRF G, d, a	BYTE-ORIE	NTED F	ILE REGISTER OPERATIONS							
ANDWF f, d, a Clarf f, a Complement f Clarf f, a Compare f with WREG, skip = 1 (2 or 3) 0110 010a fffff fffff ffff ffff ffff ff	ADDWF	f, d, a	Add WREG and f	1	0010	01da0	ffff	ffff	C, DC, Z, OV, N	1, 2
CLRF f, a Cloar f Complement f	ADDWFC	f, d, a	Add WREG and Carry bit to f	1	0010	0da	ffff	ffff	C, DC, Z, OV, N	1, 2
CLRF f, a Cloar f Complement f	ANDWF	f, d, a	AND WREG with f	1	0001	01da	ffff	ffff	Z, N	1,2
CPFSEQ f, a CPFSGT f, a CPFSGT f, a CPFSGT f, a CPFSGT f, a COmpare f with WREG, skip > CPFSLT f, a COmpare f with WREG, skip > 1 (2 or 3) 0110 010a ffff ffff None 4 4 CPFSLT f, a Decrement f, a Decrement f, a Decrement f, skip if 0 1 (2 or 3) 0110 000a ffff ffff None 1, 2 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff ffff None 1, 2, 3, 4 000 010da ffff ffff None 1, 2, 3, 4 000 010da ffff ffff ffff None 1, 2, 3, 4 000 010da ffff ffff ffff None 1, 2 000 000da ffff ffff ffff None 1, 2 000da ffff ffff ffff None 1, 2 000da ffff fffff ffff None 1, 2 00da ffff fffff ffff	CLRF	f, a	Clear f	1	0110	101a	ffff	ffff	Z	
CPFSGT	COMF	f, d, a	Complement f	1	0001	11da	ffff	ffff	Z, N	1, 2
CPFSGT	CPFSEQ	f, a	Compare f with WREG, skip =	1 (2 or 3)	0110	001a	ffff	ffff	None	4
1, 2	CPFSGT	,		, ,	0110	010a	ffff	ffff	None	4
DECF	CPFSLT		Compare f with WREG, skip <	1 (2 or 3)	0110	000a	ffff	ffff	None	1, 2
DECFSZ f, d, a Decrement f, Skip if 0	DECF	f, d, a	Decrement f	1 ` ′	0000	01da	ffff	ffff	C. DC. Z. OV. N	
DCFSNZ	DECFSZ	f, d, a	Decrement f, Skip if 0	1 (2 or 3)	0010	11da	ffff	ffff		
INCF	DCFSNZ			1 (2 or 3)	0100	11da	ffff	ffff	None	
INCFSZ	INCF			1 ` ´	0010	10da	ffff	ffff	C. DC. Z. OV. N	
INFSNZ	INCFSZ		Increment f, Skip if 0	1 (2 or 3)	0011		ffff		1 ' ' ' '	
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	INFSNZ			, ,			ffff			1. 2
$\begin{array}{llllllllllllllllllllllllllllllllllll$	IORWF			' /					Z. N	
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	MOVF			1	1	00da	ffff			
MOVWF   f, a   Move WREG to f   1   0110   111a   fffff   fffff   Mone   Move WREG to f   1   0000   001a   fffff   ffff   Mone   Move WREG to f   1   0110   111a   fffff   ffff   Mone   Move WREG to f   1   0110   110a   fffff   ffff   Mone   Move WREG to f   1   0110   110a   fffff   ffff   Mone   Move WREG to f   1   0110   110a   fffff   ffff   Mone   Move WREG to f   Move WREG to f   1   0110   110a   fffff   ffff   Mone   Move WREG to f   Move WREG to f	MOVFF		Move f <sub>e</sub> (source) to 1st word	2	1100	ffff	ffff			
MOVWF         f, a Move WREG to f         1         0110         111a         fffff         fffff         None           MULWF         f, a Multiply WREG with f         1         0000         001a         fffff         ffff         None         None           NEGF         f, a Negate f         1         0110         110a         fffff         ffff         C, DC, Z, OV, N         1, 2           RLCF         f, d, a Rotate Left f through Carry         1         0100         01da         fffff         ffff         C, Z, N         1, 2           RRCF         f, d, a Rotate Right f through Carry         1         0100         01da         fffff         ffff         C, Z, N         1, 2           RRNCF         f, d, a Rotate Right f (No Carry)         1         0100         00da         ffff         ffff         Z, N         None         1, 2           SETF         f, a Set f         1         0110         100a         ffff         ffff         C, Z, N         None         None         C, DC, Z, OV, N         1, 2           SUBFWB f, d, a Subtract WREG from f         1         0101         10da         ffff         ffff         C, DC, Z, OV, N         1, 2           SWAPF f, d, a Swap nibbles in f		3, 0			1111	ffff	ffff	ffff		
NEGF         f, a         Negate f         1         0110         110a         fffff         C, DC, Z, OV, N         1, 2           RLCF         f, d, a         Rotate Left f through Carry         1         0011         01da         fffff         ffff         C, Z, N         1, 2           RRNCF         f, d, a         Rotate Right f through Carry         1         0010         01da         fffff         ffff         C, Z, N         1, 2           RRNCF         f, d, a         Rotate Right f (No Carry)         1         0100         00da         fffff         ffff         C, Z, N         Z, N         1, 2           SETF         f, a         Set f         1         0100         00da         fffff         ffff         KONDR         Z, N         None         C, DC, Z, OV, N         1, 2           SUBFWB f, d, a         Subtract WREG with borrow         1         0101         11da         fffff         ffff         C, DC, Z, OV, N         1, 2           SWAPF f, d, a         Swap nibbles in f         1         0011         10da         fffff         ffff         None         4         None         1, 2           XORWF f, d, a         Exclusive OR WREG with f         1         1         10da	MOVWF	f, a	,	1	0110	111a	ffff	ffff	None	
NEGF         f, a         Negate f         1         0110         110a         fffff         C, DC, Z, OV, N         1, 2           RLCF         f, d, a         Rotate Left f through Carry         1         0011         01da         fffff         ffff         C, Z, N         1, 2           RRNCF         f, d, a         Rotate Right f through Carry         1         0010         01da         fffff         ffff         C, Z, N         1, 2           RRNCF         f, d, a         Rotate Right f (No Carry)         1         0100         00da         fffff         ffff         C, Z, N         Z, N         1, 2           SETF         f, a         Set f         1         0100         00da         fffff         ffff         KONDR         Z, N         None         C, DC, Z, OV, N         1, 2           SUBFWB f, d, a         Subtract WREG with borrow         1         0101         11da         fffff         ffff         C, DC, Z, OV, N         1, 2           SWAPF f, d, a         Swap nibbles in f         1         0011         10da         fffff         ffff         None         4         None         1, 2           XORWF f, d, a         Exclusive OR WREG with f         1         1         10da	MULWF	f, a	Multiply WREG with f	1	0000	001a	ffff	ffff	None	
RLNCF f, d, a Rotate Left f (No Carry)	NEGF	f, a		1	0110	110a	ffff	ffff	C, DC, Z, OV, N	1, 2
RRCF         f, d, a         Rotate Right f through Carry         1         0011         00da         fffff         G, Z, N           RRNCF         f, d, a         Rotate Right f (No Carry)         1         0100         00da         fffff         G, Z, N           SETF         f, a         Set f         1         0100         100a         fffff         G, Z, N           SUBFWB         f, d, a         Subtract f from WREG with borrow         1         0101         01da         fffff         G, DC, Z, OV, N         1, 2           SUBWFB         f, d, a         Subtract WREG from f with borrow         1         0101         10da         fffff         G, DC, Z, OV, N         1, 2           SWAPF         f, d, a         Swap nibbles in f         1         0011         10da         fffff         ffff         None         4           TSTFSZ         f, a         Test f, skip if 0         1 (2 or 3)         0110         011a         fffff         ffff         None         1, 2           XORWF         f, d, a         Exclusive OR WREG with f         1         0001         10da         fffff         ffff         None         1, 2           BBF         f, b, a         Bit Clear f         1         <	RLCF	f, d, a	Rotate Left f through Carry	1	0011	01da	ffff	ffff	C, Z, N	,
RRCF         f, d, a         Rotate Right f through Carry         1         0011         00da         fffff         G, Z, N           RRNCF         f, d, a         Rotate Right f (No Carry)         1         0100         00da         fffff         G, Z, N           SETF         f, a         Set f         1         0100         100a         fffff         G, Z, N           SUBFWB         f, d, a         Subtract f from WREG with borrow         1         0101         01da         fffff         G, DC, Z, OV, N         1, 2           SUBWFB         f, d, a         Subtract WREG from f with borrow         1         0101         10da         fffff         G, DC, Z, OV, N         1, 2           SWAPF         f, d, a         Swap nibbles in f         1         0011         10da         fffff         ffff         None         4           TSTFSZ         f, a         Test f, skip if 0         1 (2 or 3)         0110         011a         fffff         ffff         None         1, 2           XORWF         f, d, a         Exclusive OR WREG with f         1         0001         10da         fffff         ffff         None         1, 2           BBF         f, b, a         Bit Clear f         1         <	RLNCF	f, d, a	Rotate Left f (No Carry)	1	0100	01da	ffff	ffff	Z, N	1, 2
RRNCF         f, d, a         Rotate Right f (No Carry)         1         0100         00da         fffff         ffff         Z, N           SETF         f, a         Set f         1         0110         100a         fffff         ffff         None           SUBFWB         f, d, a         Subtract f from WREG with borrow         1         0101         01da         fffff         C, DC, Z, OV, N         1, 2           SUBWF         f, d, a         Subtract WREG from f with borrow         1         0101         11da         fffff         C, DC, Z, OV, N         1, 2           SWAPF         f, d, a         Swap nibbles in f         1         0011         10da         fffff         ffff         None         4           TSTFSZ         f, a         Test f, skip if 0         1 (2 or 3)         0110         011a         fffff         ffff         None         1, 2           XORWF         f, d, a         Exclusive OR WREG with f         1         0001         10da         fffff         ffff         None         1, 2           BBF         f, b, a         Bit Clear f         1         1000         bbba         fffff         ffff         None         1, 2           1         1	RRCF			1	0011	00da	ffff	ffff	C, Z, N	-
SETF f, a Set f SUBFWB f, d, a Subtract f from WREG with borrow  SUBWF f, d, a Subtract WREG from f SUBWFB f, d, a Subtract WREG from f with borrow  SUBWFB f, d, a Subtract WREG from f with borrow  SWAPF f, d, a Swap nibbles in f TSTFSZ f, a Test f, skip if 0 XORWF f, d, a Exclusive OR WREG with f  BIT-ORIENTED FILE REGISTER OPERATIONS  BCF f, b, a Bit Clear f BSF f, b, a Bit Set f  1 0110 100a fffff ffff C, DC, Z, OV, N 1, 2 0101 10da fffff ffff None 4 1 (2 or 3) 0110 011a fffff ffff None 1, 2 2 None 1, 2 3 None 1, 2 4 None 1, 2 5 None 1, 2	RRNCF			1	0100	00da	ffff	ffff		
SUBWF   f, d, a   Subtract WREG from f   1   0101   11da   fffff   ffff   C, DC, Z, OV, N   SUBWFB   f, d, a   Subtract WREG from f with borrow   SWAPF   f, d, a   Swap nibbles in f   1   0011   10da   fffff   ffff   C, DC, Z, OV, N   1, 2   1,	SETF		1	1	0110	100a	ffff	ffff		
SUBWFB f, d, a Subtract WREG from f with borrow  SWAPF f, d, a Swap nibbles in f TSTFSZ f, a Test f, skip if 0 XORWF f, d, a Exclusive OR WREG with f  BIT-ORIENTED FILE REGISTER OPERATIONS  BCF f, b, a Bit Clear f BSF f, b, a Bit Set f  SWAPG from f with borrow  1 0101 10da fffff ffff None 1 1 0011 10da fffff ffff None 1 1 0001 10da fffff ffff None 1 1 1 1001 bbba fffff ffff None 1 1 2 1000 bbba fffff ffff None	SUBFWB	f, d, a		1	0101	01da	ffff	ffff	C, DC, Z, OV, N	1, 2
SUBWFB f, d, a Subtract WREG from f with borrow  SWAPF f, d, a Swap nibbles in f TSTFSZ f, a Test f, skip if 0 XORWF f, d, a Exclusive OR WREG with f  BIT-ORIENTED FILE REGISTER OPERATIONS  BCF f, b, a Bit Clear f BSF f, b, a Bit Set f  SWAPG from f with borrow  1 0101 10da fffff ffff None 1 1 0011 10da fffff ffff None 1 1 0001 10da fffff ffff None 1 1 1 1001 bbba fffff ffff None 1 1 2 1000 bbba fffff ffff None	SUBWF	f. d. a	Subtract WREG from f	1	0101	11da	ffff	ffff	C. DC. Z. OV. N	
SWAPF   f, d, a   Swap nibbles in f   1   0011   10da   fffff   ffff   None   4   TSTFSZ   f, a   Test f, skip if 0   1 (2 or 3)   0110   011a   fffff   ffff   None   1, 2   XORWF   f, d, a   Exclusive OR WREG with f   1   0001   10da   fffff   ffff   Z, N   BIT-ORIENTED FILE REGISTER OPERATIONS    BCF   f, b, a   Bit Clear f   1   1001   bbba   fffff   ffff   None   1, 2   BSF   f, b, a   Bit Set f   1   1000   bbba   fffff   ffff   None   1, 2   1, 2   1   1, 2	SUBWFB			1						1. 2
SWAPF         f, d, a         Swap nibbles in f         1         0011         10da         fffff         ffff         None         4           TSTFSZ         f, a         Test f, skip if 0         1 (2 or 3)         0110         011a         ffff         ffff         None         1, 2           XORWF         f, d, a         Exclusive OR WREG with f         1         0001         10da         ffff         ffff         Z, N         1           BIT-ORIENTED FILE REGISTER OPERATIONS         B         1         1001         bbba         fffff         None         1, 2           BSF         f, b, a         Bit Clear f         1         1000         bbba         fffff         None         1, 2           BSF         f, b, a         Bit Set f         1         1000         bbba         fffff         ffff         None         1, 2		., .,			1 - 1 -				-,, -,,	-, -
TSTFSZ f, a Test f, skip if 0	SWAPF	f, d, a	Swap nibbles in f	1	0011	10da	ffff	ffff	None	4
XORWF         f, d, a         Exclusive OR WREG with f         1         0001         10da         fffff         Z, N           BIT-ORIENTED FILE REGISTER OPERATIONS           BCF         f, b, a         Bit Clear f         1         1001         bbba         ffff         None         1, 2           BSF         f, b, a         Bit Set f         1         1000         bbba         ffff         None         1, 2			·	1 (2 or 3)						1. 2
BIT-ORIENTED FILE REGISTER OPERATIONS           BCF         f, b, a         Bit Clear f         1         1001 bbba ffff ffff         None         1, 2           BSF         f, b, a         Bit Set f         1         1000 bbba ffff ffff         None         1, 2	XORWF				0001	10da	ffff	ffff	Z, N	,
BCF         f, b, a         Bit Clear f         1         1001 bbba ffff ffff         None         1, 2           BSF         f, b, a         Bit Set f         1         1000 bbba ffff ffff         None         1, 2	BIT-ORIEN			1					1 '	
BSF f, b, a Bit Set f 1 1000 bbba ffff ffff None 1,2	BCF			1	1001	bbba	ffff	ffff	None	1. 2
	BSF			1 -					1	
BTFSC f, b, a Bit Test f, Skip if Clear   1 (2 or 3)   1011 bbba fffff   None   3, 4	BTFSC			1 (2 or 3)						
	BTFSS									
	BTG			1. ` '	1					

Note 1: When a PORT register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

- 2: If this instruction is executed on the TMR0 register (and, where applicable, d = 1), the prescaler will be cleared if assigned.
- 3: If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

<sup>4:</sup> Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP, unless the first word of the instruction retrieves the information embedded in these 16-bits. This ensures that all program memory locations have a valid instruction.

<sup>5:</sup> If the Table Write starts the write cycle to internal memory, the write will continue until terminated.

TABLE 20-2: PIC18FXXX INSTRUCTION SET (CONTINUED)

Mnemonic,		Description	Cycles	16-	·Bit Instr	uction W	ord/	Status	Notes
Opera	nds	Description	Cycles	MSb	MSb LSb		Affected	Notes	
CONTROL	OPERA	TIONS							
BC	n	Branch if Carry	1 (2)	1110	0010	nnnn	nnnn	None	
BN	n	Branch if Negative	1 (2)	1110	0110	nnnn	nnnn	None	
BNC	n	Branch if Not Carry	1 (2)	1110	0011	nnnn	nnnn	None	
BNN	n	Branch if Not Negative	1 (2)	1110	0111	nnnn	nnnn	None	
BNOV	n	Branch if Not Overflow	1 (2)	1110	0101	nnnn	nnnn	None	
BNZ	n	Branch if Not Zero	2	1110	0001	nnnn	nnnn	None	
BOV	n	Branch if Overflow	1 (2)	1110	0100	nnnn	nnnn	None	
BRA	n	Branch Unconditionally	1 (2)	1101	0nnn	nnnn	nnnn	None	
BZ	n	Branch if Zero	1 (2)	1110	0000	nnnn	nnnn	None	
CALL	n, s	Call subroutine1st word	2	1110	110s	kkkk	kkkk	None	
		2nd word		1111	kkkk	kkkk	kkkk		
CLRWDT	_	Clear Watchdog Timer	1	0000	0000	0000	0100	TO, PD	
DAW	_	Decimal Adjust WREG	1	0000	0000	0000	0111	С	
GOTO	n	Go to address1st word	2	1110	1111	kkkk	kkkk	None	
		2nd word		1111	kkkk	kkkk	kkkk		
NOP	_	No Operation	1	0000	0000	0000	0000	None	
NOP		No Operation	1	1111	XXXX	xxxx	xxxx	None	4
POP	_	Pop top of return stack (TOS)	1	0000	0000	0000	0110	None	
PUSH	—	Push top of return stack (TOS)	1	0000	0000	0000	0101	None	
RCALL	n	Relative Call	2	1101	1nnn	nnnn	nnnn	None	
RESET		Software device RESET	1	0000	0000	1111	1111	All	
RETFIE	S	Return from interrupt enable	2	0000	0000	0001	000s	GIE/GIEH,	
								PEIE/GIEL	
RETLW	k	Return with literal in WREG	2	0000	1100	kkkk	kkkk	None	
RETURN	S	Return from Subroutine	2	0000	0000	0001	001s	None	
SLEEP	_	Go into Standby mode	1	0000	0000	0000	0011	TO, PD	

- Note 1: When a PORT register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.
  - 2: If this instruction is executed on the TMR0 register (and, where applicable, d = 1), the prescaler will be cleared if assigned.
  - 3: If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
  - **4:** Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP, unless the first word of the instruction retrieves the information embedded in these 16-bits. This ensures that all program memory locations have a valid instruction.
  - 5: If the Table Write starts the write cycle to internal memory, the write will continue until terminated.

TABLE 20-2: PIC18FXXX INSTRUCTION SET (CONTINUED)

Mnemonic,		Description	Cycles	16	-Bit Ins	truction '	Word	Status	Notes
Opera	ınds	Description	Cycles	MSb		LSb	Affected	Notes	
LITERAL (	PERAT	IONS							
ADDLW	k	Add literal and WREG	1	0000	1111	kkkk	kkkk	C, DC, Z, OV, N	
ANDLW	k	AND literal with WREG	1	0000	1011	kkkk	kkkk	Z, N	
IORLW	k	Inclusive OR literal with WREG	1	0000	1001	kkkk	kkkk	Z, N	
LFSR	f, k	Move literal (12-bit) 2nd word	2	1110	1110	OOff	kkkk	None	
		to FSRx 1st word		1111	0000	kkkk	kkkk		
MOVLB	k	Move literal to BSR<3:0>	1	0000	0001	0000	kkkk	None	
MOVLW	k	Move literal to WREG	1	0000	1110	kkkk	kkkk	None	
MULLW	k	Multiply literal with WREG	1	0000	1101	kkkk	kkkk	None	
RETLW	k	Return with literal in WREG	2	0000	1100	kkkk	kkkk	None	
SUBLW	k	Subtract WREG from literal	1	0000	1000	kkkk	kkkk	C, DC, Z, OV, N	
XORLW	k	Exclusive OR literal with WREG	1	0000	1010	kkkk	kkkk	Z, N	
DATA MEN	MORY ↔	PROGRAM MEMORY OPERATION	S						
TBLRD*		Table Read	2	0000	0000	0000	1000	None	
TBLRD*+		Table Read with post-increment		0000	0000	0000	1001	None	
TBLRD*-		Table Read with post-decrement		0000	0000	0000	1010	None	
TBLRD+*		Table Read with pre-increment		0000	0000	0000	1011	None	
TBLWT*		Table Write	2 (5)	0000	0000	0000	1100	None	
TBLWT*+		Table Write with post-increment		0000	0000	0000	1101	None	
TBLWT*-		Table Write with post-decrement		0000	0000	0000	1110	None	
TBLWT+*		Table Write with pre-increment		0000	0000	0000	1111	None	

- Note 1: When a PORT register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.
  - 2: If this instruction is executed on the TMR0 register (and, where applicable, d = 1), the prescaler will be cleared if assigned.
  - 3: If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
  - 4: Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP, unless the first word of the instruction retrieves the information embedded in these 16-bits. This ensures that all program memory locations have a valid instruction.
  - 5: If the Table Write starts the write cycle to internal memory, the write will continue until terminated.

#### 20.1 Instruction Set

ADD	LW	ADD literal to W					
Synt	ax:	[label] A	[label] ADDLW k				
Ope	rands:	$0 \le k \le 25$	5				
Ope	ration:	$(W) + k \rightarrow$	W				
Statu	us Affected:	N, OV, C,	DC, Z				
Encoding:		0000	1111	kkk	k kkkk		
Description:		8-bit litera	The contents of W are added to the 8-bit literal 'k' and the result is placed in W.				
Word	ds:	1	1				
Cycles:		1	1				
Q Cycle Activity:							
	Q1	Q2	Q3		Q4		
	Decode	Read literal 'k'	Proces Data		Write to W		

Example: ADDLW 0x15

Before Instruction W = 0x10 After Instruction W = 0x25

ADDWF	ADD W to	f			
Syntax:	[ label ] Al	[ label ] ADDWF f [,d [,a]			
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$				
Operation:	(W) + (f) -	→ dest			
Status Affected:	N, OV, C,	DC, Z			
Encoding:	0010	01da	ffff	ffff	
Description:	Add W to register 'f'. If 'd' is 0, the result is stored in W. If 'd' is 1, the result is stored back in register 'f' (default). If 'a' is 0, the Access Bank will be selected. If 'a' is 1, the BSR is used.				
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2	Q3	}	Q4	
Decode	Read register 'f'	Proce Data		Write to estination	

Example: ADDWF REG, 0, 0

Before Instruction

W = 0x17 REG = 0xC2

After Instruction

W = 0xD9 REG = 0xC2

ADDWFC	ADD W and Carry bit to f					
Syntax:	[ label ] AD	DWFC	f [,d [,a	a]		
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$					
Operation:	$(W) + (f) + (C) \rightarrow dest$					
Status Affected:	N,OV, C, DC, Z					
Encoding:	0010	00da	ffff	ffff		
Description:	Add W, the Carry Flag and data memory location 'f'. If 'd' is 0, the result is placed in W. If 'd' is 1, the result is placed in data memory location 'f'. If 'a' is 0, the Access Bank will be selected. If 'a' is 1, the BSR will not be overridden.					

Words:	1
Cycles:	1
Q Cycle Activity:	

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to
	register 'f'	Data	destination

Example: ADDWFC REG, 0, 1

Before Instruction

Carry bit = 1REG = 0x02W = 0x4D

After Instruction

Carry bit = 0 REG = 0x02 W = 0x50

ANDLW	AND literal with W				
Syntax:	[label] ANDLW				

Operands:  $0 \le k \le 255$ 

Operation: (W) .AND.  $k \rightarrow W$ 

Status Affected: N,Z

Encoding: 0000 1011 kkkk kkkk

Description: The contents of W are ANDed with the 8-bit literal 'k'. The result is

placed in W.

Words: 1
Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to W
	'k'	Data	

Example: ANDLW 0x5F

Before Instruction

W = 0xA3

After Instruction

W = 0x03

**ANDWF** AND W with f

Syntax: [label] ANDWF f [,d [,a]

Operands:  $0 \le f \le 255$  $d \in [0,1]$  $a \in [0,1]$ 

Operation: (W) .AND. (f)  $\rightarrow$  dest

Status Affected: N,Z

Encodina: 0001 01da ffff ffff

Description: The contents of W are AND'ed with register 'f'. If 'd' is 0, the result is

stored in W. If 'd' is 1, the result is stored back in register 'f' (default). If 'a' is 0, the Access Bank will be selected. If 'a' is 1, the BSR will not

be overridden (default).

Words: 1 Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to
	register 'f'	Data	destination

Example: ANDWF REG, 0, 0

Before Instruction

W 0x17 REG 0xC2

After Instruction

0x02 REG 0xC2 BC **Branch if Carry** 

Syntax: [label] BC n Operands: -128 ≤ n ≤ 127 Operation: if carry bit is '1'

 $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0010 nnnn nnnn

If the Carry bit is '1', then the Description:

program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC+2+2n. This instruction is then

a two-cycle instruction.

1 Words:

Cycles: 1(2)

Q Cycle Activity:

If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	'n'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE BC 5

Before Instruction

PC address (HERE)

After Instruction

If Carry PC

address (HERE+12)

If Carry PC address (HERE+2)

BCF	Bit Clear	f		
Syntax:	[label] E	BCF f,	b[,a]	
Operands:	$0 \le f \le 25$ $0 \le b \le 7$ $a \in [0,1]$	5		
Operation:	$0 \rightarrow f < b >$			
Status Affected:	None			
Encoding:	1001	bbba	ffff	ffff
Description:	Bit 'b' in r is 0, the A selected, If 'a' = 1, selected (default).	Access E overridir then the	Bank will b ng the BS bank will	oe R value. be
Words:	1			
Cycles:	1			
Q Cycle Activity:				

Example: FLAG\_REG,

Q2

Read

register 'f'

Q3

Process

Data

Q4 Write

register 'f'

Before Instruction  $FLAG_REG = 0xC7$ After Instruction  $FLAG_REG = 0x47$ 

Q1

Decode

BN	Branch is	i Negativ	ve	
Syntax:	[label] E	3N n		
Operands:	-128 ≤ n s	≤ 127		
Operation:	if negative (PC) + 2			
Status Affected:	None			
Encoding:	1110	0110	nnnn	nnnn
Description:	If the Neg program v The 2's co added to have incre instruction PC+2+2n a two-cyc	will brand omplemented the PC. emented n, the ne This in	ch. ent numb Since th to fetch w addres	per '2n' is e PC will the next ss will be
Words:	1			
Cycles:	1(2)			
Q Cycle Activity: If Jump:				
Q1	Q2	Q3	}	Q4
Docado	Dood literal	Drago	00 14/	ito to DC

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	'n'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE BN Jump Before Instruction

PC address (HERE)

After Instruction

If Negative PC If Negative PC 1; address (Jump) 0; address (HERE+2) **BNC Branch if Not Carry** 

Syntax: [label] BNC n Operands:  $-128 \le n \le 127$ 

Operation: if carry bit is '0'  $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0011 nnnn

If the Carry bit is '0', then the Description:

program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC+2+2n. This instruction is then

nnnn

a two-cycle instruction.

Words: 1

Cycles: 1(2)

Q Cycle Activity:

If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	'n'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE BNC Jump

Before Instruction

PC address (HERE)

After Instruction

If Carry

PC address (Jump) If Carry PC

address (HERE+2)

**BNN Branch if Not Negative** 

Syntax: [label] BNN n Operands: -128 ≤ n ≤ 127 Operation: if negative bit is '0'  $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0111 nnnn nnnn

If the Negative bit is '0', then the Description:

program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC+2+2n. This instruction is then

a two-cycle instruction.

Words: 1

Cycles: 1(2)

Q Cycle Activity:

If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	'n'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE BNN Jump

Before Instruction

PC address (HERE)

After Instruction

If Negative PC

address (Jump)

If Negative PC address (HERE+2)

BNOV	Branch if Not Overflow
Syntax:	[label] BNOV n
Operands:	-128 ≤ n ≤ 127
Operation:	if overflow bit is '0' $(PC) + 2 + 2n \rightarrow PC$
Status Affected:	None
Encoding:	1110 0101 nnnn nnnn
Description:	If the Overflow bit is '0', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the post.

have incremented to fetch the next instruction, the new address will be PC+2+2n. This instruction is then

a two-cycle instruction.

Words: 1 Cycles: 1(2)

Q Cycle Activity: If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	'n'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE BNOV Jump

Before Instruction

PC address (HERE)

After Instruction

If Overflow

PC address (Jump) If Overflow PC address (HERE+2) **BNZ Branch if Not Zero** 

[label] BNZ n Syntax: Operands:  $-128 \le n \le 127$ Operation: if zero bit is '0'

 $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0001 nnnn nnnn

If the Zero bit is '0', then the pro-Description: gram will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC+2+2n. This instruction is then

a two-cycle instruction.

1 Words: Cycles: 1(2)

Q Cycle Activity:

If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	'n'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE BNZJump

Before Instruction

PC address (HERE)

After Instruction

If Zero PC

address (Jump)

If Zero PC address (HERE+2)

**BRA Unconditional Branch** 

Syntax: [label] BRA n Operands:  $-1024 \le n \le 1023$ 

Operation:  $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1101 0nnn nnnn nnnn

Description: Add the 2's complement number '2n' to the PC. Since the PC will

have incremented to fetch the next instruction, the new address will be PC+2+2n. This instruction is a

two-cycle instruction.

Words:

Cycles:

Q Cycle Activity: Q1 Q2 Q3 Q4 Read literal Process Write to PC Decode Data 'n'

No No No No operation operation operation operation

Example: HERE Jump

2

Before Instruction

PC address (HERE)

After Instruction

PC address (Jump) **BSF** Bit Set f

Syntax: [label] BSF f,b[,a]

Operands:  $0 \le f \le 255$ 

> $0 \le b \le 7$  $a \in [0,1]$

> > 1000

 $1 \rightarrow f < b >$ Operation:

Status Affected: None

Encodina:

ffff Description: Bit 'b' in register 'f' is set. If 'a' is 0

Access Bank will be selected, over-

bbba

riding the BSR value. If 'a' = 1, then the bank will be selected as per the

ffff

BSR value.

Words: 1 Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write
	register 'f'	Data	register 'f'

Example: BSF FLAG REG, 7, 1

Before Instruction

FLAG\_REG 0x0A

After Instruction

FLAG\_REG 0x8A

BTF	sc	Bit Test Fi	le, Skip if Cle	ear	BTF	SS	Bit Test Fi	le, Skip if Se	t
Synta	ax:	[label] B1	FSC f,b[,a]		Synt	ax:	[ label ] BT	FSS f,b[,a]	
Oper	ands:	$0 \le f \le 255$ $0 \le b \le 7$ $a \in [0,1]$			Ope	rands:	$0 \le f \le 255$ $0 \le b \le 7$ $a \in [0,1]$		
Oper	ation:	skip if (f <b:< td=""><td>») = 0</td><td></td><td>Ope</td><td>ration:</td><td>skip if (f<b></b></td><td>&gt;) = 1</td><td></td></b:<>	») = 0		Ope	ration:	skip if (f <b></b>	>) = 1	
Statu	s Affected:	None			Statu	us Affected:	None		
Enco	oding:	1011	bbba ff	ff ffff	Enco	oding:	1010	bbba ffi	ff ffff
Desc	eription:	next instruction in the second of the second	egister 'f' is 0 ction is skippe the the nexing the currer s discarded, a nstead, makin action. If 'a' is nk will be sele SSR value. If ' ill be selected (default).	ed.  At instruction  and a NOP is  ag this a two-  0, the  ected, over-  a' = 1, then	Desc	cription:	next instruction life bit 'b' is 1 fetched duration executt NOP is execute a two-cycle Access Barriding the E	egister 'f' is 1, then the new ting the currer ion, is discard cuted instead a instruction. Ink will be selected (default).	ed. At instruction at instruc- aded and a at making this at a is 0, the acted, over- a' = 1, then
Word	ds:	1	,		Word	ds:	1	,	
Cycle	9S:		ycles if skip a a 2-word inst		Cycl	es:		cycles if skip a a 2-word inst	
QC	ycle Activity:				QC	ycle Activity:			
	Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
	Decode	Read register 'f'	Process Data	No operation		Decode	Read register 'f'	Process Data	No operation
lf sk	ip:				If sk	dp:			
,	Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
	No operation	No operation	No operation	No operation		No operation	No operation	No operation	No operation
lf sk	ip and follow	ed by 2-word	instruction:		lf sk	ip and follow	ed by 2-word	instruction:	
ı	Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
	No operation	No operation	No operation	No operation		No operation	No operation	No operation	No operation
	No operation	No operation	No operation	No operation		No operation	No operation	No operation	No operation
Exan	nple:	HERE B' FALSE : TRUE :	FSC FLAG	, 1, 0	<u>Exar</u>	nple:	HERE BT	rfss flag	, 1, 0
	Before Instru PC After Instructi If FLAG< PC If FLAG<	ction = add ion 1> = 0; = add 1> = 1;	ress (HERE) ress (TRUE) ress (FALSE)			Before Instru PC After Instruct If FLAG< PC If FLAG< PC	iction = add ion 1> = 0; = add 1> = 1;	ress (HERE)	

BTG Bit Toggle f

Syntax: [ label ] BTG f,b[,a]

Operands:  $0 \le f \le 255$   $0 \le b \le 7$  $a \in [0,1]$ 

 $a \in [0,1]$  $(f < b >) \rightarrow f < b >$ 

Status Affected: None

Operation:

Encoding: 0111 bbba ffff ffff

Description: Bit 'b' in data memory location 'f' is

inverted. If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value

(default).

Words: 1
Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write
	register 'f'	Data	register 'f'

Example: BTG PORTC, 4, 0

Before Instruction:

PORTC = 0111 0101 [0x75]

After Instruction:

PORTC = 0110 0101 [0x65]

BOV Branch if Overflow

Syntax: [label] BOV n Operands:  $-128 \le n \le 127$ Operation: if overflow bit is '1'

 $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0100 nnnn nnnn

Description: If the Overflow bit is '1', then the

program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC+2+2n. This instruction is then

a two-cycle instruction.

Words: 1

Cycles: 1(2)

Q Cycle Activity:

If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	'n'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE BOV Jump

Before Instruction

PC = address (HERE)

After Instruction

If Overflow = 1;

PC = address (Jump)

If Overflow = 0; PC = address (HERE+2) BZ Branch if Zero

Syntax: [ label ] BZ n Operands:  $-128 \le n \le 127$ Operation: if Zero bit is '1'

 $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0000 nnnn nnnn

Description: If the Zero bit is '1', then the pro-

gram will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC+2+2n. This instruction is then

a two-cycle instruction.

Words: 1 Cycles: 1(2)

Q Cycle Activity: If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	'n'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE BZ Jump

Before Instruction

PC = address (HERE)

After Instruction

If Zero = 1

 $\begin{array}{ccccc} PC & = & address & (\texttt{Jump}) \\ \text{If Zero} & = & 0; \\ PC & = & address & (\texttt{HERE+2}) \end{array}$ 

CALL Subroutine Call

Syntax: [label] CALL k [,s]

Operands:  $0 \le k \le 1048575$ 

 $s \in [0,1]$ 

Operation: (PC) + 4  $\rightarrow$  TOS,

 $k \rightarrow PC<20:1>$ , if s = 1 (W)  $\rightarrow$  WS,

 $(STATUS) \rightarrow STATUSS$ ,

 $(\mathsf{BSR}) \to \mathsf{BSRS}$ 

Status Affected: None

Encoding:

1st word (k<7:0>) 2nd word(k<19:8>)

1110		k <sub>7</sub> kkk	kkkk <sub>o</sub>
1111	k <sub>19</sub> kkk	kkkk	kkkk <sub>8</sub>

Description: Subroutine call of entire 2 Mbyte

memory range. First, return address (PC+ 4) is pushed onto the return stack. If 's' = 1, the W, STATUS and BSR registers are also pushed into their respective shadow registers, WS, STATUSS and BSRS. If 's' = 0, no update occurs (default). Then, the 20-bit value 'k' is loaded into PC<20:1>. CALL is a two-cycle instruction.

Words: 2 Cycles: 2

Q Cycle Activity:

	Q1	Q2	Q3	Q4
	Decode	Read literal	Push PC to	Read literal
		'k'<7:0>,	stack	'k'<19:8>,
				Write to PC
	No	No	No	No
Į	operation	operation	operation	operation

Example: HERE CALL THERE, 1

Before Instruction

PC = address (HERE)

After Instruction

PC = address (THERE) TOS = address (HERE + 4)

WS = W BSRS = BSR STATUSS= STATUS **CLRF** Clear f Syntax: [label] CLRF f[,a]  $0 \le f \le 255$ Operands:  $a \in [0,1]$  $000h \rightarrow f$ Operation:  $1 \to Z$ Status Affected: Ζ Encoding: 0110 ffff ffff 101a Description: Clears the contents of the specified register. If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default). Words: 1 Cycles: 1 Q Cycle Activity: Q1 Q2 Q3 Q4

Example: CLRF FLAG\_REG, 1

Read register 'f'

Before Instruction

Decode

 $FLAG_REG = 0x5A$ 

After Instruction

 $FLAG_REG = 0x00$ 

CLRWDT	Clear Wa	tchdog	Timer	
Syntax:	[ label ]	CLRWD	T	
Operands:	None			
Operation:	$000h \rightarrow 000h \rightarrow $	,	stscaler,	
Status Affected:	$\overline{TO}$ , $\overline{PD}$			
Encoding:	0000	0000	0000	0100
Description:	Watchdo	g Timer. er of the	on resets It also res WDT. Sta	sets the
Words:	1			
Cycles:	1			
Q Cycle Activity:				
Q1	Q2	Q	3	Q4

Process

Data

Nο

operation

Example: CLRWDT

Before Instruction

WDT Counter =

th - - t - - t - - - t - - -

After Instruction WDT Counter

Decode

Write

register 'f'

Process

Data

 $\begin{array}{llll} \text{WDT Counter} & = & 0x00 \\ \underline{\text{WDT Postscaler}} & = & 0 \\ \underline{\text{TO}} & = & 1 \\ \hline{\text{PD}} & = & 1 \end{array}$ 

No

operation

COMF	Complem	nent f		
Syntax:	[label]	COMF	f [,d [,a]	
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	5		
Operation:	$(\overline{f}) \rightarrow de$	est		
Status Affected:	N, Z			
Encoding:	0001	11da	ffff	ffff
	stored in \		,	
	'a' is 0, the selected, If 'a' = 1, 1 selected a (default).	e Acces overridir then the	s Bank w ng the BS bank wil	R value. I be
Words:	'a' is 0, the selected, If 'a' = 1, 1 selected a	e Acces overridir then the	s Bank w ng the BS bank wil	vill be SR value. I be
Words: Cycles:	'a' is 0, the selected, If 'a' = 1, the selected at (default).	e Acces overridir then the	s Bank w ng the BS bank wil	vill be SR value. I be
	'a' is 0, th selected, If 'a' = 1, 1 selected a (default).	e Acces overridir then the	s Bank w ng the BS bank wil	vill be SR value. I be
Cycles:	'a' is 0, th selected, If 'a' = 1, 1 selected a (default).	e Acces overridir then the	s Bank w ng the BS bank wil e BSR v	vill be SR value. I be
Cycles:  Q Cycle Activity	'a' is 0, the selected, If 'a' = 1, 1 selected a (default).	e Acces overridir then the as per th	s Bank wang the BS bank will be BSR versions	vill be SR value. I be alue

CPFSEQ	Compar	e f with \	N, skip if	f = W
Syntax:	[ label ]	CPFSEC	) f [,a]	
Operands:	$0 \le f \le 25$ $a \in [0,1]$	55		
Operation:	(f) - (W), skip if (f) (unsigne		rison)	
Status Affected:	None			
Encoding:	0110	001a	ffff	ffff
Description:	Compares the contents of data memory location 'f' to the contents of W by performing an unsigned subtraction. If 'f' = W, then the fetched instruction is discarded and a NOP is executed instead, making this a two-cycle instruction. If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).			
Words:	1			
Cycles:		-	skip and rd instruc	

Betore Insti	ructio	n		
REG	=	0x13		
After Instruction				
REG	=	0x13		
W	=	0xEC		

Q1	Q2	Q3	Q4
Decode	Read	Process	No
	register 'f'	Data	operation

If skip:

Q Cycle Activity:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation

If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation
No	No	No	No
operation	operation	operation	operation

Example:	HERE NEQUAL EQUAL		SEQ REG,	0
Before Instruc	tion			
PC Addres	s =	HERE		
W	=	?		
REG	=	?		
After Instruction	n			
If REG	=	W;		

PC = Address (NEQUAL)

000a

ffff

by a 2-word instruction.

ffff

**CPFSGT CPFSLT** Compare f with W, skip if f > W Compare f with W, skip if f < W Syntax: Syntax: [label] CPFSLT f[,a] [label] CPFSGT f[,a] Operands:  $0 \le f \le 255$ Operands:  $0 \le f \le 255$  $a \in [0,1]$  $a \in [0,1]$ (f) - (W),Operation: (f) - (W),Operation: skip if (f) > (W)skip if (f) < (W)(unsigned comparison) (unsigned comparison) Status Affected: None Status Affected: None Encoding: ffff 0110 010a ffff Encoding: 0110 Description: Compares the contents of data Description: Compares the contents of data memory location 'f' to the contents memory location 'f' to the contents of the W by performing an of W by performing an unsigned unsigned subtraction. subtraction. If the contents of 'f' are greater than If the contents of 'f' are less than the contents of WREG, then the the contents of W, then the fetched fetched instruction is discarded and instruction is discarded and a NOP a NOP is executed instead, making is executed instead, making this a two-cycle instruction. If 'a' is 0, the this a two-cycle instruction. If 'a' is 0, the Access Bank will be Access Bank will be selected. If 'a' selected, overriding the BSR value. is 1, the BSR will not be overridden If 'a' = 1, then the bank will be (default). selected as per the BSR value Words: 1 (default). Cycles: 1(2) Words: 1 Note: 3 cycles if skip and followed Cycles: 1(2)Note: 3 cycles if skip and followed Q Cycle Activity: by a 2-word instruction. Q Cycle Activity:

	,	•		
	Q1	Q2	Q3	Q4
	Decode	Read	Process	No
		register 'f'	Data	operation
If sk	dp:			

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation

#### If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation
No	No	No	No
operation	operation	operation	operation

Example:	HERE	CPFSLT	REG,	1
	NLESS	:		
	LESS	:		

Before Instruction

Address (HERE)

After Instruction

If REG W٠

Address (LESS) PC =

If REG ≥ W;

PC Address (NLESS)

Q1	Q2	Q3	Q4
Decode	Read	Process	No
	register 'f'	Data	operation

#### If skip:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation

#### If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4	
No No		No	No	
operation	operation	operation	operation	
No No		No	No	
operation	operation	operation	operation	

Example: HERE CPFSGT REG, 0

NGREATER GREATER

Before Instruction

PC Address (HERE)

W

After Instruction

If REG W:

> PC Address (GREATER)

If REG ≤

> PC Address (NGREATER)

DAW	D	Decimal Adjust W Register				
Syntax:	[	label] [	DAW			
Operands:	N	lone				
Operation:	(\ e	N<3:0>) Ise	0.79 or [DC $0.79$ + 6 $0.79$ W<3:0>	3:0>;		
	(\ e	W<7:4>) Ise	· >9] or [C = + 6 → W<7 → W<7:4>	7:4>;		
Status Affected:	Ċ	;		•		
Encoding:		0000	0000 0	000 0111		
Description:	tio p	DAW adjusts the eight-bit value in W, resulting from the earlier addition of two variables (each in packed BCD format) and produces a correct packed BCD result.				
Words:	1					
Cycles:	1					
Q Cycle Activity:	:					
Q1		Q2	Q3	Q4		
Decode		Read gister W	Process Data	Write W		
Example1:	D.	AW				
Before Instru	ıctio	n				
W C DC	= = =	0xA5 0 0				
After Instruc	tion					
W C DC Example 2:	= = =	0x05 1 0				
Before Instru	ıctio	n				
<del></del>	uctio = = = =	on 0xCE 0 0				
Before Instru W C	= =	0xCE 0				

DECF	Decremen	nt f				
Syntax:	[label] [	DECF f	[,d [,a]			
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$					
Operation:	$(f) - 1 \rightarrow c$	lest				
Status Affected:	C, DC, N,	OV, Z				
Encoding:	0000	01da	ffff	ffff		
Description:	Decrement register 'f'. If 'd' is 0, the result is stored in W. If 'd' is 1, the result is stored back in register 'f' (default). If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).					
Words:	1					
Cycles:	1	1				
Q Cycle Activity:						
Q1	Q2	Q3		Q4		
Decode	Read register 'f'	Proces Data		Write to stination		

DECF	SZ	Decremen	nt f, skip if (	)	DCI	SNZ	Decreme	nt f, skip if n	ot 0
Syntax: [ label		[label] [	DECFSZ f[	,d [,a]]	Syn	tax:	[label] [	OCFSNZ f[	,d [,a]
Opera	.nds:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	5		Оре	erands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	5	
Opera	tion:	(f) $-1 \rightarrow 0$ skip if resu			Оре	eration:	(f) $-1 \rightarrow 0$ skip if resu		
Status	Affected:	None			Stat	us Affected:	None		
Encod	ling:	0010	11da ff	ff ffff	Enc	oding:	0100	11da fff	f ffff
Description:  The contents of register 'f' are decremented. If 'd' is 0, the result is placed in W. If 'd' is 1, the result is placed back in register 'f' (default). If the result is 0, the next instruction, which is already fetched, is discarded, and a NOP is executed instead, making it a two-cycle instruction. If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).		Des	cription:	remented. placed ba placed ba If the resu instruction fetched, is executed i cycle instr Access Ba overriding then the b	nts of register If 'd' is 0, the W. If 'd' is 1, ck in register It is not 0, the part of the character of the second of the character of the second of the s	e result is the result is 'f' (default). e next ready and a NOP is ing it a two- s 0, the elected, ue. If 'a' = 1, elected as			
Words	s:	1			Wor	ds:	1		
Cycles	5:		ycles if skip a 2-word ins	and followed truction.	Сус	les:	<ul><li>1(2)</li><li>Note: 3 cycles if skip and followed by a 2-word instruction.</li></ul>		
Q Cy	cle Activity	:			Q	Cycle Activity	:		
	Q1	Q2	Q3	Q4	-	Q1	Q2	Q3	Q4
	Decode	Read register 'f'	Process Data	Write to destination		Decode	Read register 'f'	Process Data	Write to destination
If skip	D:	, regions i			if s	kip:	i regioner		
	Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
	No	No	No	No		No	No	No	No
	operation	operation	operation	operation		operation	operation	operation	operation
If skip		ved by 2-word			If s	kip and follov	-		
Г	Q1	Q2	Q3	Q4	]	Q1	Q2	Q3	Q4
	No operation	No operation	No operation	No operation		No operation	No operation	No operation	No operation
	No operation	No operation	No operation	No operation		No operation	No operation	No operation	No operation
<u>Exam</u>	ole:	HERE CONTINUE	DECFSZ GOTO	CNT, 1, 1 LOOP	<u>Exa</u>	mple:	ZERO	OCFSNZ TEM :	IP, 1, 0
В	efore Instru PC		(HERE)			Before Instru	uction =	?	
A	fter Instruc CNT If CNT PC If CNT PC	= CNT - 1 = 0; = Address ≠ 0;	CONTINUE (HERE+2)	3)		After Instruc TEMP If TEMP PC If TEMP PC	tion = = = = # =	TEMP - 1, 0; Address (2 0; Address (1	

GOTO Unconditional Branch

Syntax: [label] GOTO k

Operands:  $0 \le k \le 1048575$ Operation:  $k \to PC < 20:1 >$ 

Status Affected: None

Encoding: 1st word (k<7:0>) 1110 2nd word(k<19:8>) 1111

1110 1111 k<sub>7</sub>kkk kkkk<sub>0</sub> ) 1111 k<sub>19</sub>kkk kkkk kkkk<sub>8</sub>

Description: GOTO allows an unconditional

branch anywhere within entire 2 Mbyte memory range. The 20-bit value 'k' is loaded into PC<20:1>. GOTO is always a two-cycle

instruction.

Words: 2 Cycles: 2

Q Cycle Activity:

	Q1	Q2	Q3	Q4
	Decode	Read literal	No	Read literal
		'k'<7:0>,	operation	'k'<19:8>,
				Write to PC
	No	No	No	No
l	operation	operation	operation	operation

Example: GOTO THERE

After Instruction

PC = Address (THERE)

nt f
nt

Syntax: [ label ] INCF f [,d [,a]

 $\begin{array}{ll} \text{Operands:} & 0 \leq f \leq 255 \\ & d \in [0,1] \\ & a \in [0,1] \end{array}$ 

Operation: (f) + 1  $\rightarrow$  dest Status Affected: C, DC, N, OV, Z

Encoding: 0010 10da fffff ffff

Description: The contents of register 'f' are

incremented. If 'd' is 0, the result is placed in W. If 'd' is 1, the result is placed back in register 'f' (default). If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value

(default).

Words: 1
Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Decode Read		Write to
	register 'f'	Data	destination

Example: INCF CNT, 1, 0

Before Instruction

CNT = 0xFF Z = 0 C = ? DC = ?

After Instruction

CNT = 0x00 Z = 1 C = 1 DC = 1

INCF	SZ	Incremen	t f, skip if 0		INF	SNZ	Incremen	t f, skip if n	ot 0
Synta	ax:	[label]	NCFSZ f[	,d [,a]	Syn	tax:	[ label ]	INFSNZ f	[,d [,a]
Oper	ands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	i		Ope	erands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	5	
Oper	ation:	(f) + 1 $\rightarrow$ c skip if resu			Ope	ration:	(f) + 1 $\rightarrow$ 0 skip if resu		
Statu	s Affected:	None			State	us Affected:	None		
Enco	ding:	0011	11da ff	ff ffff	Enc	oding:	0100	10da ff	ff ffff
Encoding:    0011   11da   ffff   ffff     The contents of register 'f' are incremented. If 'd' is 0, the result is placed in W. If 'd' is 1, the result is placed back in register 'f'. (default) If the result is 0, the next instruction, which is already fetched, is discarded, and a NOP is executed instead, making it a two-cycle instruction. If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).		Des	cription:	increment placed in placed bath for the result instruction fetched, is executed cycle instruction. Access Bath inding the bank with placed in the placed in	W. If 'd' is 1, ck in registe It is not 0, th, which is al discarded, instead, mal uction. If 'a' ank will be s	, the result is the result is r 'f' (default). he next ready and a NOP is king it a two-			
Word	ds:	1			Wor	ds:	1		
Cycle	es:	1(2)  Note: 3 cycles if skip and followed by a 2-word instruction.		Cycl	les:		cycles if skip a 2-word ins	and followed struction.	
QC	ycle Activity:				QC	Cycle Activity	<b>/</b> :		
-	Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
	Decode	Read register 'f'	Process Data	Write to destination		Decode	Read register 'f'	Process Data	Write to destination
If sk	ip:				if sl	kip:	1 0		
	Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
	No	No	No	No		No	No	No	No
[	operation	operation	operation	operation		operation	operation	operation	operation
If sk	•	red by 2-word			lt si	-	wed by 2-wor		
Г	Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
	No operation	No operation	No operation	No operation		No operation	No operation	No operation	No operation
	No operation	No operation	No operation	No operation		No operation	No operation	No operation	No operation
Example: HERE INCFSZ CNT, 1, 0 NZERO : ZERO :		<u>Exa</u>	mple:	HERE ZERO NZERO	INFSNZ RE	G, 1, 0			
	Before Instru PC After Instruct CNT If CNT PC If CNT PC	= Address tion = CNT + 1 = 0; = Address ≠ 0;	G (ZERO)			Before Instruction REG If REG PC If REG PC	= Address ction = REG + ≠ 0; = Address = 0;	S (HERE)  1 S (NZERO) S (ZERO)	

IOR	LW	Inclusive	Inclusive OR literal with W				
Syn	tax:	[ label ]	IORLW	k			
Ope	rands:	$0 \le k \le 25$	55				
Ope	ration:	(W) .OR.	$k\toW$				
Stati	us Affected:	N, Z					
Encoding:		0000	1001	kkk	k kkkk		
Des	cription:		bit literal		OR'ed with he result is		
Wor	ds:	1					
Cycles:		1					
Q Cycle Activity:							
	Q1	Q2	Q3		Q4		
	Decode	Read	Proces	ss	Write to W		

Example: IORLW 0x35

literal 'k'

Data

Before Instruction

W = 0x9A

After Instruction

W = 0xBF

IORWF Inclusive OR W with f							
Synt	ax:	[ label ]	[ label ] IORWF f [,d [,a]				
Ope	rands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	5				
Ope	ration:	(W) .OR. (	$(f) \rightarrow des$	t			
Statu	us Affected:	N, Z					
Enco	oding:	0001	00da	ffff	ffff		
Description:		Inclusive OR W with register 'f'. If 'd' is 0, the result is placed in W. If 'd' is 1, the result is placed back in register 'f' (default). If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).					
Word	ds:	1	1				
Cycl	es:	1	1				
Q Cycle Activity:							
	Q1	Q2	Q3		Q4		
	Decode	Read register 'f'	Proces Data		rite to stination		

Example: IORWF RESULT, 0, 1

Before Instruction

RESULT = 0x13

W = 0x91

After Instruction

RESULT = 0x13 W = 0x93

DS39564B-page 234

LFSR Load FSR

Syntax: [ label ] LFSR f,k

Operands:  $0 \le f \le 2$ 

 $0 \le k \le 4095$ 

Status Affected: None

Encoding: 1110 1110 00ff  $k_{11}kkk$ 1111 0000  $k_{7}kkk$  kkkk

Description: The 12-bit literal 'k' is loaded into

the file select register pointed to

by 'f'.

Words: 2 Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k' MSB	Process Data	Write literal 'k' MSB to FSRfH
Decode	Read literal 'k' LSB	Process Data	Write literal 'k' to FSRfL

Example: LFSR 2, 0x3AB

After Instruction

FSR2H = 0x03FSR2L = 0xAB MOVF Move f

Syntax: [ label ] MOVF f [,d [,a]

Operands:  $0 \le f \le 255$ 

 $d \in [0,1]$  $a \in [0,1]$ 

Operation:  $f \rightarrow dest$ 

Status Affected: N, Z

Encoding: 0101 00da fffff ffff

Description: The contents of register 'f' are

moved to a destination dependent upon the status of 'd'. If 'd' is 0, the result is placed in W. If 'd' is 1, the result is placed back in register 'f' (default). Location 'f' can be anywhere in the 256 byte bank. If 'a' is

0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value

(default).

Words: 1 Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4	
Decode	Read	Process	Write W	
	reaister 'f'	Data		

Example: MOVF REG, 0, 0

Before Instruction

 $\begin{array}{rcl}
\mathsf{REG} & = & \mathsf{0x22} \\
\mathsf{W} & = & \mathsf{0xFF}
\end{array}$ 

After Instruction

REG = 0x22 W = 0x22

MOVFF Move f to f

Syntax: [label] MOVFF f<sub>s</sub>,f<sub>d</sub>

Operands:  $0 \le f_s \le 4095$ 

 $0 \le f_d \le 4095$ 

Operation:  $(f_s) \rightarrow f_d$ 

Status Affected: None

Encoding: 1st word (source) 2nd word (destin.)

|--|

Description:

The contents of source register ' $f_s$ ' are moved to destination register ' $f_d$ '. Location of source ' $f_s$ ' can be anywhere in the 4096 byte data space (000h to FFFh), and location of destination ' $f_d$ ' can also be anywhere from 000h to FFFh.

Either source or destination can be W (a useful special situation).

MOVFF is particularly useful for transferring a data memory location to a peripheral register (such as the transmit buffer or an I/O port).

The MOVFF instruction cannot use the PCL, TOSU, TOSH or TOSL as the destination register.

Note: The MOVFF instruction

should not be used to modify interrupt settings while any interrupt is enabled.
See Section 8.0 for more

information.

Words: 2 Cycles: 2 (3)

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f' (src)	Process Data	No operation
Decode	No operation No dummy read	No operation	Write register 'f' (dest)

Example: MOVFF REG1, REG2

Before Instruction

 $REG1 = 0x33 \\
 REG2 = 0x11$ 

After Instruction

 $REG1 = 0x33, \\
 REG2 = 0x33$ 

MOVLB Move literal to low nibble in BSR

Syntax: [label] MOVLB k

Status Affected: None

Encoding: 0000 0001 kkkk kkkk

Description: The 8-bit literal 'k' is loaded into the Bank Select Register (BSR).

Words: 1

Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal	Process Data	Write literal 'k' to BSB
			BSR

Example: MOVLB 5

Before Instruction

BSR register = 0x02

After Instruction

BSR register = 0x05

MOVLW Move literal to W

Syntax: [label] MOVLW k

Status Affected: None
Encoding: 0000

Description: The eight-bit literal 'k' is loaded

1110

kkkk

kkkk

into W.

Words: 1 Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to W

Example: MOVLW 0x5A

After Instruction

W = 0x5A

MOVWF Move W to f

Syntax: [ label ] MOVWF f [,a]

Operands:  $0 \le f \le 255$ 

 $a \in [0,1]$  Operation:  $(W) \to f$ 

Status Affected: None

Encoding: 0110 111a ffff ffff

Description: Move data from W to register 'f'.

Location 'f' can be anywhere in the 256 byte bank. If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then

riding the BSR value. If 'a' = 1, then the bank will be selected as per the

BSR value (default).

Words: 1

Cycles: Q Cycle Activity:

 Q1
 Q2
 Q3
 Q4

 Decode
 Read register 'f'
 Process Data
 Write register 'f'

Example: MOVWF REG, 0

1

Before Instruction

W = 0x4F REG = 0xFF

After Instruction

W = 0x4F REG = 0x4F

MULLW	Multiply	Literal v	vith W	
Syntax:	[ label ]	MULLW	' k	
Operands:	$0 \le k \le 25$	55		
Operation:	(W) x k –	→ PRODI	H:PRODL	_
Status Affected:	None			
Encoding:	0000	1101	kkkk	kkkk
Description:	An unsigned multiplication is carried out between the contents of W and the 8-bit literal 'k'. The 16-bit result is placed in PRODH:PRODL register pair. PRODH contains the high byte. W is unchanged. None of the status flags are affected. Note that neither overflow nor carry is possible in this operation. A zero result is possible but not detected.			
Words:	1			
Cycles:	1			
Q Cycle Activity:				
Q1	Q2	Q3	}	Q4

Q1	Q2	Q3	Q4
Decode	Read	Process	Write
	literal 'k'	Data	registers
			PRODH:
			PRODL

Example: MULLW 0xC4

Before Instruction

 $\begin{array}{lll} W & = & 0xE2 \\ PRODH & = & ? \\ PRODL & = & ? \end{array}$ 

After Instruction

W = 0xE2PRODH = 0xAD PRODL = 0x08

MULWF	Multiply W with f
Syntax:	[ label ] MULWF f [,a]
Operands:	$0 \le f \le 255$ a $\in [0,1]$
Operation:	(W) $x (f) \rightarrow PRODH:PRODL$
Status Affected:	None
Encoding:	0000 00la ffff ffff
Description:	An unsigned multiplication is carried out between the contents of W and the register file location 'f'. The 16-bit result is stored in the PRODH:PRODL register pair. PRODH contains the high byte. Both W and 'f' are unchanged. None of the status flags are affected.  Note that neither overflow nor carry is possible in this operation. A zero result is possible but not detected. If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).
Words:	1
Cycles:	1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write registers PRODH: PRODL

Example: MULWF REG, 1

Before Instruction

W = 0xC4 REG = 0xB5 PRODH = ? PRODL = ?

After Instruction

W = 0xC4 REG = 0xB5 PRODH = 0x8A PRODL = 0x94 **NEGF** Negate f Syntax: [label] NEGF f [,a]  $0 \le f \le 255$ Operands:  $a \in [0,1]$  $(\overline{f}) + 1 \rightarrow f$ Operation: Status Affected: N, OV, C, DC, Z Encoding: 0110 110a ffff ffff Description: Location 'f' is negated using two's complement. The result is placed in the data memory location 'f'. If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value. Words: Cycles: 1 Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write
	register 'f'	Data	register 'f'

Example: NEGF REG, 1

Before Instruction

REG = 0011 1010 [0x3A]

After Instruction

REG = 1100 0110 [0xC6]

NOF	•	No Operation				
Synt	ax:	[ label ]	NOP			
Ope	rands:	None				
Ope	ration:	No opera	ation			
Status Affected:		None				
Encoding:		0000	0000	000	00	0000
		1111	xxxx	XXX	кх	xxxx
Description:		No operation.				
Words:		1	1			
Cycles:		1				
Q Cycle Activity:						
	Q1	Q2	Q3	}		Q4
	Decode	No	No			No

operation

operation

operation

Example:

None.

POP Pop Top of Return Stack Syntax: [label] POP Operands: None Operation: (TOS) → bit bucket Status Affected: None Encoding: 0000 0000 0000 0110 Description: The TOS value is pulled off the

return stack and is discarded. The TOS value then becomes the previous value that was pushed onto the return stack.

This instruction is provided to enable the user to properly manage the return stack to incorporate a

software stack.

Words: Cycles:

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	No	POP TOS	No
	operation	value	operation

Example: POP

GOTO NEW

Before Instruction

TOS 0031A2h Stack (1 level down) 014332h

After Instruction

TOS PC 014332h NEW

**PUSH Push Top of Return Stack** 

Syntax: [label] PUSH

Operands: None

Operation:  $(PC+2) \rightarrow TOS$ 

Status Affected: None

Encoding: 0000 0000 0000 0101

The PC+2 is pushed onto the top of Description: the return stack. The previous TOS

> value is pushed down on the stack. This instruction allows to implement a software stack by modifying TOS, and then push it onto the return

stack.

Words: 1 Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	PUSH PC+2	No	No
	onto return	operation	operation
	stack		

Example: PUSH

Before Instruction

TOS PC 00345Ah 000124h

After Instruction

PC TOS 000126h 000126h 00345Ah Stack (1 level down)

RCALL Relative Call

Syntax: [label] RCALL n

Operands:  $-1024 \le n \le 1023$ 

Operation: (PC) + 2  $\rightarrow$  TOS, (PC) + 2 + 2n  $\rightarrow$  PC

Status Affected: None

Encoding: 1101 1nnn nnnn nnnn

Description: Subroutine call with a jump up to 1K from the current location. First, return address (PC+2) is pushed

onto the stack. Then, add the 2's complement number '2n' to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC+2+2n. This instruction is a two-cycle

instruction.

Words: 1 Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal	Process Data	Write to PC
	Push PC to stack		
No	No	No	No
operation	operation	operation	operation

Example: HERE RCALL Jump

Before Instruction

PC = Address (HERE)

After Instruction

PC = Address (Jump) TOS = Address (HERE+2)

Reset			
[ label ]	RESET		
None			
All			
0000	0000	1111	1111
			,
1			
1			
	[ label ] None Reset all are affect All  0000 This instr	[ label ] RESET  None  Reset all registers are affected by a All  O000 0000  This instruction process.	[ label ] RESET  None  Reset all registers and flag are affected by a MCLR Re

Example: RESET

Q1

Decode

After Instruction

Registers = Reset Value Flags\* = Reset Value

Q2

Start

reset

Q3

No

operation

Q4

Νo

operation

RETFIE	Return from Interrupt
Syntax:	[label] RETFIE [s]
Operands:	s ∈ [0,1]
Operation:	$\begin{split} &(TOS) \to PC, \\ &1 \to GIE/GIEH \text{ or PEIE/GIEL}, \\ &\text{if s} = 1 \\ &(WS) \to W, \\ &(STATUSS) \to STATUS, \\ &(BSRS) \to BSR, \\ &PCLATU, PCLATH \text{ are unchanged}. \end{split}$
Status Affected:	GIE/GIEH, PEIE/GIEL.
Encoding:	0000 0000 0001 000s
Description:	Return from Interrupt. Stack is popped and Top-of-Stack (TOS) is loaded into the PC. Interrupts are enabled by setting either the high or low priority global interrupt

enable bit. If 's' = 1, the contents of the shadow registers WS, STATUSS and BSRS are loaded into their corresponding registers, W, STATUS and BSR. If 's' = 0, no

update of these registers occurs (default).

Words: 1 Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	No operation	No operation	pop PC from stack
			Set GIEH or GIEL
No	No	No	No
operation	operation	operation	operation

Example: RETFIE 1

After Interrupt

RETLW Return Literal to W

Syntax: [label] RETLW k
Operands:  $0 \le k \le 255$ 

PCLATU, PCLATH are unchanged

Status Affected: None

Encoding: 0000 1100 kkkk kkkk

Description: W is loaded with the eight-bit litera

escription: W is loaded with the eight-bit literal 'k'. The program counter is loaded from the top of the stack (the return address). The high address latch

(PCLATH) remains unchanged.

Words: 1 Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	pop PC from stack, Write to W
No	No	No	No
operation	operation	operation	operation

#### Example:

```
CALL TABLE ; W contains table ; offset value ; W now has ; table value
```

TABLE

ADDWF PCL ; W = offset RETLW k0 ; Begin table

RETLW k1:

RETLW kn ; End of table

Before Instruction

W = 0x07

After Instruction

W = value of kn

RETURN	Return from Subroutine				
Syntax:	[label] RETURN [s]				
Operands:	s ∈ [0,1]				
Operation:	$(TOS) \rightarrow PC$ , if s = 1 $(WS) \rightarrow W$ , $(STATUSS) \rightarrow STATUS$ , $(BSRS) \rightarrow BSR$ , PCLATU, $PCLATH$ are unchanged				
Status Affected:	None				
Encoding:	0000 0000 0001 001s				
Description:	Return from subroutine. The stack is popped and the top of the stack (TOS) is loaded into the program counter. If 's' = 1, the contents of the shadow registers WS, STATUSS and BSRS are loaded into their corresponding registers, W, STATUS and BSR. If 's' = 0, no update of these registers occurs (default).				
Words:	1				

Words: 1 Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	No	Process	pop PC from
	operation	Data	stack
No	No	No	No
operation	operation	operation	operation

Example: RETURN

After Interrupt PC = TOS

RLCF		Rotate Left f through Carry			
Synta	ıx:	[ label ]	RLCF	f [,d [,a]	
Opera	ands:	$0 \le f \le 25$ $d \in [0,1]$ $a \in [0,1]$	5		
Opera	ation:	$(f) \rightarrow (f<7>) \rightarrow (C) \rightarrow de$	C,	1>,	
Status	s Affected:	C, N, Z			
Enco	ding:	0011	01da	ffff	ffff
		The contents of register 'f' are rotated one bit to the left through the Carry Flag. If 'd' is 0, the result is placed in W. If 'd' is 1, the result is stored back in register 'f' (default). If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).			
Word	s:	1			
Cycle	es:	1			
Q Cy	cle Activity:				
	Q1	Q2	Q3		Q4
	Decode	Read register 'f'	Proces Data	-	rite to tination

Example: RLCF REG, 0, 0

Before Instruction

After Instruction

REG = 1110 0110 W = 1100 1100 C = 1

RLNCF	Rotate L	eft f (no	carry)	
Syntax:	[ label]	RLNCF	f [,d [,a	a]
Operands:	$0 \le f \le 25$ $d \in [0,1]$ $a \in [0,1]$	5		
Operation:	$ \begin{array}{c} (f < n >) \rightarrow \\ (f < 7 >) \rightarrow \end{array} $			
Status Affected:	N, Z			
Encoding:	0100	01da	ffff	ffff
Description:	The conterotated or the result the result 'f' (defaul Bank will the BSR bank will BSR valu	ne bit to is place is stored t). If 'a' is be select value. If be select ie (defau	the left. If d in W. If d back in s 0, the A cted, over 'a' is 1, th ted as pe	f 'd' is 0, 'd' is 1, register ccess riding nen the
Words:	1			
Cycles:	1			
Q Cycle Activity:				
Q1	Q2	Q3		Q4
Decode	Read register 'f'	Proces Data		rite to tination
Example:	RLNCF	REG,	1, 0	
Before Instru REG	ction = 1010 1	.011		

RRCF	Rotate Ri	Rotate Right f through Carry			
Syntax:	[ label ]	RRCF	f [,d [,a]		
Operands:	$0 \le f \le 25$ : $d \in [0,1]$ $a \in [0,1]$	5			
Operation:	$(f) \rightarrow (f<0>) \rightarrow (C) \rightarrow des$	C,	>,		
Status Affected:	C, N, Z				
Encoding:	0011	00da	ffff	ffff	
Description:	rotated or the Carry is placed is placed (default). Bank will the BSR v bank will	The contents of register 'f' are rotated one bit to the right through the Carry Flag. If 'd' is 0, the result is placed in W. If 'd' is 1, the result is placed back in register 'f' (default). If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' is 1, then the bank will be selected as per the BSR value (default).			
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2	Q3		Q4	
Decode	Read register 'f'	Proce: Data		rite to stination	
Example:	RRCF	REG,	0, 0		
Before Instruction  REG = 1110 0110					

After Instruction

REG = 0101 0111

**RRNCF** Rotate Right f (no carry) Syntax: [label] RRNCF f[,d[,a] Operands:  $0 \le f \le 255$  $d \in [0,1]$  $a \in [0,1]$ Operation:  $(f<n>) \rightarrow dest<n-1>,$  $(f<0>) \rightarrow dest<7>$ Status Affected: N, Z Encoding: 00da ffff ffff 0100 Description: The contents of register 'f' are rotated one bit to the right. If 'd' is 0, the result is placed in W. If 'd' is 1, the result is placed back in register 'f' (default). If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' is 1, then the bank will be selected as per the BSR value (default).

register f

Words: 1 1 Cycles:

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to
	register 'f'	Data	destination

Example 1: RRNCF REG, 1, 0

Before Instruction

REG = 1101 0111

After Instruction

REG 1110 1011

Example 2: RRNCF REG, 0, 0

Before Instruction

W

REG 1101 0111

After Instruction

1110 1011 REG 1101 0111

SETF	Set f					
Syntax:	[label]S	[label]SETF f[,a]				
Operands:	$0 \le f \le 255$ a $\in [0,1]$					
Operation:	$FFh \rightarrow f$					
Status Affected:	None					
Encoding:	0110	100a	ffff	ffff		
Description:	The conte			_		

ter are set to FFh. If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' is 1, then the bank will be selected as per the

BSR value (default).

Words: 1 Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write
	register 'f'	Data	register 'f'

Example: SETF REG,1

Before Instruction

REG 0x5A

After Instruction

REG 0xFF

SLEEP Enter SLEEP mode						
Synt	ax:	[ label]	[ label ] SLEEP			
Ope	rands:	None				
Ope	ration:					
Statu	us Affected:	$\overline{TO},\overline{PD}$				
Enco	oding:	0000	0000	000	0	0011
Desc	cription:	cleared. TO) is set its postso	The power-down status bit (PD) is cleared. The time-out status bit (TO) is set. Watchdog Timer and its postscaler are cleared. The processor is put into SLEEP mode with the oscillator stopped.			
Word	ds:	1				
Cycles:		1	1			
QC	cycle Activity:					
	Q1	Q2	Q3	ļ .		Q4
	Decode	No operation	Proce: Data			Go to sleep

Example:

Before Instruction

After Instruction  $\frac{\overline{TO}}{\overline{PD}} = 1 \uparrow \\ \overline{PD} = 0$ 

† If WDT causes wake-up, this bit is cleared.

SUE	BFWB	Sı	ubtract	f from W w	ith borrow		
Syn	tax:	[ /	abel]	SUBFWB	f [,d [,a]		
Ope	rands:		≤ f ≤ 25	55			
			∈ [0,1] ∈ [0,1]				
One	ration:			$-(\overline{C}) \rightarrow des$	<del>†</del>		
	us Affected:		, , ,	– (C) → des , DC, Z	ı		
					£ £ £ £ £ £ £		
	oding:		0101		ff ffff		
Des	cription:	(b m ste ste 0, ov the	Subtract register 'f and carry flag (borrow) from W (2's complement method). If 'd' is 0, the result is stored in W. If 'd' is 1, the result is stored in register 'f' (default). If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' is 1, then the bank will be selected as per the BSR value (default).				
Wor	ds:	1					
Сус	es:	1					
QC	Cycle Activity						
	Q1		<b>Q</b> 2	Q3	Q4		
	Decode		ead ster 'f'	Process Data	Write to destination		
Exa	mple 1:	SU	BFWB	REG, 1,	)		
	Before Instru	iction					
	REG W	=	3 2				
	C	=	1				
	After Instruc						
	REG W	=	FF 2				
	С	=	0				
	Z N	=	0 1 ; re	sult is negativ	re		
Exa	mple 2:	SU	BFWB	REG, 0,	)		
	Before Instru	ıction					
	REG	=	2				
	W C	=	5 1				
	After Instruc	tion					
	REG	=	2				
	W C	=	3 1				
	Ž	=	0	sult is positive	,		
Exa	mple 3:	SU	BFWB	REG, 1, (			
	Before Instru	ction					
	REG	=	1				
	C W	=	2 0				
	After Instruc		J				
	REG	=	0				
	W	=	2				
	C Z	=	1 ; re	sult is zero			
	N	=	0				

SUBLW	Subtract W from literal	SUBWF	Subtract W from f
Syntax:	[label] SUBLW k	Syntax:	[ label ] SUBWF f [,d [,a]
Operands:	$0 \le k \le 255$	Operands:	$0 \le f \le 255$
Operation:	$k - (W) \rightarrow W$		d ∈ [0,1]
Status Affected:	N, OV, C, DC, Z	0	$\mathbf{a} \in [0,1]$
Encoding:	0000 1000 kkkk kkkk	Operation:	$(f) - (W) \rightarrow dest$
Description:	W is subtracted from the eight-bit	Status Affected:	N, OV, C, DC, Z
	literal 'k'. The result is placed	Encoding:	0101 11da ffff ffff
Mondo	in W.	Description:	Subtract W from register 'f' (2's complement method). If 'd' is 0,
Words:	1		the result is stored in W. If 'd' is 1,
Cycles:	1		the result is stored back in register 'f' (default). If 'a' is 0, the
Q Cycle Activity: Q1	Q2 Q3 Q4		Access Bank will be selected,
Decode	Read Process Write to W		overriding the BSR value. If 'a' is
	literal 'k' Data		1, then the bank will be selected as per the BSR value (default).
Example 1:	SUBLW 0x02	Words:	1
Before Instru	etion	Cycles:	1
W	= 1	Q Cycle Activity:	•
C After Instructi	= ? on	Q1	Q2 Q3 Q4
W	= 1	Decode	Read Process Write to
C Z	= 1 ; result is positive = 0		register 'f' Data destination
N	= 0 = 0	Example 1:	SUBWF REG, 1, 0
Example 2:	SUBLW 0x02	Before Instruc	
Before Instru	etion	REG W	= 3 = 2
W C	= 2 = ?	С	= ?
After Instructi		After Instructi REG	on = 1
W	= 0		= 2
C Z	= 1 ; result is zero = 1	_	= 1 ; result is positive = 0
N	= 1 = 0	N	= 0
Example 3:	SUBLW 0x02	Example 2:	SUBWF REG, 0, 0
Before Instru	ction	Before Instruc	
W	= 3	REG W	= 2 = 2
C After Instructi	= ? on	С	= ?
W	= FF ; (2's complement)	After Instructi	
C Z	= 0 ; result is negative		= 2 = 0
Z N	= 0 = 1	C	= 1 ; result is zero
		Z N	= 1 = 0
		Example 3:	SUBWF REG, 1, 0
		Before Instruc	ction
			= 1
		W C	= 2 = ?
		After Instructi	
		REG	= FFh ;(2's complement)
			= 2 = 0 ; result is negative
		Z	= 0
		N	= 1

SUBWFB	Subtract \	N from f wit	Borrow	SWA	\PF	Swap f		
Syntax:	[label] S	UBWFB f[	d [,a]	Syn	tax:	[label] S	[label] SWAPF f[,d[,a]	
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	i		Ope	rands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	5	
Operation:	(f) - (W) -	$(\overline{C}) \to dest$		Ope	ration:		(f<3:0>) → dest<7:4>, (f<7:4>) → dest<3:0>	
Status Affected:	N, OV, C, I	DC, Z		State	us Affected:	None	7 0031<0.0>	
Encoding:	0101	10da fff	f ffff				55	
Description:		and the carr			Encoding: 0011 10da fff			
	method). If in W. If 'd' is back in reg the Access overriding t then the ba	egister 'f' (2's 'd' is 0, the re s 1, the result ister 'f' (defaus Bank will be the BSR valuank will be sel alue (default).	sult is stored is stored lt). If 'a' is 0, selected, e. If 'a' is 1,	Des	cription:	ister f are result is pl result is pl (default). I Bank will I the BSR v bank will I	exchanged.	Access overriding 1, then the
Words:	1			Wor	de:	1	(aciauli).	
Cycles:	1			Cycl		1		
Q Cycle Activity:	:			-				
Q1	Q2	Q3	Q4	Qt	Cycle Activity		Q3	04
Decode	Read register 'f'	Process Data	Write to destination		Q1 Decode	Q2 Read	Process	Q4 Write to
Example 1:	SUBWFB	REG, 1, 0				register 'f'	Data	destination
Before Instru		REG, I, U		Eva	mple:	SWAPF F	REG, 1, 0	
REG W C	= 0x19 = 0x0D	(0001 100 (0000 110	•	LX	Before Instri REG			
After Instruc	= 1 tion				After Instruc	tion		
REG	= 0x0C	(0000 101	.1)		REG	= 0x35		
W C	= 0x0D = 1	(0000 110	1)					
Z	= 1 = 0							
N	= 0	; result is po	sitive					
Example 2:		REG, 0, 0						
Before Instru		(0000 000	- >					
REG w	= 0x1B = 0x1A	(0001 101						
С	= 0	(0001 10	,					
After Instruc								
REG W	= 0x1B = 0x00	(0001 101	.1)					
C	= 1							
Z N	= 1 = 0	; result is ze	ero					
Example 3:	SUBWFB	REG, 1, 0						
Before Instru	uction							
REG	= 0x03	(0000 001	.1)					
W C	= 0x0E = 1	(0000 110	1)					
After Instruc								
REG	= 0xF5	(1111 010	00)					
W	= 0x0E	; [2's comp] (0000 110	11 \					
С	= 0	(0000 11(	111					
Z N	= 0 = 1	; result is ne	gative					

TBLRD Table Read

Syntax: [ label ] TBLRD ( \*; \*+; \*-; +\*)

Operands: None
Operation: if TBLRD \*,

(Prog Mem (TBLPTR)) → TABLAT;

TBLPTR - No Change;

if TBLRD \*+,

(Prog Mem (TBLPTR)) → TABLAT;

(TBLPTR) +1 → TBLPTR;

if TBLRD \*-,

 $(Prog Mem (TBLPTR)) \rightarrow TABLAT;$ 

(TBLPTR)  $-1 \rightarrow$  TBLPTR;

if TBLRD +\*,

 $(TBLPTR) + 1 \rightarrow TBLPTR;$ 

(Prog Mem (TBLPTR)) → TABLAT;

Status Affected: None

Encoding: 0000

0000	0000	10nn	
		nn=0	*
		=1	*+
		=2	* _
		=3	+*
	0000	0000 0000	nn=0 =1 =2

Description:

This instruction is used to read the contents of Program Memory (P.M.). To address the program memory, a pointer called Table Pointer (TBLPTR) is used. The TBLPTR (a 21-bit pointer) points to each byte in the program memory. TBLPTR has a 2 Mbyte address range.

TBLPTR[0] = 0: Least Significant Byte of Program

Memory Word

TBLPTR[0] = 1: Most Significant

Byte of Program Memory Word

The TBLRD instruction can modify the value of TBLPTR as follows:

no change

· post-increment

· post-decrement

· pre-increment

Words: 1
Cycles: 2
Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	No	No	No
	operation	operation	operation
No operation	No operation (Read Program Memory)	No operation	No operation (Write TABLAT)

TBLRD Table Read (cont'd)

Example1:

Before Instruction

TABLAT = 0x55 TBLPTR = 0x00A356 MEMORY(0x00A356) = 0x34

After Instruction

TABLAT = 0x34 TBLPTR = 0x00A357

Example2: TBLRD +\*;

Before Instruction

TABLAT = 0xAA TBLPTR = 0x01A357 MEMORY(0x01A357) = 0x12 MEMORY(0x01A358) = 0x34

After Instruction

TABLAT = 0x34TBLPTR = 0x01A358 **TBLWT Table Write** 

Syntax: [ label ] TBLWT ( \*; \*+; \*-; +\*)

Operands: None Operation: if TBLWT\*,

 $(TABLAT) \rightarrow Holding Register;$ 

TBLPTR - No Change;

if TBLWT\*+.

(TABLAT) → Holding Register;  $(TBLPTR) +1 \rightarrow TBLPTR;$ 

if TBLWT\*-

(TABLAT) → Holding Register; (TBLPTR)  $-1 \rightarrow$  TBLPTR;

if TBLWT+\*

 $(TBLPTR) +1 \rightarrow TBLPTR;$ (TABLAT) → Holding Register;

Status Affected: None

Encoding:

0000	0000	0000	11nn	
			nn=0	*
			=1	*+
			=2	* _
			=3	+*

Description:

This instruction uses the 3 LSbs of the TBLPTR to determine which of the 8 holding registers the TABLAT data is written to. The 8 holding registers are used to program the contents of Program Memory (P.M.). See Section 5.0 for information on writing to FLASH

The TBLPTR (a 21-bit pointer) points to each byte in the program memory. TBLPTR has a 2 MBtye address range. The LSb of the TBLPTR selects which byte of the program memory location to access.

> TBLPTR[0] = 0: Least Significant Byte of Program Memory Word

> TBLPTR[0] = 1: Most Significant Byte of Program Memory Word

The TBLWT instruction can modify the value of TBLPTR as follows:

no change

post-increment

post-decrement

pre-increment

Words: Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	No	No	No
	operation	operation	operation
No	No	No	No
operation	operation	operation	operation
	(Read		(Write to Holding
	TABLAT)		Register or Memory)

**TBLWT** Table Write (Continued)

Example1:

Before Instruction

**TABLAT** 0x55 **TBLPTR** 0x00A356 HOLDING REGISTER (0x00A356) 0xFF

After Instructions (table write completion)

TABLAT 0x55 **TBLPTR** 0x00A357 HOLDING REGISTER

(0x00A356) 0x55

Example 2: TBLWT +\*;

Before Instruction

**TABLAT** 0x34 **TBLPTR** 0x01389A

HOLDING REGISTER (0x01389A)

0xFF HOLDING REGISTER (0x01389B) 0xFF

After Instruction (table write completion)

TABLAT 0x01389B **TBLPTR** 

HOLDING REGISTER

(0x01389A) 0xFF HOLDING REGISTER (0x01389B) 0x34 **TSTFSZ** Test f, skip if 0

Syntax: [label] TSTFSZ f[,a]

Operands:  $0 \le f \le 255$ 

 $a \in [0,1]$ 

skip if f = 0Operation:

Status Affected: None

Encoding: 0110 011a ffff ffff

If f' = 0, the next instruction, Description:

fetched during the current instruction execution, is discarded and a NOP is executed, making this a twocycle instruction. If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' is 1, then the bank will be selected as per the BSR value (default).

1 Words: Cycles: 1(2)

Note: 3 cycles if skip and followed

by a 2-word instruction.

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	No
	register 'f'	Data	operation

If skip:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation

If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation
No	No	No	No
operation	operation	operation	operation

Example: TSTFSZ CNT, 1

> NZERO ZERO

Before Instruction

PC = Address (HERE)

After Instruction

If CNT 0x00,

PC If CNT Address (ZERO)

0x00,

Address (NZERO)

**XORLW Exclusive OR literal with W** 

[label] XORLW k Syntax:

Operands:  $0 \le k \le 255$ 

(W) .XOR.  $k \rightarrow W$ Operation:

Status Affected: N, Z

Encoding: 0000 1010 kkkk kkkk

Description: The contents of W are XORed

with the 8-bit literal 'k'. The result

is placed in W.

Words: Cycles:

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to W
	literal 'k'	Data	

Example: XORLW 0xAF

Before Instruction

W 0xB5

After Instruction

W 0x1A

### PIC18FXX2

### XORWF Exclusive OR W with f

Syntax: [ label ] XORWF f [,d [,a]

Operands:  $0 \le f \le 255$ 

 $\begin{array}{l} d \in \left[0,1\right] \\ a \in \left[0,1\right] \end{array}$ 

Operation: (W) .XOR. (f)  $\rightarrow$  dest

Status Affected: N, Z

Encoding: 0001 10da fffff ffff

Description: Exclusive OR the contents of W

with register 'f'. If 'd' is 0, the result is stored in W. If 'd' is 1, the result is stored back in the register 'f' (default). If 'a' is 0, the Access Bank will be selected, overriding the BSR value. If 'a' is 1, then the bank will be selected as per the

BSR value (default).

Words: 1 Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to
	register 'f'	Data	destination

Example: XORWF REG, 1, 0

Before Instruction

 $\begin{array}{rcl} \mathsf{REG} & = & \mathsf{0xAF} \\ \mathsf{W} & = & \mathsf{0xB5} \end{array}$ 

After Instruction

 $\begin{array}{rcl} REG & = & 0x1A \\ W & = & 0xB5 \end{array}$ 

#### 21.0 DEVELOPMENT SUPPORT

The PICmicro<sup>®</sup> microcontrollers are supported with a full range of hardware and software development tools:

- · Integrated Development Environment
  - MPLAB® IDE Software
- · Assemblers/Compilers/Linkers
  - MPASM™ Assembler
  - MPLAB C17 and MPLAB C18 C Compilers
  - MPLINK™ Object Linker/ MPLIB™ Object Librarian
- · Simulators
  - MPLAB SIM Software Simulator
- Emulators
  - MPLAB ICE 2000 In-Circuit Emulator
  - ICEPIC™ In-Circuit Emulator
- · In-Circuit Debugger
  - MPLAB ICD
- · Device Programmers
  - PRO MATE® II Universal Device Programmer
  - PICSTART® Plus Entry-Level Development Programmer
- · Low Cost Demonstration Boards
  - PICDEM™ 1 Demonstration Board
  - PICDEM 2 Demonstration Board
  - PICDEM3 Demonstration Board
  - PICDEM 17 Demonstration Board
  - KEELOQ® Demonstration Board

### 21.1 MPLAB Integrated Development Environment Software

The MPLAB IDE software brings an ease of software development previously unseen in the 8-bit microcontroller market. The MPLAB IDE is a Windows® based application that contains:

- · An interface to debugging tools
  - simulator
  - programmer (sold separately)
  - emulator (sold separately)
  - in-circuit debugger (sold separately)
- · A full-featured editor
- · A project manager
- · Customizable toolbar and key mapping
- · A status bar
- · On-line help

The MPLAB IDE allows you to:

- · Edit your source files (either assembly or 'C')
- One touch assemble (or compile) and download to PICmicro emulator and simulator tools (automatically updates all project information)
- · Debug using:
  - source files
  - absolute listing file
  - machine code

The ability to use MPLAB IDE with multiple debugging tools allows users to easily switch from the cost-effective simulator to a full-featured emulator with minimal retraining.

#### 21.2 MPASM Assembler

The MPASM assembler is a full-featured universal macro assembler for all PICmicro MCU's.

The MPASM assembler has a command line interface and a Windows shell. It can be used as a stand-alone application on a Windows 3.x or greater system, or it can be used through MPLAB IDE. The MPASM assembler generates relocatable object files for the MPLINK object linker, Intel<sup>®</sup> standard HEX files, MAP files to detail memory usage and symbol reference, an absolute LST file that contains source lines and generated machine code, and a COD file for debugging.

The MPASM assembler features include:

- · Integration into MPLAB IDE projects.
- User-defined macros to streamline assembly code
- Conditional assembly for multi-purpose source files
- Directives that allow complete control over the assembly process.

# 21.3 MPLAB C17 and MPLAB C18 C Compilers

The MPLAB C17 and MPLAB C18 Code Development Systems are complete ANSI 'C' compilers for Microchip's PIC17CXXX and PIC18CXXX family of microcontrollers, respectively. These compilers provide powerful integration capabilities and ease of use not found with other compilers.

For easier source level debugging, the compilers provide symbol information that is compatible with the MPLAB IDE memory display.

### 21.4 MPLINK Object Linker/ MPLIB Object Librarian

The MPLINK object linker combines relocatable objects created by the MPASM assembler and the MPLAB C17 and MPLAB C18 C compilers. It can also link relocatable objects from pre-compiled libraries, using directives from a linker script.

The MPLIB object librarian is a librarian for precompiled code to be used with the MPLINK object linker. When a routine from a library is called from another source file, only the modules that contain that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications. The MPLIB object librarian manages the creation and modification of library files.

The MPLINK object linker features include:

- Integration with MPASM assembler and MPLAB C17 and MPLAB C18 C compilers.
- Allows all memory areas to be defined as sections to provide link-time flexibility.

The MPLIB object librarian features include:

- Easier linking because single libraries can be included instead of many smaller files.
- Helps keep code maintainable by grouping related modules together.
- Allows libraries to be created and modules to be added, listed, replaced, deleted or extracted.

### 21.5 MPLAB SIM Software Simulator

The MPLAB SIM software simulator allows code development in a PC-hosted environment by simulating the PICmicro series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file, or user-defined key press, to any of the pins. The execution can be performed in single step, execute until break, or trace mode.

The MPLAB SIM simulator fully supports symbolic debugging using the MPLAB C17 and the MPLAB C18 C compilers and the MPASM assembler. The software simulator offers the flexibility to develop and debug code outside of the laboratory environment, making it an excellent multiproject software development tool.

# 21.6 MPLAB ICE High Performance Universal In-Circuit Emulator with MPLAB IDE

The MPLAB ICE universal in-circuit emulator is intended to provide the product development engineer with a complete microcontroller design tool set for PICmicro microcontrollers (MCUs). Software control of the MPLAB ICE in-circuit emulator is provided by the MPLAB Integrated Development Environment (IDE), which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICE 2000 is a full-featured emulator system with enhanced trace, trigger and data monitoring features. Interchangeable processor modules allow the system to be easily reconfigured for emulation of different processors. The universal architecture of the MPLAB ICE in-circuit emulator allows expansion to support new PICmicro microcontrollers.

The MPLAB ICE in-circuit emulator system has been designed as a real-time emulation system, with advanced features that are generally found on more expensive development tools. The PC platform and Microsoft<sup>®</sup> Windows environment were chosen to best make these features available to you, the end user.

#### 21.7 ICEPIC In-Circuit Emulator

The ICEPIC low cost, in-circuit emulator is a solution for the Microchip Technology PIC16C5X, PIC16C6X, PIC16C7X and PIC16CXXX families of 8-bit One-Time-Programmable (OTP) microcontrollers. The modular system can support different subsets of PIC16C5X or PIC16CXXX products through the use of interchangeable personality modules, or daughter boards. The emulator is capable of emulating without target application circuitry being present.

### 21.8 MPLAB ICD In-Circuit Debugger

Microchip's In-Circuit Debugger, MPLAB ICD, is a powerful, low cost, run-time development tool. This tool is based on the FLASH PICmicro MCUs and can be used to develop for this and other PICmicro microcontrollers. The MPLAB ICD utilizes the in-circuit debugging capability built into the FLASH devices. This feature, along with Microchip's In-Circuit Serial Programming™ protocol, offers cost-effective in-circuit FLASH debugging from the graphical user interface of the MPLAB Integrated Development Environment. This enables a designer to develop and debug source code by watching variables, single-stepping and setting break points. Running at full speed enables testing hardware in real-time.

### 21.9 PRO MATE II Universal Device Programmer

The PRO MATE II universal device programmer is a full-featured programmer, capable of operating in stand-alone mode, as well as PC-hosted mode. The PRO MATE II device programmer is CE compliant.

The PRO MATE II device programmer has programmable VDD and VPP supplies, which allow it to verify programmed memory at VDD min and VDD max for maximum reliability. It has an LCD display for instructions and error messages, keys to enter commands and a modular detachable socket assembly to support various package types. In stand-alone mode, the PRO MATE II device programmer can read, verify, or program PICmicro devices. It can also set code protection in this mode.

### 21.10 PICSTART Plus Entry Level Development Programmer

The PICSTART Plus development programmer is an easy-to-use, low cost, prototype programmer. It connects to the PC via a COM (RS-232) port. MPLAB Integrated Development Environment software makes using the programmer simple and efficient.

The PICSTART Plus development programmer supports all PICmicro devices with up to 40 pins. Larger pin count devices, such as the PIC16C92X and PIC17C76X, may be supported with an adapter socket. The PICSTART Plus development programmer is CE compliant.

### 21.11 PICDEM 1 Low Cost PICmicro Demonstration Board

The PICDEM 1 demonstration board is a simple board which demonstrates the capabilities of several of Microchip's microcontrollers. The microcontrollers supported are: PIC16C5X (PIC16C54 to PIC16C58A), PIC16C61, PIC16C62X, PIC16C71, PIC16C8X, PIC17C42, PIC17C43 and PIC17C44. All necessary hardware and software is included to run basic demo programs. The user can program the sample microcontrollers provided with the PICDEM 1 demonstration board on a PRO MATE II device programmer, or a PICSTART Plus development programmer, and easily test firmware. The user can also connect the PICDEM 1 demonstration board to the MPLAB ICE incircuit emulator and download the firmware to the emulator for testing. A prototype area is available for the user to build some additional hardware and connect it to the microcontroller socket(s). Some of the features include an RS-232 interface, a potentiometer for simulated analog input, push button switches and eight LEDs connected to PORTB.

### 21.12 PICDEM 2 Low Cost PIC16CXX Demonstration Board

The PICDEM 2 demonstration board is a simple demonstration board that supports the PIC16C62, PIC16C64, PIC16C65, PIC16C73 and PIC16C74 microcontrollers. All the necessary hardware and software is included to run the basic demonstration pro-The user can program the sample microcontrollers provided with the PICDEM 2 demonstration board on a PRO MATE II device programmer. or a PICSTART Plus development programmer, and easily test firmware. The MPLAB ICE in-circuit emulator may also be used with the PICDEM 2 demonstration board to test firmware. A prototype area has been provided to the user for adding additional hardware and connecting it to the microcontroller socket(s). Some of the features include a RS-232 interface, push button switches, a potentiometer for simulated analog input, a serial EEPROM to demonstrate usage of the I<sup>2</sup>C<sup>™</sup> bus and separate headers for connection to an LCD module and a keypad.

### 21.13 PICDEM 3 Low Cost PIC16CXXX Demonstration Board

The PICDEM 3 demonstration board is a simple demonstration board that supports the PIC16C923 and PIC16C924 in the PLCC package. It will also support future 44-pin PLCC microcontrollers with an LCD Module. All the necessary hardware and software is included to run the basic demonstration programs. The user can program the sample microcontrollers provided with the PICDEM 3 demonstration board on a PRO MATE II device programmer, or a PICSTART Plus development programmer with an adapter socket, and easily test firmware. The MPLAB ICE in-circuit emulator may also be used with the PICDEM 3 demonstration board to test firmware. A prototype area has been provided to the user for adding hardware and connecting it to the microcontroller socket(s). Some of the features include a RS-232 interface, push button switches, a potentiometer for simulated analog input, a thermistor and separate headers for connection to an external LCD module and a keypad. Also provided on the PICDEM 3 demonstration board is a LCD panel, with 4 commons and 12 segments, that is capable of displaying time, temperature and day of the week. The PICDEM 3 demonstration board provides an additional RS-232 interface and Windows software for showing the demultiplexed LCD signals on a PC. A simple serial interface allows the user to construct a hardware demultiplexer for the LCD signals.

#### 21.14 PICDEM 17 Demonstration Board

The PICDEM 17 demonstration board is an evaluation board that demonstrates the capabilities of several Microchip microcontrollers, including PIC17C752, PIC17C756A, PIC17C762 and PIC17C766. All necessary hardware is included to run basic demo programs, which are supplied on a 3.5-inch disk. A programmed sample is included and the user may erase it and program it with the other sample programs using the PRO MATE II device programmer, or the PICSTART Plus development programmer, and easily debug and test the sample code. In addition, the PICDEM 17 demonstration board supports downloading of programs to and executing out of external FLASH memory on board. The PICDEM 17 demonstration board is also usable with the MPLAB ICE in-circuit emulator, or the PICMASTER emulator and all of the sample programs can be run and modified using either emulator. Additionally, a generous prototype area is available for user hardware.

### 21.15 KEELOQ Evaluation and Programming Tools

KEELOQ evaluation and programming tools support Microchip's HCS Secure Data Products. The HCS evaluation kit includes a LCD display to show changing codes, a decoder to decode transmissions and a programming interface to program test transmitters.

TABLE 21-1: DEVELOPMENT TOOLS FROM MICROCHIP

						)	>	1	)		-	X		X	2	>				
		PICISCXXX	PIC14000	PIC16C5X	PIC16C6X	PIC16CXXX	PIC16F62)	PIC16C7X	PIC16C7XX	PIC16F8X	PIC16F8XX	PIC16C9X)	PIC17C4X	XTOTIOIA	PIC18CXX	PIC18FXXX	93CXX SECXX\ SHCXX\	нсеххх	WCBEXXX	WCP2510
MPLAB® Integrated Development Environment	d onment	>	>	>	>	>	>	>	>	>	>	>	>	>	>	>				
MPLAB® C17 C Compiler	mpiler												>	>						
MPLAB <sup>®</sup> C18 C Compiler	mpiler														^	1				
MPASM™ Assembler/ MPLINK™ Object Linker	ler/ inker	>	>	>	>	>	>	>	>	>	>	>	>	>	>	>	>	>		
MPLAB® ICE In-Circuit Emulator	cuit Emulator	>	>	`>	`	`>	** `	`	`	`	`	>	>	>	>	^				
ICEPICTM In-Circuit Emulator	Emulator	>		>	>	>		>	>	>		>								
MPLAB® ICD In-Circuit Debugger	cuit				*,			*			>					<b>*</b>				
PICSTART® Plus Entry Level Development Programmer	ntry Level rammer	>	>	>	>	>	**	>	>	>	`	>	>	>	>	^				
PRO MATE® II Universal Device Programmer	rogrammer	>	>	>	>	>	**	>	>	>	>	>	>	>	>	>	<i>&gt;</i>	>		
PICDEM™ 1 Demonstration Board	nstration			>		>		+		`			>							
PICDEM™ 2 Demonstration Board	nstration				7			7							>	>				
PICDEM™ 3 Demonstration Board	nstration											>								
PICDEM™ 14A Demonstration Board	nonstration		>																	
PICDEM™ 17 Demonstration Board	onstration													^						
KEELOQ® Evaluation Kit	n Kit																	>		
KEELoo® Transponder Kit	ider Kit																	`		
microlD™ Programmer's Kit	mer's Kit																		>	
125 kHz microlD™ Developer's Kit																			>	
125 kHz Anticollision microlD™ Developer's Kit	on microID <sup>TM</sup>																		^	
13.56 MHz Anticollision microlD™ Developer's Kit	sion er's Kit																		>	
MCP2510 CAN Developer's Kit	eloper's Kit																			>

© 2002 Microchip Technology Inc.

### PIC18FXX2

**NOTES:** 

### 22.0 ELECTRICAL CHARACTERISTICS

### Absolute Maximum Ratings (†)

Ambient temperature under bias	55°C to +125°C
Storage temperature	65°C to +150°C
Voltage on any pin with respect to Vss (except VDD, MCLR, and RA4)	
Voltage on VDD with respect to VSS	-0.3V to +7.5V
Voltage on MCLR with respect to Vss (Note 2)	
Voltage on RA4 with respect to Vss	0V to +8.5V
Total power dissipation (Note 1)	1.0W
Maximum current out of Vss pin	300 mA
Maximum current into VDD pin	250 mA
Input clamp current, IiK (VI < 0 or VI > VDD)	±20 mA
Output clamp current, IOK (VO < 0 or VO > VDD)	±20 mA
Maximum output current sunk by any I/O pin	25 mA
Maximum output current sourced by any I/O pin	25 mA
Maximum current sunk by PORTA, PORTB, and PORTE (Note 3) (combined)	200 mA
Maximum current sourced by PORTA, PORTB, and PORTE (Note 3) (combined)	200 mA
Maximum current sunk by PORTC and PORTD (Note 3) (combined)	200 mA
Maximum current sourced by PORTC and PORTD (Note 3) (combined)	200 mA

- Note 1: Power dissipation is calculated as follows: Pdis = VDD x {IDD  $\sum$  IOH} +  $\sum$  {(VDD-VOH) x IOH} +  $\sum$ (VOI x IOL)
  - 2: Voltage spikes below Vss at the  $\overline{MCLR}/VPP$  pin, inducing currents greater than 80 mA, may cause latchup. Thus, a series resistor of 50-100 $\Omega$  should be used when applying a "low" level to the  $\overline{MCLR}/VPP$  pin, rather than pulling this pin directly to Vss.
  - 3: PORTD and PORTE not available on the PIC18F2X2 devices.

† NOTICE: Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.

FIGURE 22-1: PIC18FXX2 VOLTAGE-FREQUENCY GRAPH (INDUSTRIAL)





FIGURE 22-2: PIC18LFXX2 VOLTAGE-FREQUENCY GRAPH (INDUSTRIAL)



### 22.1 DC Characteristics: PIC18FXX2 (Industrial, Extended) PIC18LFXX2 (Industrial)

PIC18L (Ind	FXX2 ustrial)			ard Ope			itions (unless otherwise stated) -40°C ≤ TA ≤ +85°C for industrial
PIC18F (Ind	<b>XX2</b> ustrial, Ex	itended)		ard Ope	_	ire ·	itions (unless otherwise stated) -40°C ≤ TA ≤ +85°C for industrial -40°C ≤ TA ≤ +125°C for extended
Param No.	Symbol	Characteristic	Min	Тур	Max	Units	Conditions
	VDD	Supply Voltage		<u>'</u>			
D001		PIC18LFXX2	2.0	_	5.5	V	HS, XT, RC and LP Osc mode
D001		PIC18FXX2	4.2	_	5.5	V	
D002	VDR	RAM Data Retention Voltage <sup>(1)</sup>	1.5	_	_	V	
D003	VPOR	VDD Start Voltage to ensure internal Power-on Reset signal	_	_	0.7	V	See Section 3.1 (Power-on Reset) for details
D004	SVDD	VDD Rise Rate to ensure internal Power-on Reset signal	0.05	_	_	V/ms	See Section 3.1 (Power-on Reset) for details
	VBOR	Brown-out Reset Voltage	je		•	•	
D005		PIC18LFXX2					
		BORV1:BORV0 = 11	1.98	_	2.14	V	85°C ≥ T ≥ 25°C
		BORV1:BORV0 = 10	2.67	_	2.89	V	
		BORV1:BORV0 = 01	4.16	_	4.5	V	
		BORV1:BORV0 = 00	4.45	_	4.83	V	
D005		PIC18FXX2					
		BORV1:BORV0 = 1x	N.A.	_	N.A.	V	Not in operating voltage range of device
		BORV1:BORV0 = 01	4.16	_	4.5	V	
		BORV1:BORV0 = 00	4.45	_	4.83	V	

Legend: Shading of rows is to assist in readability of the table.

Note 1: This is the limit to which VDD can be lowered in SLEEP mode, or during a device RESET, without losing RAM data.

2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active Operation mode are:

- 3: The power-down current in SLEEP mode does not depend on the oscillator type. Power-down current is measured with the part in SLEEP mode, with all I/O pins in hi-impedance state and tied to VDD or Vss, and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR,...).
- **4:** For RC osc configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kOhm.
- 5: The LVD and BOR modules share a large portion of circuitry. The \( \Delta \text{BOR} \) and \( \Delta \text{LVD} \) currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

### 22.1 DC Characteristics: PIC18FXX2 (Industrial, Extended) PIC18LFXX2 (Industrial) (Continued)

PIC18L (Ind	FXX2 ustrial)			ard Ope			itions (unless otherwise stated) -40°C $\leq$ TA $\leq$ +85°C for industrial
PIC18F	<b>XX2</b> ustrial, Ex	tended)		ard Ope		ire -	itions (unless otherwise stated) -40°C ≤ TA ≤ +85°C for industrial -40°C ≤ TA ≤ +125°C for extended
Param No.	Symbol	Characteristic	Min	Тур	Max	Units	Conditions
	IDD	Supply Current <sup>(2,4)</sup>		•	•	•	
D010		PIC18LFXX2		.5 .5 1.2 .3 .3 1.5	1 1.25 2 1 1 3 1 1 3	mA mA mA mA mA mA	XT osc configuration  VDD = 2.0V, +25°C, FOSC = 4 MHz  VDD = 2.0V, -40°C to +85°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FOSC = 4 MHz  RC osc configuration  VDD = 2.0V, +25°C, FOSC = 4 MHz  VDD = 2.0V, -40°C to +85°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FOSC = 4 MHz  RCIO osc configuration  VDD = 2.0V, +25°C, FOSC = 4 MHz  VDD = 2.0V, +25°C, FOSC = 4 MHz  VDD = 2.0V, -40°C to +85°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FOSC = 4 MHz
D010		PIC18FXX2		1.2 1.2 1.2 1.5 1.5 1.6 .75 .75	1.5 2 3 4 4 2 3 3	mA mA mA mA mA mA	XT osc configuration  VDD = 4.2V, +25°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +125°C, FOSC = 4 MHz  RC osc configuration  VDD = 4.2V, +25°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +125°C, FOSC = 4 MHz  RCIO osc configuration  VDD = 4.2V, +25°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +125°C, FOSC = 4 MHz
D010A		PIC18LFXX2	_	14	30	μΑ	LP osc, Fosc = 32 kHz, WDT disabled VDD = 2.0V, -40°C to +85°C
D010A	Cha -!'	PIC18FXX2	_	40 50	70 100	μ <b>Α</b> μ <b>Α</b>	LP osc, Fosc = 32 kHz, WDT disabled VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C

Legend: Shading of rows is to assist in readability of the table.

- Note 1: This is the limit to which VDD can be lowered in SLEEP mode, or during a device RESET, without losing RAM data.
  - 2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active Operation mode are:

- **3:** The power-down current in SLEEP mode does not depend on the oscillator type. Power-down current is measured with the part in SLEEP mode, with all I/O pins in hi-impedance state and tied to VDD or Vss, and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR,...).
- **4:** For RC osc configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kOhm.
- 5: The LVD and BOR modules share a large portion of circuitry. The ΔIBOR and ΔILVD currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

### 22.1 DC Characteristics: PIC18FXX2 (Industrial, Extended) PIC18LFXX2 (Industrial) (Continued)

PIC18L (Ind	FXX2 ustrial)			ard Ope			itions (unless otherwise stated) -40°C ≤ Ta ≤ +85°C for industrial
PIC18F (Ind	XX2 ustrial, Ex	tended)		ard Ope		ire ·	itions (unless otherwise stated) -40°C ≤ Ta ≤ +85°C for industrial -40°C ≤ Ta ≤ +125°C for extended
Param No.	Symbol	Characteristic	Min	Тур	Max	Units	Conditions
	IDD	Supply Current <sup>(2,4)</sup> (Co	ntinuec	d)			
D010C		PIC18LFXX2		10	25	mA	EC, ECIO osc configurations VDD = 4.2V, -40°C to +85°C
D010C		PIC18FXX2	_	10	25	mA	EC, ECIO osc configurations VDD = 4.2V, -40°C to +125°C
D013		PIC18LFXX2	_ _ _	.6 10 15	2 15 25	mA mA	HS osc configuration FOSC = 4 MHz, VDD = 2.0V FOSC = 25 MHz, VDD = 5.5V HS + PLL osc configurations FOSC = 10 MHz, VDD = 5.5V
D013		PIC18FXX2	_	10 15	15 25	mA mA	HS osc configuration Fosc = 25 MHz, VDD = 5.5V HS + PLL osc configurations Fosc = 10 MHz, VDD = 5.5V
D014		PIC18LFXX2	_	15	55	μΑ	Timer1 osc configuration FOSC = 32 kHz, VDD = 2.0V
D014		PIC18FXX2	_	_	200 250	μ <b>Α</b> μ <b>Α</b>	Timer1 osc configuration FOSC = 32 kHz, VDD = 4.2V, -40°C to +85°C FOSC = 32 kHz, VDD = 4.2V, -40°C to +125°C
	IPD	Power-down Current <sup>(3)</sup>					
D020		PIC18LFXX2	_	.08 .1 3	.9 4 10	μΑ μΑ μΑ	VDD = 2.0V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C
D020 D021B		PIC18FXX2	_	.1 3 15	.9 10 25	μΑ μΑ μΑ	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C

Legend: Shading of rows is to assist in readability of the table.

Note 1: This is the limit to which VDD can be lowered in SLEEP mode, or during a device RESET, without losing RAM data.

2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active Operation mode are:

- 3: The power-down current in SLEEP mode does not depend on the oscillator type. Power-down current is measured with the part in SLEEP mode, with all I/O pins in hi-impedance state and tied to VDD or Vss, and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR,...).
- **4:** For RC osc configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kOhm.
- 5: The LVD and BOR modules share a large portion of circuitry. The ΔIBOR and ΔILVD currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

# 22.1 DC Characteristics: PIC18FXX2 (Industrial, Extended) PIC18LFXX2 (Industrial) (Continued)

PIC18L (Ind	FXX2 ustrial)			ard Ope			itions (unless otherwise stated) -40°C $\leq$ TA $\leq$ +85°C for industrial
PIC18F.	<b>XX2</b> ustrial, Ex	tended)		ard Ope		ıre -	itions (unless otherwise stated) -40°C ≤ TA ≤ +85°C for industrial -40°C ≤ TA ≤ +125°C for extended
Param No.	Symbol	Characteristic	Min	Тур	Max	Units	Conditions
		Module Differential Cur	rent				
D022	Δlwdt	Watchdog Timer PIC18LFXX2		.75 2 10	1.5 8 25	μ <b>Α</b> μ <b>Α</b> μ <b>Α</b>	VDD = 2.0V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C
D022		Watchdog Timer PIC18FXX2		7 10 25	15 25 40	μΑ μΑ μΑ	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C
D022A	ΔIBOR	Brown-out Reset <sup>(5)</sup> PIC18LFXX2		29 29 33	35 45 50	μΑ μΑ μΑ	VDD = 2.0V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C
D022A		Brown-out Reset <sup>(5)</sup> PIC18FXX2	1	36 36 36	40 50 65	μΑ μΑ μΑ	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C
D022B	ΔILVD	Low Voltage Detect <sup>(5)</sup> PIC18LFXX2		29 29 33	35 45 50	μΑ μΑ μΑ	VDD = 2.0V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C
D022B		Low Voltage Detect <sup>(5)</sup> PIC18FXX2		33 33 33	40 50 65	μΑ μΑ μΑ	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C
D025	ΔITMR1	Timer1 Oscillator PIC18LFXX2		5.2 5.2 6.5	30 40 50	μΑ μΑ μΑ	VDD = 2.0V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C
D025		Timer1 Oscillator PIC18FXX2	_	6.5 6.5 6.5	40 50 65	μ <b>Α</b> μ <b>Α</b> μ <b>Α</b>	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C

Legend: Shading of rows is to assist in readability of the table.

Note 1: This is the limit to which VDD can be lowered in SLEEP mode, or during a device RESET, without losing RAM data.

2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active Operation mode are:

- 3: The power-down current in SLEEP mode does not depend on the oscillator type. Power-down current is measured with the part in SLEEP mode, with all I/O pins in hi-impedance state and tied to VDD or Vss, and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR,...).
- **4:** For RC osc configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kOhm.
- 5: The LVD and BOR modules share a large portion of circuitry. The ΔIBOR and ΔILVD currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

# 22.2 DC Characteristics: PIC18FXX2 (Industrial, Extended) PIC18LFXX2 (Industrial)

DC CHA	ARACTER	RISTICS		emperature -4	l0°C ≤	s (unless otherwise stated) TA $\leq$ +85°C for industrial TA $\leq$ +125°C for extended
Param No.	Symbol	Characteristic	Min	Max	Units	Conditions
	VIL	Input Low Voltage				
		I/O ports:				
D030		with TTL buffer	Vss	0.15 VDD	V	VDD < 4.5V
D030A			_	0.8	V	$4.5V \le VDD \le 5.5V$
D031		with Schmitt Trigger buffer	Vss	0.2 VDD	V	
		RC3 and RC4	Vss	0.3 VDD	V	
D032		MCLR	Vss	0.2 VDD	V	
D032A		OSC1 (in XT, HS and LP modes) and T1OSI	Vss	0.3 VDD	V	
D033		OSC1 (in RC and EC mode) <sup>(1)</sup>	Vss	0.2 VDD	V	
	ViH	Input High Voltage				
		I/O ports:				
D040		with TTL buffer	0.25 VDD + 0.8V	VDD	V	VDD < 4.5V
D040A			2.0	VDD	V	4.5V ≤ VDD ≤ 5.5V
D041		with Schmitt Trigger buffer RC3 and RC4	0.8 VDD 0.7 VDD	Vdd Vdd	V V	
D042		MCLR, OSC1 (EC mode)	0.7 VDD	VDD	V	
D042A		OSC1 (in XT, HS and LP modes)	0.7 VDD	VDD	V	
D042A		and T1OSI	0.7 400	<b>V</b> DD	\ \ \	
D043		OSC1 (RC mode) <sup>(1)</sup>	0.9 Vdd	VDD	V	
	I⊫	Input Leakage Current <sup>(2,3)</sup>				
D060		I/O ports	.02	±1	μΑ	Vss ≤ VPIN ≤ VDD, Pin at hi-impedance
D061		MCLR		±1	μΑ	Vss ≤ VPIN ≤ VDD
D063		OSC1	_	±1	μΑ	Vss ≤ Vpin ≤ Vdd
	IPU	Weak Pull-up Current				
D070	IPURB	PORTB weak pull-up current	50	450	μΑ	VDD = 5V, VPIN = VSS

**Note 1:** In RC oscillator configuration, the OSC1/CLKI pin is a Schmitt Trigger input. It is not recommended that the PICmicro device be driven with an external clock while in RC mode.

- **3:** Negative current is defined as current sourced by the pin.
- 4: Parameter is characterized but not tested.

<sup>2:</sup> The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

# 22.2 DC Characteristics: PIC18FXX2 (Industrial, Extended) PIC18LFXX2 (Industrial) (Continued)

DC CHA	RACTER	RISTICS	Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended					
Param No.	Symbol	Characteristic	Min	Max	Units	Conditions		
	Vol	Output Low Voltage						
D080		I/O ports	_	0.6	V	IOL = 8.5 mA, VDD = 4.5V, -40°C to +85°C		
D080A			_	0.6	V	IOL = 7.0 mA, VDD = 4.5V, -40°C to +125°C		
D083		OSC2/CLKO (RC mode)	_	0.6	V	IOL = 1.6 mA, VDD = 4.5V, -40°C to +85°C		
D083A			_	0.6	V	IOL = 1.2 mA, VDD = 4.5V, -40°C to +125°C		
	Vон	Output High Voltage <sup>(3)</sup>						
D090		I/O ports	VDD - 0.7	_	V	IOH = -3.0 mA, VDD = 4.5V, -40°C to +85°C		
D090A			VDD - 0.7	_	V	IOH = -2.5 mA, VDD = 4.5V, -40°C to +125°C		
D092		OSC2/CLKO (RC mode)	VDD - 0.7	_	V	IOH = -1.3 mA, VDD = 4.5V, -40°C to +85°C		
D092A			VDD - 0.7	_	V	IOH = -1.0 mA, VDD = 4.5V, -40°C to +125°C		
D150	Vod	Open Drain High Voltage	_	8.5	V	RA4 pin		
		Capacitive Loading Specs on Output Pins						
D100 <sup>(4)</sup>	Cosc2	OSC2 pin	_	15	pF	In XT, HS and LP modes when external clock is used to drive OSC1		
D101	Cio	All I/O pins and OSC2 (in RC mode)	_	50	pF	To meet the AC Timing Specifications		
D102	Св	SCL, SDA	_	400	pF	In I <sup>2</sup> C mode		

**Note 1:** In RC oscillator configuration, the OSC1/CLKI pin is a Schmitt Trigger input. It is not recommended that the PICmicro device be driven with an external clock while in RC mode.

<sup>2:</sup> The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

<sup>3:</sup> Negative current is defined as current sourced by the pin.

<sup>4:</sup> Parameter is characterized but not tested.

FIGURE 22-3: LOW VOLTAGE DETECT CHARACTERISTICS




TABLE 22-1: LOW VOLTAGE DETECT CHARACTERISTICS

				Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for extended								
Param No.	Symbol	Character	istic	Min	Тур	Max	Units	Conditions				
D420	VLVD	_	LVV = 0001	1.98	2.06	2.14	V	T ≥ 25°C				
		transition high to	LVV = 0010	2.18	2.27	2.36	V	T ≥ 25°C				
		low	LVV = 0011	2.37	2.47	2.57	V	T ≥ 25°C				
			LVV = 0100	2.48	2.58	2.68	V					
			LVV = 0101	2.67	2.78	2.89	V					
			LVV = 0110	2.77	2.89	3.01	V					
			LVV = 0111	2.98	3.1	3.22	V					
			LVV = 1000	3.27	3.41	3.55	V					
			LVV = 1001	3.47	3.61	3.75	V					
			LVV = 1010	3.57	3.72	3.87	V					
			LVV = 1011	3.76	3.92	4.08	V					
			LVV = 1100	3.96	4.13	4.3	V					
			LVV = 1101	4.16	4.33	4.5	V					
			LVV = 1110	4.45	4.64	4.83	V					

TABLE 22-2: MEMORY PROGRAMMING REQUIREMENTS

DC Cha	racteris	stics			ture -40°	C ≤ Ta	unless otherwise stated) ≤ +85°C for industrial ≤ +125°C for extended
Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
		Internal Program Memory Programming Specifications					
D110	VPP	Voltage on MCLR/VPP pin	9.00	_	13.25	V	
D113	IDDP	Supply Current during Programming	_	_	10	mA	
		Data EEPROM Memory					
D120	ED	Cell Endurance	100K	1M	_	E/W	-40°C to +85°C
D121	VDRW	VDD for Read/Write	VMIN	_	5.5	V	Using EECON to read/write VMIN = Minimum operating voltage
D122	TDEW	Erase/Write Cycle Time	_	4	_	ms	
D123	TRETD	Characteristic Retention	40	_	_	Year	Provided no other specifications are violated
D124	TREF	Number of Total Erase/Write Cycles before Refresh <sup>(1)</sup>	1M	10M	_	E/W	-40°C to +85°C
		Program FLASH Memory					
D130	EР	Cell Endurance	10K	100K	_	E/W	-40°C to +85°C
D131	VPR	VDD for Read	VMIN	_	5.5	V	VMIN = Minimum operating voltage
D132	VIE	VDD for Block Erase	4.5	_	5.5	V	Using ICSP port
D132A	Viw	VDD for Externally Timed Erase or Write	4.5	_	5.5	V	Using ICSP port
D132B	VPEW	VDD for Self-timed Write	VMIN	_	5.5	V	VMIN = Minimum operating voltage
D133	TIE	ICSP Block Erase Cycle Time	_	4	_	ms	VDD ≥ 4.5V
D133A	Tıw	ICSP Erase or Write Cycle Time (externally timed)	1	_	_	ms	VDD ≥ 4.5V
D133A	Tıw	Self-timed Write Cycle Time	_	2	_	ms	
D134	TRETD	Characteristic Retention	40	_	_	Year	Provided no other specifications are violated

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: Refer to Section 6.8 for a more detailed discussion on data EEPROM endurance.

### 22.3 AC (Timing) Characteristics

### 22.3.1 TIMING PARAMETER SYMBOLOGY

The timing parameter symbols have been created following one of the following formats:

1. TppS2ppS	:	3. Tcc:st	(I <sup>2</sup> C specifications only)
2. TppS		4. Ts	(I <sup>2</sup> C specifications only)
Т			
F	Frequency	Т	Time
Lowercase le	etters (pp) and their meanings:		
рр			
cc	CCP1	osc	OSC1
ck	CLKO	rd	RD
cs	CS	rw	RD or WR
di	SDI	sc	SCK
do	SDO	ss	SS
dt	Data in	t0	T0CKI
io	I/O port	t1	T1CKI
mc	MCLR	wr	WR
Uppercase le	etters and their meanings:		
S			
F	Fall	Р	Period
Н	High	R	Rise
1	Invalid (Hi-impedance)	V	Valid
L	Low	Z	Hi-impedance
I <sup>2</sup> C only			
AA	output access	High	High
BUF	Bus free	Low	Low
TCC:ST (I <sup>2</sup> C s	pecifications only)		
CC			
HD	Hold	SU	Setup
ST			
DAT	DATA input hold	STO	STOP condition
STA	START condition		

### 22.3.2 TIMING CONDITIONS

The temperature and voltages specified in Table 22-3 apply to all timing specifications unless otherwise noted. Figure 22-4 specifies the load conditions for the timing specifications.

### TABLE 22-3: TEMPERATURE AND VOLTAGE SPECIFICATIONS - AC


Standard Operating Conditions (unless otherwise stated)

Operating temperature -40°C ≤ TA ≤ +85°C for industrial
-40°C ≤ TA ≤ +125°C for extended

Operating voltage VDD range as described in DC spec Section 22.1 and Section 22.2.


LC parts operate for industrial temperatures only.

#### FIGURE 22-4: LOAD CONDITIONS FOR DEVICE TIMING SPECIFICATIONS



#### 22.3.3 TIMING DIAGRAMS AND SPECIFICATIONS

FIGURE 22-5: EXTERNAL CLOCK TIMING (ALL MODES EXCEPT PLL)



**TABLE 22-4: EXTERNAL CLOCK TIMING REQUIREMENTS** 

Param. No.	Symbol	Characteristic	Min	Max	Units	Conditions
1A	Fosc	External CLKI Frequency <sup>(1)</sup>	DC	40	MHz	EC, ECIO, -40°C to +85°C
		Oscillator Frequency <sup>(1)</sup>	DC	25	MHz	EC, ECIO, +85°C to +125°C
			DC	4	MHz	RC osc
			0.1	4	MHz	XT osc
			4	25	MHz	HS osc
			4	10	MHz	HS + PLL osc, -40°C to +85°C
			4	6.25	MHz	HS + PLL osc, +85°C to +125°C
			5	200	kHz	LP Osc mode
1	Tosc	External CLKI Period <sup>(1)</sup>	25	_	ns	EC, ECIO, -40°C to +85°C
		Oscillator Period <sup>(1)</sup>	40	_	ns	EC, ECIO, +85°C to +125°C
			250	_	ns	RC osc
			250	10,000	ns	XT osc
			40	250	ns	HS osc
			100	250	ns	HS + PLL osc, -40°C to +85°C
			160	250	ns	HS + PLL osc, +85°C to +125°C
			25	_	μs	LP osc
2	TCY	Instruction Cycle Time <sup>(1)</sup>	100		ns	Tcy = $4/F$ osc, $-40$ °C to $+85$ °C
			160	_	ns	Tcy = 4/Fosc, +85°C to +125°C
3	TosL,	External Clock in (OSC1)	30	_	ns	XT osc
	TosH	High or Low Time	2.5	_	μs	LP osc
			10	_	ns	HS osc
4	TosR,	External Clock in (OSC1)	_	20	ns	XT osc
	TosF	Rise or Fall Time	_	50	ns	LP osc
			_	7.5	ns	HS osc

Note 1: Instruction cycle period (TCY) equals four times the input oscillator time-base period for all configurations except PLL. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min." values with an external clock applied to the OSC1/CLKI pin. When an external clock input is used, the "max." cycle time limit is "DC" (no clock) for all devices.

TABLE 22-5: PLL CLOCK TIMING SPECIFICATIONS (VDD = 4.2 TO 5.5V)

Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
_	Fosc	Oscillator Frequency Range	4	_	10	MHz	HS mode only
_	Fsys	On-chip VCO System Frequency	16	_	40	MHz	HS mode only
_	t <sub>rc</sub>	PLL Start-up Time (Lock Time)	_	_	2	ms	
_	ΔCLK	CLKO Stability (Jitter)	-2	_	+2	%	

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.







TABLE 22-6: CLKO AND I/O TIMING REQUIREMENTS

Param. No.	Symbol	Characteristic	<b>;</b>	Min	Тур	Max	Units	Conditions
10	TosH2ckL	OSC1↑to CLKO↓		_	75	200	ns	(Note 1)
11	TosH2ckH	OSC1↑to CLKO↑	_	75	200	ns	(Note 1)	
12	TckR	CLKO rise time		_	35	100	ns	(Note 1)
13	TckF	CLKO fall time			35	100	ns	(Note 1)
14	TckL2ioV	CLKO↓ to Port out valid		_	_	0.5 Tcy + 20	ns	(Note 1)
15	TioV2ckH	Port in valid before CLKO ↑		0.25 Tcy + 25	_	_	ns	(Note 1)
16	TckH2ioI	Port in hold after CLKO ↑		0	_	_	ns	(Note 1)
17	TosH2ioV	OSC1↑ (Q1 cycle) to Port ou	ıt valid	_	50	150	ns	
18	TosH2ioI	OSC1↑ (Q2 cycle) to Port	PIC18FXXX	100	_	_	ns	
18A		input invalid (I/O in hold time)	PIC18 <b>LF</b> XXX	200	_	_	ns	
19	TioV2osH	Port input valid to OSC1 <sup>1</sup> (I/C	in setup time)	0	_	_	ns	
20	TioR	Port output rise time	PIC18FXXX	_	10	25	ns	
20A			PIC18 <b>LF</b> XXX	_	_	60	ns	VDD = 2V
21	TioF	Port output fall time	PIC18FXXX		10	25	ns	
21A			PIC18 <b>LF</b> XXX		_	60	ns	VDD = 2V
22††	TINP	INT pin high or low time		Tcy	_	_	ns	
23††	TRBP	RB7:RB4 change INT high or low time		Tcy			ns	
24††	TRCP	RC7:RC4 change INT high of	or low time	20			ns	

<sup>††</sup> These parameters are asynchronous events not related to any internal clock edges.

Note 1: Measurements are taken in RC mode, where CLKO output is 4 x Tosc.

FIGURE 22-7: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER TIMING



### FIGURE 22-8: BROWN-OUT RESET TIMING




TABLE 22-7: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER, POWER-UP TIMER AND BROWN-OUT RESET REQUIREMENTS

Param. No.	Symbol	Characteristic	Min	Тур	Max	Units	Conditions
30	TmcL	MCLR Pulse Width (low)	2	_	_	μs	
31	TWDT	Watchdog Timer Time-out Period (No Postscaler)	7	18	33	ms	
32	Tost	Oscillation Start-up Timer Period	1024 Tosc	_	1024 Tosc	_	Tosc = OSC1 period
33	TPWRT	Power up Timer Period	28	72	132	ms	
34	Tıoz	I/O Hi-impedance from MCLR Low or Watchdog Timer Reset	_	2	_	μs	
35	TBOR	Brown-out Reset Pulse Width	200	_	_	μs	V <sub>DD</sub> ≤ B <sub>VDD</sub> (see D005)
36	Tivrst	Time for Internal Reference Voltage to become stable	_	20	500	μs	
37	TLVD	Low Voltage Detect Pulse Width	200	_	_	μs	V <sub>DD</sub> ≤ V <sub>L</sub> VD (see D420)

T0CKI T1OSO/T1CKI 48 TMR0 or TMR1 Refer to Figure 22-4 for load conditions. Note:

**FIGURE 22-9: TIMERO AND TIMER1 EXTERNAL CLOCK TIMINGS** 

**TABLE 22-8: TIMERO AND TIMER1 EXTERNAL CLOCK REQUIREMENTS** 

Param No.	Symbol		Characteristic		Min	Max	Units	Conditions
40	Tt0H	T0CKI High Po	ulse Width	No Prescaler	0.5Tcy + 20	_	ns	
				With Prescaler	10	_	ns	
41	Tt0L	T0CKI Low Pu	lse Width	No Prescaler	0.5Tcy + 20	_	ns	
				With Prescaler	10	_	ns	
42	Tt0P	T0CKI Period		No Prescaler	Tcy + 10	_	ns	
				With Prescaler	Greater of: 20 ns or <u>TCY + 40</u> N	_	ns	N = prescale value (1, 2, 4,, 256)
45	Tt1H	T1CKI High	Synchronous, no	prescaler	0.5Tcy + 20	_	ns	
		Time	Synchronous,	PIC18FXXX	10	_	ns	
			with prescaler	PIC18LFXXX	25	_	ns	
			Asynchronous	PIC18FXXX	30	_	ns	
				PIC18 <b>LF</b> XXX	50	_	ns	
46	Tt1L	T1CKI Low	Synchronous, no	prescaler	0.5Tcy + 5	_	ns	
		Time	Synchronous,	PIC18FXXX	10	_	ns	
			with prescaler	PIC18 <b>LF</b> XXX	25	_	ns	
			Asynchronous	PIC18FXXX	30	_	ns	
				PIC18 <b>LF</b> XXX	50	_	ns	
47	Tt1P	T1CKI input period	Synchronous		Greater of: 20 ns or <u>TcY + 40</u> N	_	ns	N = prescale value (1, 2, 4, 8)
			Asynchronous		60	_	ns	
	Ft1	T1CKI oscillate	or input frequency r	ange	DC	50	kHz	
48	Tcke2tmrl	Delay from extincrement	ternal T1CKI clock	edge to timer	2 Tosc	7 Tosc	_	

FIGURE 22-10: CAPTURE/COMPARE/PWM TIMINGS (CCP1 AND CCP2)





TABLE 22-9: CAPTURE/COMPARE/PWM REQUIREMENTS (CCP1 AND CCP2)

Param. No.	Symbol	CI	naracteristi	c	Min	Max	Units	Conditions
50	TccL	CCPx input low No Prescal		er	0.5 Tcy + 20	_	ns	
	time	time	With	PIC18FXXX	10	_	ns	
			Prescaler	PIC18 <b>LF</b> XXX	20	_	ns	
51	TccH	CCPx input	CCPx input No Prescale		0.5 Tcy + 20	_	ns	
		high time	With	PIC18FXXX	10	_	ns	
			Prescaler	PIC18 <b>LF</b> XXX	20	_	ns	
52	TccP	CCPx input perio	od		3 Tcy + 40 N	_	ns	N = prescale value (1,4 or 16)
53	TccR	CCPx output fall	time	PIC18FXXX	_	25	ns	
			Ī		_	60	ns	VDD = 2V
54	TccF	CCPx output fall	time	PIC18FXXX		25	ns	
				PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V



**PARALLEL SLAVE PORT TIMING (PIC18F4X2)** FIGURE 22-11:

TABLE 22-10: PARALLEL SLAVE PORT REQUIREMENTS (PIC18F4X2)

Param. No.	Symbol	Characteristic		Min	Max	Units	Conditions
62	TdtV2wrH	Data in valid before WR↑ or CS↑		20	_	ns	- · · · ·
		setup time)		25	_	ns	Extended Temp. Range
63	TwrH2dtl	WR↑ or CS↑ to data–in invalid	PIC18FXXX	20	_	ns	
		(hold time)	PIC18LFXXX	35	_	ns	VDD = 2V
64	TrdL2dtV	RD↓ and CS↓ to data-out valid		_	80	ns	
				—	90	ns	Extended Temp. Range
65	TrdH2dtI	RD↑ or CS↓ to data–out invalid		10	30	ns	
66	TibfINH	Inhibit of the IBF flag bit being c WR↑ or CS↑	leared from	_	3 Tcy		




FIGURE 22-12: EXAMPLE SPI MASTER MODE TIMING (CKE = 0)

TABLE 22-11: EXAMPLE SPI MODE REQUIREMENTS (MASTER MODE, CKE = 0)

Param. No.	Symbol	Characteristic		Min	Max	Units	Conditions
70	TssL2scH, TssL2scL	SS↓ to SCK↓ or SCK↑ input		Tcy	_	ns	
71	TscH	SCK input high time	Continuous	1.25 Tcy + 30	_	ns	
71A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
72	TscL	SCK input low time	Continuous	1.25 Tcy + 30	_	ns	
72A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
73	TdiV2scH, TdiV2scL	Setup time of SDI data input to SC	K edge	100		ns	
73A	Тв2в	Last clock edge of Byte1 to the 1st c	lock edge of Byte2	1.5 Tcy + 40	_	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold time of SDI data input to SCK	edge	100	_	ns	
75	TdoR	SDO data output rise time	PIC18FXXX	_	25	ns	
			PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
76	TdoF	SDO data output fall time	PIC18FXXX	_	25	ns	
			PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
78	TscR	SCK output rise time	PIC18FXXX	_	25	ns	
		(Master mode)	PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
79	TscF	SCK output fall time (Master mode)	PIC18FXXX	_	25	ns	
			PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
80		SDO data output valid after SCK	PIC18FXXX	_	50	ns	
	TscL2doV	edge	PIC18 <b>LF</b> XXX	_	150	ns	VDD = 2V




FIGURE 22-13: EXAMPLE SPI MASTER MODE TIMING (CKE = 1)

TABLE 22-12: EXAMPLE SPI MODE REQUIREMENTS (MASTER MODE, CKE = 1)

Param. No.	Symbol	Characteristic		Min	Max	Units	Conditions
71	TscH	SCK input high time	Continuous	1.25 Tcy + 30	_	ns	
71A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
72	TscL	SCK input low time	Continuous	1.25 Tcy + 30	_	ns	
72A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
73	TdiV2scH, TdiV2scL	Setup time of SDI data input to SCK	edge	100	_	ns	
73A	Тв2в	Last clock edge of Byte1 to the 1st clo	ock edge of Byte2	1.5 Tcy + 40	_	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold time of SDI data input to SCK of	100	_	ns		
75	TdoR	SDO data output rise time	PIC18FXXX	_	25	ns	
			PIC18LFXXX	_	60	ns	VDD = 2V
76	TdoF	SDO data output fall time	PIC18FXXX	_	25	ns	
			PIC18LFXXX	_	60	ns	VDD = 2V
78	TscR	SCK output rise time (Master mode)	PIC18FXXX	_	25	ns	
			PIC18LFXXX	_	60	ns	VDD = 2V
79	TscF	SCK output fall time (Master mode)	PIC18FXXX	_	25	ns	
			PIC18LFXXX	_	60	ns	VDD = 2V
80	TscH2doV, SDO data output valid after SCK edge		PIC18FXXX	_	50	ns	
			PIC18LFXXX	_	150	ns	VDD = 2V
81	TdoV2scH, TdoV2scL	SDO data output setup to SCK edge	•	Tcy	_	ns	




FIGURE 22-14: EXAMPLE SPI SLAVE MODE TIMING (CKE = 0)

TABLE 22-13: EXAMPLE SPI MODE REQUIREMENTS (SLAVE MODE TIMING (CKE = 0))

Param. No.	Symbol	Characteristic	Characteristic		Max	Units	Conditions
70	TssL2scH, TssL2scL	SS↓ to SCK↓ or SCK↑ input		Tcy	_	ns	
71	TscH	SCK input high time (Slave mode)	Continuous	1.25 TcY + 30	_	ns	
71A			Single Byte	40	_	ns	(Note 1)
72	TscL	SCK input low time (Slave mode)	Continuous	1.25 Tcy + 30	_	ns	
72A			Single Byte	40	_	ns	(Note 1)
73	TdiV2scH, TdiV2scL	Setup time of SDI data input to SCK ed	lge	100	_	ns	
73A	Тв2в	Last clock edge of Byte1 to the first clock	edge of Byte2	1.5 Tcy + 40	_	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold time of SDI data input to SCK edge		100	_	ns	
75	TdoR	SDO data output rise time	PIC18FXXX	_	25	ns	
			PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
76	TdoF	SDO data output fall time	PIC18FXXX	_	25	ns	
			PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
77	TssH2doZ	SS↑ to SDO output hi-impedance		10	50	ns	
78	TscR	SCK output rise time (Master mode)	PIC18FXXX	_	25	ns	
			PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
79	TscF	SCK output fall time (Master mode)	PIC18FXXX	_	25	ns	
			PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
80	TscH2doV,	SDO data output valid after SCK edge	PIC18FXXX	_	50	ns	
	TscL2doV		PIC18 <b>LF</b> XXX	_	150	ns	VDD = 2V
83	TscH2ssH, TscL2ssH	S ↑ after SCK edge		1.5 Tcy + 40	_	ns	




FIGURE 22-15: EXAMPLE SPI SLAVE MODE TIMING (CKE = 1)

TABLE 22-14: EXAMPLE SPI SLAVE MODE REQUIREMENTS (CKE = 1)

Param. No.	Symbol	Characteristic		Min	Max	Units	Conditions
70	TssL2scH, TssL2scL	SS↓ to SCK↓ or SCK↑ input		Tcy	_	ns	
71	TscH	SCK input high time	Continuous	1.25 Tcy + 30	_	ns	
71A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
72	TscL	SCK input low time	Continuous	1.25 TcY + 30	_	ns	
72A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
73A	Тв2в	Last clock edge of Byte1 to the first cloc	k edge of Byte2	1.5 Tcy + 40	_	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold time of SDI data input to SCK ed	100	_	ns		
75	TdoR SDO data output rise time		PIC18FXXX	_	25	ns	
			PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
76	TdoF	doF SDO data output fall time	PIC18FXXX	_	25	ns	
			PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
77	TssH2doZ	SS↑ to SDO output hi-impedance		10	50	ns	
78	TscR	SCK output rise time (Master mode)	PIC18FXXX	_	25	ns	
			PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
79	TscF	SCK output fall time (Master mode)	PIC18FXXX	_	25	ns	
			PIC18 <b>LF</b> XXX	_	60	ns	VDD = 2V
80	TscH2doV,	SDO data output valid after SCK	PIC18FXXX	_	50	ns	
	TscL2doV	edge	PIC18 <b>LF</b> XXX	_	150	ns	VDD = 2V
82	TssL2doV	SDO data output valid after SS↓ edge	PIC18FXXX	_	50	ns	
			PIC18 <b>LF</b> XXX	_	150	ns	VDD = 2V
83	TscH2ssH, TscL2ssH	SS ↑ after SCK edge		1.5 TcY + 40	_	ns	

FIGURE 22-16: I<sup>2</sup>C BUS START/STOP BITS TIMING





TABLE 22-15: I<sup>2</sup>C BUS START/STOP BITS REQUIREMENTS (SLAVE MODE)

Param. No.	Symbol	Characte	eristic	Min	Max	Units	Conditions
90	Tsu:sta	START condition	100 kHz mode	4700	_	ns	Only relevant for Repeated
		Setup time	400 kHz mode	600	_		START condition
91	THD:STA	START condition	100 kHz mode	4000	_	ns	After this period, the first
		Hold time	400 kHz mode	600	_		clock pulse is generated
92	Tsu:sto	STOP condition	100 kHz mode	4700	_	ns	
		Setup time	400 kHz mode	600	_		
93	THD:STO	STOP condition	100 kHz mode	4000	_	ns	
		Hold time	400 kHz mode	600	_		

FIGURE 22-17: I<sup>2</sup>C BUS DATA TIMING



### TABLE 22-16: I<sup>2</sup>C BUS DATA REQUIREMENTS (SLAVE MODE)

Param. No.	Symbol	Characte	eristic	Min	Max	Units	Conditions
100	THIGH	Clock high time	100 kHz mode	4.0	_	μѕ	PIC18FXXX must operate at a minimum of 1.5 MHz
			400 kHz mode	0.6	_	μs	PIC18FXXX must operate at a minimum of 10 MHz
			SSP Module	1.5 TcY	_		
101	TLOW	Clock low time	100 kHz mode	4.7	_	μs	PIC18FXXX must operate at a minimum of 1.5 MHz
			400 kHz mode	1.3	_	μѕ	PIC18FXXX must operate at a minimum of 10 MHz
			SSP Module	1.5 TcY	_		
102	TR	SDA and SCL rise	100 kHz mode	_	1000	ns	
		time	400 kHz mode	20 + 0.1 CB	300	ns	CB is specified to be from 10 to 400 pF
103	TF	SDA and SCL fall	100 kHz mode	_	1000	ns	VDD ≥ 4.2V
		time	400 kHz mode	20 + 0.1 CB	300	ns	VDD ≥ 4.2V
90	Tsu:sta	START condition	100 kHz mode	4.7	_	μs	Only relevant for Repeated
		setup time	400 kHz mode	0.6	_	μs	START condition
91	THD:STA	START condition hold	100 kHz mode	4.0	_	μs	After this period, the first clock
		time	400 kHz mode	0.6		μs	pulse is generated
106	THD:DAT	Data input hold time	100 kHz mode	0	_	ns	
			400 kHz mode	0	0.9	μs	
107	TSU:DAT	Data input setup time	100 kHz mode	250	_	ns	(Note 2)
			400 kHz mode	100	_	ns	
92	Tsu:sto	STOP condition	100 kHz mode	4.7	_	μs	
		setup time	400 kHz mode	0.6	_	μs	
109	TAA	Output valid from	100 kHz mode	_	3500	ns	(Note 1)
		clock	400 kHz mode	_	_	ns	
110	TBUF	Bus free time	100 kHz mode	4.7	_	μs	Time the bus must be free
			400 kHz mode	1.3	_	μs	before a new transmission can start
D102	Св	Bus capacitive loading		-	400	pF	

Note 1: As a transmitter, the device must provide this internal minimum delay time to bridge the undefined region (min. 300 ns) of the falling edge of SCL to avoid unintended generation of START or STOP conditions.

<sup>2:</sup> A Fast mode I<sup>2</sup>C bus device can be used in a Standard mode I<sup>2</sup>C bus system, but the requirement Tsu:DAT ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the LOW period of the SCL signal. If such a device does stretch the LOW period of the SCL signal, it must output the next data bit to the SDA line.

TR max. + Tsu:DAT = 1000 + 250 = 1250 ns (according to the Standard mode I<sup>2</sup>C bus specification) before the SCL line is released.

FIGURE 22-18: MASTER SSP I<sup>2</sup>C BUS START/STOP BITS TIMING WAVEFORMS




TABLE 22-17: MASTER SSP I<sup>2</sup>C BUS START/STOP BITS REQUIREMENTS

Param. No.	Symbol	Characte	ristic	Min	Max	Units	Conditions
90	Tsu:sta	START condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ns	Only relevant for
		Setup time	400 kHz mode	2(Tosc)(BRG + 1)	_		Repeated START
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_		condition
91	THD:STA	START condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ns	After this period, the
		Hold time	400 kHz mode	2(Tosc)(BRG + 1)	_		first clock pulse is
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_		generated
92	Tsu:sto	STOP condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ns	
		Setup time	400 kHz mode	2(Tosc)(BRG + 1)	_		
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_		
93	THD:STO	STOP condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ns	
		Hold time	400 kHz mode	2(Tosc)(BRG + 1)	_		
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_		

**Note 1:** Maximum pin capacitance = 10 pF for all I<sup>2</sup>C pins.

FIGURE 22-19: MASTER SSP I<sup>2</sup>C BUS DATA TIMING





TABLE 22-18: MASTER SSP I<sup>2</sup>C BUS DATA REQUIREMENTS

Param. No.	Symbol	Charac	teristic	Min	Max	Units	Conditions
100	THIGH	Clock high time	100 kHz mode	2(Tosc)(BRG + 1)	_	ms	
			400 kHz mode	2(Tosc)(BRG + 1)	_	ms	
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	ms	
101	TLOW	Clock low time	100 kHz mode	2(Tosc)(BRG + 1)	_	ms	
			400 kHz mode	2(Tosc)(BRG + 1)	_	ms	
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	ms	
102	TR	SDA and SCL	100 kHz mode	_	1000	ns	CB is specified to be from
		rise time	400 kHz mode	20 + 0.1 CB	300	ns	10 to 400 pF
			1 MHz mode <sup>(1)</sup>	_	300	ns	
103	TF	SDA and SCL	100 kHz mode	_	1000	ns	VDD ≥ 4.2V
		fall time	400 kHz mode	20 + 0.1 CB	300	ns	VDD ≥ 4.2V
90	TSU:STA	START condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ms	Only relevant for
		setup time	400 kHz mode	2(Tosc)(BRG + 1)	_	ms	Repeated START
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	ms	condition
91	THD:STA	START condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ms	After this period, the first
		hold time	400 kHz mode	2(Tosc)(BRG + 1)	_	ms	clock pulse is generated
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	ms	
106	THD:DAT	Data input	100 kHz mode	0	_	ns	
		hold time	400 kHz mode	0	0.9	ms	
107	TSU:DAT	Data input	100 kHz mode	250	_	ns	(Note 2)
		setup time	400 kHz mode	100	_	ns	
92	Tsu:sto	STOP condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ms	
		setup time	400 kHz mode	2(Tosc)(BRG + 1)	_	ms	
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	ms	
109	TAA	Output valid from	100 kHz mode	_	3500	ns	
		clock	400 kHz mode	_	1000	ns	
			1 MHz mode <sup>(1)</sup>	_	_	ns	
110	TBUF	Bus free time	100 kHz mode	4.7		ms	Time the bus must be free
			400 kHz mode	1.3	_	ms	before a new transmission can start
D102	Св	Bus capacitive loa	ading	_	400	pF	

**Note 1:** Maximum pin capacitance = 10 pF for all  $I^2\text{C}$  pins.

<sup>2:</sup> A Fast mode I<sup>2</sup>C bus device can be used in a Standard mode I<sup>2</sup>C bus system, but parameter #107 ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the LOW period of the SCL signal. If such a device does stretch the LOW period of the SCL signal, it must output the next data bit to the SDA line, parameter #102 + parameter #107 = 1000 + 250 = 1250 ns (for 100 kHz mode) before the SCL line is released.


### FIGURE 22-20: USART SYNCHRONOUS TRANSMISSION (MASTER/SLAVE) TIMING



### TABLE 22-19: USART SYNCHRONOUS TRANSMISSION REQUIREMENTS

Param. No.	Symbol	Characteristic		Min	Max	Units	Conditions
120	TckH2dtV	SYNC XMIT (MASTER & SLAVE)					
		Clock high to data out valid	PIC18FXXX		50	ns	
			PIC18 <b>LF</b> XXX		150	ns	VDD = 2V
121	Tckr	Clock out rise time and fall time	PIC18FXXX	_	25	ns	
		(Master mode)	PIC18 <b>LF</b> XXX		60	ns	VDD = 2V
122	Tdtr	Data out rise time and fall time	PIC18FXXX		25	ns	
			PIC18 <b>LF</b> XXX		60	ns	VDD = 2V

### FIGURE 22-21: USART SYNCHRONOUS RECEIVE (MASTER/SLAVE) TIMING



### TABLE 22-20: USART SYNCHRONOUS RECEIVE REQUIREMENTS

Param. No.	Symbol	Characteristic			Max	Units	Conditions
125	TdtV2ckl	SYNC RCV (MASTER & SLAVE)  Data hold before CK ↓ (DT hold time)		10	_	ns	
126	TckL2dtl	Data hold after CK ↓ (DT hold time)	PIC18FXXX	15	_	ns	
			PIC18 <b>LF</b> XXX	20	_	ns	VDD = 2V


TABLE 22-21: A/D CONVERTER CHARACTERISTICS: PIC18FXX2 (INDUSTRIAL, EXTENDED) PIC18LFXX2 (INDUSTRIAL)

Param No.	Symbol	Characteristic	Min	Тур	Мах	Units	Conditions
A01	NR	Resolution	_	_	10	bit	
A03	EiL	Integral linearity error	_	_	<±1	LSb	VREF = VDD = 5.0V
A04	EDL	Differential linearity error	_	_	<±1	LSb	VREF = VDD = 5.0V
A05	Eg	Gain error	_	_	<±1	LSb	VREF = VDD = 5.0V
A06	Eoff	Offset error	_	_	<±1.5	LSb	VREF = VDD = 5.0V
A10	_	Monotonicity	gı	uaranteed	<sub>]</sub> (2)	_	VSS ≤ VAIN ≤ VREF
A20 A20A	VREF	Reference Voltage (VREFH – VREFL)	1.8V 3V	_	_	V V	VDD < 3.0V VDD ≥ 3.0V
A21	VREFH	Reference voltage High	AVss	_	AVDD + 0.3V	٧	
A22	VREFL	Reference voltage Low	AVss - 0.3V	_	VREFH	٧	
A25	VAIN	Analog input voltage	AVss - 0.3V	_	AVDD + 0.3V	٧	VDD ≥ 2.5V (Note 3)
A30	ZAIN	Recommended impedance of analog voltage source	_	_	2.5	kΩ	(Note 4)
A50	IREF	VREF input current (Note 1)	_	_	5	μΑ	During VAIN acquisition
			_	_	150	μA	During A/D conversion cycle

Note 1:  $Vss \le VAIN \le VREF$ 

- 2: The A/D conversion result never decreases with an increase in the Input Voltage, and has no missing codes.
- 3: For VDD < 2.5V, VAIN should be limited to < .5 VDD.
- 4: Maximum allowed impedance for analog voltage source is 10 kΩ. This requires higher acquisition times.

FIGURE 22-22: A/D CONVERSION TIMING



#### TABLE 22-22: A/D CONVERSION REQUIREMENTS

Param No.	Symbol	Characteristic		Min	Max	Units	Conditions
130	TAD	A/D clock period	PIC18FXXX	1.6	20 <sup>(4)</sup>	μs	Tosc based
			PIC18FXXX	2.0	6.0	μs	A/D RC mode
131	TCNV	Conversion time (not including acquisition time) (Note 1)		11	12	TAD	
132	TACQ	Acquisition time (Note 2)		5 10	_	μs μs	VREF = VDD = 5.0V VREF = VDD = 2.5V
135	Tswc	Switching Time from c	onvert $\rightarrow$ sample	_	(Note 3)		

Note 1: ADRES register may be read on the following TcY cycle.

- 2: The time for the holding capacitor to acquire the "New" input voltage, when the new input value has not changed by more than 1 LSB from the last sampled voltage. The source impedance (Rs) on the input channels is  $50\Omega$ . See Section 17.0 for more information on acquisition time consideration.
- 3: On the next Q4 cycle of the device clock.
- **4:** The time of the A/D clock period is dependent on the device frequency and the TAD clock divider.

#### 23.0 DC AND AC CHARACTERISTICS GRAPHS AND TABLES

**Note:** The graphs and tables provided following this note are a statistical summary based on a limited number of samples and are provided for informational purposes only. The performance characteristics listed herein are not tested or guaranteed. In some graphs or tables, the data presented may be outside the specified operating range (e.g., outside specified power supply range) and therefore, outside the warranted range.

"Typical" represents the mean of the distribution at 25°C. "Maximum" or "minimum" represents (mean +  $3\sigma$ ) or (mean -  $3\sigma$ ) respectively, where  $\sigma$  is a standard deviation, over the whole temperature range.

FIGURE 23-1: TYPICAL IDD vs. FOSC OVER VDD (HS MODE)




FIGURE 23-2: MAXIMUM IDD vs. Fosc OVER VDD (HS MODE)




FIGURE 23-3: TYPICAL IDD vs. FOSC OVER VDD (HS/PLL MODE)




FIGURE 23-4: MAXIMUM IDD vs. Fosc OVER VDD (HS/PLL MODE)




FIGURE 23-5: TYPICAL IDD vs. FOSC OVER VDD (XT MODE)




FIGURE 23-6: MAXIMUM IDD vs. Fosc OVER VDD (XT MODE)





FIGURE 23-7: TYPICAL IDD vs. Fosc OVER VDD (LP MODE)








FIGURE 23-9: TYPICAL IDD vs. Fosc OVER VDD (EC MODE)




FIGURE 23-10: MAXIMUM IDD vs. Fosc OVER VDD (EC MODE)




FIGURE 23-11: TYPICAL AND MAXIMUM IDD vs. VDD (TIMER1 AS MAIN OSCILLATOR, 32.768 kHz, C1 AND C2 = 47 pF)




FIGURE 23-12: AVERAGE FOSC vs. VDD FOR VARIOUS VALUES OF R (RC MODE,  $C = 20 \text{ pF}, +25^{\circ}\text{C}$ )




FIGURE 23-13: AVERAGE FOSC vs. VDD FOR VARIOUS VALUES OF R (RC MODE, C = 100 pF, +25°C)




FIGURE 23-14: AVERAGE FOSC vs. VDD FOR VARIOUS VALUES OF R (RC MODE, C = 300 pF, +25°C)




FIGURE 23-15: IPD vs. VDD, -40°C TO +125°C (SLEEP MODE, ALL PERIPHERALS DISABLED)




FIGURE 23-16:  $\triangle$ IBOR vs. VDD OVER TEMPERATURE (BOR ENABLED, VBOR = 2.00 - 2.16V)




FIGURE 23-17: TYPICAL AND MAXIMUM  $\triangle$ ITMR1 vs. VDD OVER TEMPERATURE (-10°C TO +70°C, TIMER1 WITH OSCILLATOR, XTAL = 32 kHz, C1 AND C2 = 47 pF)




FIGURE 23-18: TYPICAL AND MAXIMUM AIWDT vs. VDD OVER TEMPERATURE (WDT ENABLED)




FIGURE 23-19: TYPICAL, MINIMUM AND MAXIMUM WDT PERIOD vs. VDD (-40°C TO +125°C)




FIGURE 23-20:  $\triangle$ ILVD vs. VDD OVER TEMPERATURE (LVD ENABLED, VLVD = 4.5 - 4.78V)




FIGURE 23-21: TYPICAL, MINIMUM AND MAXIMUM VOH vs. IOH (VDD = 5V, -40°C TO +125°C)




FIGURE 23-22: TYPICAL, MINIMUM AND MAXIMUM VOH vs. IOH (VDD = 3V, -40°C TO +125°C)




FIGURE 23-23: TYPICAL AND MAXIMUM Vol vs. Iol (VDD = 5V, -40°C TO +125°C)




FIGURE 23-24: TYPICAL AND MAXIMUM Vol vs. Iol (VDD = 3V, -40°C TO +125°C)




FIGURE 23-25: MINIMUM AND MAXIMUM VIN vs. VDD (ST INPUT, -40°C TO +125°C)




FIGURE 23-26: MINIMUM AND MAXIMUM VIN vs. VDD (TTL INPUT, -40°C TO +125°C)




FIGURE 23-27: MINIMUM AND MAXIMUM VIN vs. VDD (I<sup>2</sup>C INPUT, -40°C TO +125°C)






FIGURE 23-28: A/D NON-LINEARITY vs. VREFH (VDD = VREFH, -40°C TO +125°C)





A/D NON-LINEARITY vs. VREFH (VDD = 5V, -40°C TO +125°C) FIGURE 23-29:

**NOTES:** 

#### 24.0 PACKAGING INFORMATION

#### 24.1 Package Marking Information

#### 28-Lead PDIP (Skinny DIP)



#### Example



#### 28-Lead SOIC



#### Example



Legend: XX...X Customer specific information\*

Y Year code (last digit of calendar year)
YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')

NNN Alphanumeric traceability code

**Note**: In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line thus limiting the number of available characters for customer specific information.

Standard PICmicro device marking consists of Microchip part number, year code, week code, and traceability code. For PICmicro device marking beyond this, certain price adders apply. Please check with your Microchip Sales Office. For QTP devices, any special marking adders are included in QTP price.

#### Package Marking Information (Cont'd)

#### 40-Lead PDIP



#### Example



#### 44-Lead TQFP



#### Example



#### 44-Lead PLCC




#### Example



#### 24.2 **Package Details**

The following sections give the technical details of the packages.

#### 28-Lead Skinny Plastic Dual In-line (SP) – 300 mil (PDIP)



	Units		INCHES*		M	IILLIMETERS	
Dimension	n Limits	MIN	NOM	MAX	MIN	NOM	MAX
Number of Pins	n		28			28	
Pitch	р		.100			2.54	
Top to Seating Plane	Α	.140	.150	.160	3.56	3.81	4.06
Molded Package Thickness	A2	.125	.130	.135	3.18	3.30	3.43
Base to Seating Plane	A1	.015			0.38		
Shoulder to Shoulder Width	E	.300	.310	.325	7.62	7.87	8.26
Molded Package Width	E1	.275	.285	.295	6.99	7.24	7.49
Overall Length	D	1.345	1.365	1.385	34.16	34.67	35.18
Tip to Seating Plane	L	.125	.130	.135	3.18	3.30	3.43
Lead Thickness	С	.008	.012	.015	0.20	0.29	0.38
Upper Lead Width	B1	.040	.053	.065	1.02	1.33	1.65
Lower Lead Width	В	.016	.019	.022	0.41	0.48	0.56
Overall Row Spacing §	eB	.320	.350	.430	8.13	8.89	10.92
Mold Draft Angle Top	α	5	10	15	5	10	15
Mold Draft Angle Bottom	β	5	10	15	5	10	15

Dimension D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.


JEDEC Equivalent: MO-095

Drawing No. C04-070

<sup>\*</sup> Controlling Parameter § Significant Characteristic

Notes:

### 28-Lead Plastic Small Outline (SO) - Wide, 300 mil (SOIC)



	Units		INCHES*		MILLIMETERS		
Dimension	Limits	MIN	NOM	MAX	MIN	NOM	MAX
Number of Pins	n		28			28	
Pitch	р		.050			1.27	
Overall Height	Α	.093	.099	.104	2.36	2.50	2.64
Molded Package Thickness	A2	.088	.091	.094	2.24	2.31	2.39
Standoff §	A1	.004	.008	.012	0.10	0.20	0.30
Overall Width	Е	.394	.407	.420	10.01	10.34	10.67
Molded Package Width	E1	.288	.295	.299	7.32	7.49	7.59
Overall Length	D	.695	.704	.712	17.65	17.87	18.08
Chamfer Distance	h	.010	.020	.029	0.25	0.50	0.74
Foot Length	L	.016	.033	.050	0.41	0.84	1.27
Foot Angle Top	ф	0	4	8	0	4	8
Lead Thickness	С	.009	.011	.013	0.23	0.28	0.33
Lead Width	В	.014	.017	.020	0.36	0.42	0.51
Mold Draft Angle Top	α	0	12	15	0	12	15
Mold Draft Angle Bottom	β	0	12	15	0	12	15


Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed

.010" (0.254mm) per side. JEDEC Equivalent: MS-013

Drawing No. C04-052

<sup>\*</sup> Controlling Parameter § Significant Characteristic

#### 40-Lead Plastic Dual In-line (P) - 600 mil (PDIP)



	Units		INCHES*		N	3	
Dimens	on Limits	MIN	NOM	MAX	MIN	NOM	MAX
Number of Pins	n		40			40	
Pitch	р		.100			2.54	
Top to Seating Plane	Α	.160	.175	.190	4.06	4.45	4.83
Molded Package Thickness	A2	.140	.150	.160	3.56	3.81	4.06
Base to Seating Plane	A1	.015			0.38		
Shoulder to Shoulder Width	E	.595	.600	.625	15.11	15.24	15.88
Molded Package Width	E1	.530	.545	.560	13.46	13.84	14.22
Overall Length	D	2.045	2.058	2.065	51.94	52.26	52.45
Tip to Seating Plane	L	.120	.130	.135	3.05	3.30	3.43
Lead Thickness	С	.008	.012	.015	0.20	0.29	0.38
Upper Lead Width	B1	.030	.050	.070	0.76	1.27	1.78
Lower Lead Width	В	.014	.018	.022	0.36	0.46	0.56
Overall Row Spacing §	eB	.620	.650	.680	15.75	16.51	17.27
Mold Draft Angle Top	α	5	10	15	5	10	15
Mold Draft Angle Bottom	β	5	10	15	5	10	15

Notes:


Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed

.010" (0.254mm) per side. JEDEC Equivalent: MO-011

Drawing No. C04-016

<sup>\*</sup> Controlling Parameter § Significant Characteristic

### 44-Lead Plastic Thin Quad Flatpack (PT) 10x10x1 mm Body, 1.0/0.10 mm Lead Form (TQFP)




	Units	INCHES		MILLIMETERS*		*	
Dimension Limits		MIN	NOM	MAX	MIN	NOM	MAX
Number of Pins	n		44			44	
Pitch	р		.031			0.80	
Pins per Side	n1		11			11	
Overall Height	Α	.039	.043	.047	1.00	1.10	1.20
Molded Package Thickness	A2	.037	.039	.041	0.95	1.00	1.05
Standoff §	A1	.002	.004	.006	0.05	0.10	0.15
Foot Length	L	.018	.024	.030	0.45	0.60	0.75
Footprint (Reference)	(F)		.039		1.00		
Foot Angle	ф	0	3.5	7	0	3.5	7
Overall Width	Е	.463	.472	.482	11.75	12.00	12.25
Overall Length	D	.463	.472	.482	11.75	12.00	12.25
Molded Package Width	E1	.390	.394	.398	9.90	10.00	10.10
Molded Package Length	D1	.390	.394	.398	9.90	10.00	10.10
Lead Thickness	С	.004	.006	.008	0.09	0.15	0.20
Lead Width	В	.012	.015	.017	0.30	0.38	0.44
Pin 1 Corner Chamfer	CH	.025	.035	.045	0.64	0.89	1.14
Mold Draft Angle Top	α	5	10	15	5	10	15
Mold Draft Angle Bottom	β	5	10	15	5	10	15

Dimensions D1 and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed

.010" (0.254mm) per side. JEDEC Equivalent: MS-026 Drawing No. C04-076

<sup>\*</sup> Controlling Parameter § Significant Characteristic

### 44-Lead Plastic Leaded Chip Carrier (L) – Square (PLCC)



Units		INCHES*			MILLIMETERS		
Dimension Limits		MIN	NOM	MAX	MIN	NOM	MAX
Number of Pins	n		44			44	
Pitch	р		.050			1.27	
Pins per Side	n1		11			11	
Overall Height	Α	.165	.173	.180	4.19	4.39	4.57
Molded Package Thickness	A2	.145	.153	.160	3.68	3.87	4.06
Standoff §	A1	.020	.028	.035	0.51	0.71	0.89
Side 1 Chamfer Height	A3	.024	.029	.034	0.61	0.74	0.86
Corner Chamfer 1	CH1	.040	.045	.050	1.02	1.14	1.27
Corner Chamfer (others)	CH2	.000	.005	.010	0.00	0.13	0.25
Overall Width	E	.685	.690	.695	17.40	17.53	17.65
Overall Length	D	.685	.690	.695	17.40	17.53	17.65
Molded Package Width	E1	.650	.653	.656	16.51	16.59	16.66
Molded Package Length	D1	.650	.653	.656	16.51	16.59	16.66
Footprint Width	E2	.590	.620	.630	14.99	15.75	16.00
Footprint Length	D2	.590	.620	.630	14.99	15.75	16.00
Lead Thickness	С	.008	.011	.013	0.20	0.27	0.33
Upper Lead Width	B1	.026	.029	.032	0.66	0.74	0.81
Lower Lead Width	В	.013	.020	.021	0.33	0.51	0.53
Mold Draft Angle Top	α	0	5	10	0	5	10
Mold Draft Angle Bottom	β	0	5	10	0	5	10

Notes:

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed

.010" (0.254mm) per side. JEDEC Equivalent: MO-047 Drawing No. C04-048

<sup>\*</sup> Controlling Parameter § Significant Characteristic

**NOTES:** 

#### APPENDIX A: REVISION HISTORY

#### Revision A (June 2001)

Original data sheet for the PIC18FXX2 family.

#### **Revision B (August 2002)**

This revision includes the DC and AC Characteristics Graphs and Tables. The Electrical Specifications in Section 22.0 have been updated and there have been minor corrections to the data sheet text.

#### APPENDIX B: DEVICE

**DIFFERENCES** 

The differences between the devices listed in this data sheet are shown in Table B-1.

TABLE B-1: DEVICE DIFFERENCES

Feature	PIC18F242	PIC18F252	PIC18F442	PIC18F452
Program Memory (Kbytes)	16	32	16	32
Data Memory (Bytes)	768	1536	768	1536
A/D Channels	5	5	8	8
Parallel Slave Port (PSP)	No	No	Yes	Yes
Package Types	28-pin DIP 28-pin SOIC	28-pin DIP 28-pin SOIC	40-pin DIP 44-pin PLCC 44-pin TQFP	40-pin DIP 44-pin PLCC 44-pin TQFP

# APPENDIX C: CONVERSION CONSIDERATIONS

This appendix discusses the considerations for converting from previous versions of a device to the ones listed in this data sheet. Typically, these changes are due to the differences in the process technology used. An example of this type of conversion is from a PIC16C74A to a PIC16C74B.

**Not Applicable** 

# APPENDIX D: MIGRATION FROM BASELINE TO ENHANCED DEVICES

This section discusses how to migrate from a Baseline device (i.e., PIC16C5X) to an Enhanced MCU device (i.e., PIC18FXXX).

The following are the list of modifications over the PIC16C5X microcontroller family:

**Not Currently Available** 

# APPENDIX E: MIGRATION FROM MID-RANGE TO ENHANCED DEVICES

A detailed discussion of the differences between the mid-range MCU devices (i.e., PIC16CXXX) and the enhanced devices (i.e., PIC18FXXX) is provided in AN716, "Migrating Designs from PIC16C74A/74B to PIC18F442". The changes discussed, while device specific, are generally applicable to all mid-range to enhanced device migrations.

This Application Note is available as Literature Number DS00716.

# APPENDIX F: MIGRATION FROM HIGH-END TO ENHANCED DEVICES

A detailed discussion of the migration pathway and differences between the high-end MCU devices (i.e., PIC17CXXX) and the enhanced devices (i.e., PIC18FXXX) is provided in AN726, "PIC17CXXX to PIC18FXXX Migration". This Application Note is available as Literature Number DS00726.

**NOTES:** 

#### INDEX

A		Block Diagrams	
A/D	181	A/D Converter	
A/D Converter Flag (ADIF Bit)		Analog Input Model	
A/D Converter Interrupt, Configuring		Baud Rate Generator	151
Acquisition Requirements		Capture Mode Operation	119
ADCON0 Register		Compare Mode Operation	120
ADCONO Register		Low Voltage Detect	
9		External Reference Source	190
ADRESH Register		Internal Reference Source	190
ADRESH/ADRESL Registers		MSSP	
ADRESL Register		I <sup>2</sup> C Mode	134
Analog Port Pins		MSSP (SPI Mode)	
Analog Port Pins, Configuring		On-Chip Reset Circuit	
Associated Registers	188		
Configuring the Module	184	Parallel Slave Port (PORTD and PORTE)	
Conversion Clock (TAD)	186	PIC18F2X2	
Conversion Status (GO/DONE Bit)	183	PIC18F4X2	
Conversions		PLL	
Converter Characteristics	287	PORTC (Peripheral Output Override)	
Equations		PORTD (I/O Mode)	
Acquisition Time	185	PORTE (I/O Mode)	
Minimum Charging Time		PWM Operation (Simplified)	122
Examples		RA3:RA0 and RA5 Port Pins	87
Calculating the Minimum Required		RA4/T0CKI Pin	88
	105	RA6 Pin	88
Acquisition Time		RB2:RB0 Port Pins	
Result Registers		RB3 Pin	
Special Event Trigger (CCP)		RB7:RB4 Port Pins	
TAD vs. Device Operating Frequencies		Table Read Operation	
Use of the CCP2 Trigger		Table Write Operation	
Absolute Maximum Ratings	259	Table Writes to FLASH Program Memory	
AC (Timing) Characteristics	269	Timer0 in 16-bit Mode	
Load Conditions for Device Timing			
Specifications	270	Timer0 in 8-bit Mode	
Parameter Symbology	269	Timer1	
Temperature and Voltage Specifications - AC		Timer1 (16-bit R/W Mode)	
Timing Conditions		Timer2	
ACKSTAT Status Flag		Timer3	
ADCON0 Register		Timer3 (16-bit R/W Mode)	114
GO/DONE Bit		USART	
ADCON1 Register		Asynchronous Receive	174
ADDLW		Asynchronous Transmit	172
		Watchdog Timer	
ADDWE		BN	220
ADDWFC		BNC	
ADRESH Register		BNN	
ADRESH/ADRESL Registers		BNOV	
ADRESL Register	181	BNZ	
Analog-to-Digital Converter. See A/D			222
ANDLW	218	BOR. See Brown-out Reset	005
ANDWF	219	BOV	
Assembler		BRA	223
MPASM Assembler	253	BRG. See Baud Rate Generator	
		Brown-out Reset (BOR)	
В		BSF	
Baud Rate Generator	151	BTFSC	
BC		BTFSS	224
BCF		BTG	225
BF Status Flag		Bus Collision During a STOP Condition	163
Di Cialas i lag	100	BZ	

C	D	
CALL226	Data EEPROM Memory	
Capture (CCP Module)119	Associated Registers	69
Associated Registers121	EEADR Register	
CCP Pin Configuration119	EECON1 Register	
CCPR1H:CCPR1L Registers119	EECON2 Register	
Software Interrupt119	Operation During Code Protect	
Timer1/Timer3 Mode Selection	Protection Against Spurious Write	
Capture/Compare/PWM (CCP)	Reading	
Capture Mode. See Capture	Using	
CCP1118	Write Verify	
CCPR1H Register118	Writing	
CCPR1L Register118	Data Memory	
CCP2118	General Purpose Registers	
CCPR2H Register118	Map for PIC18F242/442	
CCPR2L Register118	Map for PIC18F252/452	44
Compare Mode. See Compare	Special Function Registers	42
Interaction of Two CCP Modules118	DAW	230
PWM Mode. See PWM	DC and AC Characteristics	
Timer Resources118	Graphs and Tables	289
Clocking Scheme/Instruction Cycle39	DC Characteristics	
CLRF227	DCFSNZ	
CLRWDT	DEGF	_
Code Examples	DECFSZ	
16 x 16 Signed Multiply Routine72	Development Support	
16 x 16 Unsigned Multiply Routine72	Device Differences	
8 x 8 Signed Multiply Routine	Device Overview	
8 x 8 Unsigned Multiply Routine71	Features	
Changing Between Capture Prescalers119	Direct Addressing	
Data EEPROM Read67	Example	49
Data EEPROM Refresh Routine68	E	
Data EEPROM Write67	<del>-</del>	
Erasing a FLASH Program Memory Row60	Electrical Characteristics	
Fast Register Stack39	Errata	5
How to Clear RAM (Bank1) Using	F	
Indirect Addressing50		
Initializing PORTA87	Firmware Instructions	
Initializing PORTB90	FLASH Program Memory	
Initializing PORTC93	Associated Registers	
Initializing PORTD95	Control Registers	56
Initializing PORTE97	Erase Sequence	
Loading the SSPBUF (SSPSR) Register128	Erasing	60
Reading a FLASH Program Memory Word59	Operation During Code Protect	63
Saving STATUS, WREG and BSR	Reading	59
Registers in RAM85	TABLAT Register	58
Writing to FLASH Program Memory	Table Pointer	
Code Protection	Boundaries Based on Operation	
	Table Pointer Boundaries	
COMF	Table Reads and Table Writes	
Compare (CCP Module)	Block Diagrams	
Associated Registers121	•	n/ 50
CCP Pin Configuration120	Reads from FLASH Program Memo	
CCPR1 Register120	Writing to	
Software Interrupt120	Protection Against Spurious Writes	
Special Event Trigger109, 115, 120, 188	Unexpected Termination	
Timer1/Timer3 Mode Selection120	Write Verify	63
Configuration Bits195	G	
Context Saving During Interrupts85		
Conversion Considerations314	General Call Address Support	
CPFSEQ228	GOTO	232
CPFSGT229		
CPESLT 229		

1		Instruction Set	211
I/O Ports	87	ADDLW	217
I <sup>2</sup> C (MSSP Module)		ADDWF	
ACK Pulse	139	ADDWFC	218
Read/Write Bit Information (R/W Bit)		ANDLW	218
I <sup>2</sup> C (SSP Module)		ANDWF	219
ACK Pulse	138	BC	219
I <sup>2</sup> C Master Mode Reception		BCF	220
1 <sup>2</sup> C Mode	100	BN	220
Clock Stretching	144	BNC	221
I <sup>2</sup> C Mode (MSSP Module)		BNN	221
Registers		BNOV	222
1 <sup>2</sup> C Module	134	BNZ	222
ACK Pulse13	0 120	BOV	225
		BRA	223
Acknowledge Sequence Timing		BSF	223
Baud Rate Generator	151	BTFSC	224
Bus Collision	100	BTFSS	
Repeated START Condition		BTG	225
START Condition		BZ	-
Clock Arbitration		CALL	=
Effect of a RESET		CLRF	
General Call Address Support		CLRWDT	
Master Mode		COMF	
Operation		CPFSEQ	
Repeated START Condition Timing	154		
Master Mode START Condition	153	CPFSGT	
Master Mode Transmission	155	CPFSLT	
Multi-Master Communication, Bus Collision		DAW	
and Arbitration	159	DCFSNZ	
Multi-Master Mode	159	DECF	
Operation	138	DECFSZ	
Read/Write Bit Information (R/W Bit)13	8, 139	GOTO	
Serial Clock (RC3/SCK/SCL)		INCF	
Slave Mode		INCFSZ	
Addressing		INFSNZ	
Reception		IORLW	
Transmission		IORWF	234
Slave Mode Timing (10-bit Reception,		LFSR	235
SEN = 0)	142	MOVF	235
Slave Mode Timing (10-bit Reception,		MOVFF	236
SEN = 1)	147	MOVLB	236
Slave Mode Timing (10-bit Transmission)		MOVLW	237
Slave Mode Timing (10-bit Hansinission)	140	MOVWF	237
SEN = 0)	140	MULLW	238
Slave Mode Timing (7-bit Reception,		MULWF	238
		NEGF	239
SEN = 1)		NOP	239
Slave Mode Timing (7-bit Transmission)		POP	240
SLEEP Operation		PUSH	240
STOP Condition Timing		RCALL	241
ICEPIC In-Circuit Emulator		RESET	
ID Locations	- / -	RETFIE	
INCF		RETLW	
INCFSZ		RETURN	
In-Circuit Debugger		RLCF	
In-Circuit Serial Programming (ICSP)19	5, 210	RLNCF	
Indirect Addressing	51		
INDF and FSR Registers	50	RRCF	
Indirect Addressing Operation	51	RRNCF	-
Indirect File Operand	42	SETF	
INFSNZ	233	SLEEP	
Instruction Cycle		SUBFWB	=
Instruction Flow/Pipelining		SUBLW	
Instruction Format		SUBWF	
		SUBWFB	=
		SWAPF	248

TBLWT TSTFSZ TSTFSZ TORLW TSTFS	SP. 42 45 38 268
TSTFSZ	SP. 42 45 38 268
Master Synchronous Serial Port. See MSSP	
Memory Organization   Data Memory   Memory Organization   Data Memory   Program Memory   Memory Organization   Data Memory   Program Memory   Memory   Program Memory   Program Memory   Memory   Memory   Memory   Memory	35 268
Data Memory   Summary Table   Street	35 268
Two-Word Instructions   Program Memory   Two-Word Instructions   Two-Word In	35 268
Two-Word Instructions	268
INT Interrupt (RB0/INT). See Interrupt Sources   INTCON Register   RBIF Bit   90   INTCON Registers   75–77   Inter-Integrated Circuit. See I <sup>2</sup> C   Interrupt Sources   195   A/D Conversion Complete   184   Capture Complete (CCP)   119   Compare Complete (CCP)   120   INTO   RBIS Interrupt-on-Change (RB7:RB4)   90   PORTB, Interrupt-on-Change (RB7:RB4)   90   TMR2 to PR2 Match   111   122   TMR2 to PR2 Match   111   122   TMR2 to PR2 Match   113   USART Receive/Transmit Complete   165   Interrupts, Enable Bits   CCP1 Enable (CCP1IE Bit)   119   Interrupts, Enable Bits   CCP1 Enable (CCP1IE Bit)   119   Interrupt-on-Change (RB7:RB4)   Fig. (RBIF Bit)   100   INTO   INTERPREDICT   INTERPR	
INTCON Register	314
RBIF Bit   90	
Intraction   Training   Trainin	
Inter-Integrated Circuit. See	
Interrupt Sources	
A/D Conversion Complete (CCP) 119 Compare Complete (CCP) 119 Compare Complete (CCP) 120 INTO 85 Interrupt-on-Change (RB7:RB4) 90 PORTB, Interrupt-on-Change 85 RB0/INT Pin, External 85 TMR0 85 TMR0 105 TMR1 Overflow 105 TMR1 Overflow 107, 109 TMR2 to PR2 Match 1112 TMR2 to PR2 Match (PWM) 111, 122 TMR3 Overflow 113, 115 USART Receive/Transmit Complete 165 Interrupts, Enable Bits CCP1 Enable (CCP1 IE Bit) 119 Interrupts, Flag Bits A/D Converter Flag (ADIF Bit) 19 CCP1 Flag (CCP1 IF Bit) 19 CCP1 Flag (CCP1 IF Bit) 19 CCP1 Flag (CCP1 IF Bit) 19 CRIM (RBIF Bit) 90 IORLW 234 ICRWF 234 IPR Registers 82-83  MOVLW MOVWF MOVWF MOVWF MOVUW MOVWW MOVWF MPLAB ICT and MPLAB C18 C Compilers MPLAB ICD In-Circuit Debugger MPLAB ICD In-Circuit Debugger MPLAB ICE High Performance Universal In-Circuit Emulator with MPLAB IDE MPLAB Interruit Debugger MPLAB ICT Intervible Debugger MPLA	
Capture Complete (CCP) 119 Compare Complete (CCP) 120 INTO 85 Interrupt-on-Change (RB7:RB4) 90 PORTB, Interrupt-on-Change 85 RB0/INT Pin, External 85 TMR0 85 TMR0 85 TMR1 Overflow 105 TMR1 Overflow 111, 122 TMR2 to PR2 Match (PWM) 111, 122 TMR3 Overflow 113, 115 USART Receive/Transmit Complete 165 Interrupts, Enable Bits CCP1 Enable (CCP1IE Bit) 19 Interrupts, Flag Bits A/D Converter Flag (ADIF Bit) 19 Interrupt-on-Change (RB7:RB4) Flag (RBIF Bit) 90 IORLW 234 ICRWF 234 IR Registers 82–83  MOVWF MPLAB ICT and MPLAB C18 C Compilers	
Compare Complete (CCP)	237
INTO	237
Interrupt-on-Change (RB7:RB4 )	
PORTB, Interrupt-on-Change	25
RB0/INT Pin, External	1
TMR0	254
TMR0 Overflow         105           TMR1 Overflow         107, 109           TMR2 to PR2 Match         112           TMR2 to PR2 Match (PWM)         111, 122           TMR3 Overflow         113, 115           USART Receive/Transmit Complete         165           Interrupts         73           Logic         74           Interrupts, Enable Bits         74           CCP1 Enable (CCP1IE Bit)         119           Interrupts, Flag Bits         MULLW           A/D Converter Flag (ADIF Bit)         119           CCP1 Flag (CCP1IF Bit)         119           CCP1 Flag (CCP1IF Bit)         119           CCP1 Flag (CCP1IF Bit)         120           Interrupt-on-Change (RB7:RB4) Flag         NEGF           (RBIF Bit)         90           IORLW         234           IORWF         234           IPR Registers         82-83	
TMR1 Overflow	253
TMR1 Overflow	
TMR2 to PR2 Match	
IMR2 to PH2 Match (PWM)       111, 122         TMR3 Overflow       113, 115         USART Receive/Transmit Complete       165         Interrupts       73         Logic       74         Interrupts, Enable Bits       74         CCP1 Enable (CCP1IE Bit)       119         Interrupts, Flag Bits       87I Master Mode         A/D Converter Flag (ADIF Bit)       183         CCP1 Flag (CCP1IF Bit)       119         CCP1 Flag (CCP1IF Bit)       119         CCP1 Flag (CCP1IF Bit)       120         Interrupt-on-Change (RB7:RB4) Flag       NEGF         (RBIF Bit)       90         IORLW       234         IORWF       234         IPR Registers       82-83     Enabling SPI I/O  Operation  Typical Connection  MSSP Module  SPI Master //Slave Connection  SPI Slave Mode  MULLW  MULWF  N  NEGF  NOP  Opcode Field Descriptions  Opcode Field Description  Opcod	
TMR3 Overflow	
Typical Connection   MSSP Module   SPI Master Mode   SPI Master	
Interrupts	
Logic	120
Interrupts, Enable Bits	120
CCP1 Enable (CCP1IE Bit) 119 Interrupts, Flag Bits	
Interrupts, Flag Bits	
A/D Converter Flag (ADIF Bit) 183 CCP1 Flag (CCP1IF Bit) 119 CCP1IF Flag (CCP1IF Bit) 120 Interrupt-on-Change (RB7:RB4) Flag (RBIF Bit) 90 IORLW 234 IORWF 234 IPR Registers 82–83 Opcode Field Descriptions	
CCP1 Flag (CCP1IF Bit)	
CCP1IF Flag (CCP1IF Bit)	230
Interrupt-on-Change (RB7:RB4) Flag	
(RBIF Bit)       90         IORLW       234         IORWF       234         IPR Registers       82–83         Opcode Field Descriptions         OPTION REG Register	000
IORLW         234           IORWF         234           IPR Registers         82–83           Opcode Field Descriptions           OPTION REG Register	
IORWF	238
IPR Registers	
OPTION DEG Position	01/
	214
	401
KEELOQ Evaluation and Programming Tools	
1000 Bit	
L TOPS2:TOPS0 Bits	
LFSR	
Lookup Tables Oscillator Configuration	
Computed GOTO41	17
EGIO	17
Table Reads, Table Writes41 HS	17
Low Voltage Detect	17
Converter Characteristics	17
Effects of a RESET	17
Operation	17
Current Consumption	13
During SLEEP	19
Reference Voltage Set Point193 Oscillator. Timer1	
Typical Application	
LVD. See Low Voltage Detect	

P	RC7/RX/DT15
Packaging305	RD0/PSP016
Details	RD1/PSP116
Marking Information	RD2/PSP216
Parallel Slave Port	RD3/PSP3
PORTD100	RD4/PSP4
	RD5/PSP5
Parallel Slave Port (PSP)95, 100	RD6/PSP616
Associated Registers101	RD7/PSP716
RE0/RD/AN5 Pin	RE0/RD/AN5
RE1/WR/AN6 Pin	RE1/WR/AN6
RE2/CS/AN7 Pin99, 100	RE2/CS/AN7
Select (PSPMODE Bit)95, 100	VDD
PIC18F2X2 Pin Functions	Vss
MCLR/VPP10	
OSC1/CLKI10	PIC18FXX2 Voltage-Frequency Graph (Industrial)260
OSC2/CLKO/RA610	
RA0/AN010	PIC18LFXX2 Voltage-Frequency Graph
RA1/AN110	(Industrial)
RA2/AN2/VREF 10	PICDEM 1 Low Cost PICmicro
RA3/AN3/VREF+10	Demonstration Board
RA4/T0CKI 10	PICDEM 17 Demonstration Board
RA5/AN4/SS/LVDIN10	PICDEM 2 Low Cost PIC16CXX
RB0/INT011	Demonstration Board
RB1/INT111	PICDEM 3 Low Cost PIC16CXXX
RB2/INT211	Demonstration Board
RB3/CCP2	PICSTART Plus Entry Level Development
RB4	Programmer
RB5/PGM11	PIE Registers80-81
RB6/PGC11	Pinout I/O Descriptions
RB7/PGD11	PIC18F2X2 10
RC0/T1OSO/T1CKI12	PIR Registers78–79
RC1/T1OSI/CCP212	PLL Lock Time-out
	Pointer, FSR50
RC2/CCP1	POP
RC3/SCK/SCL12	POR. See Power-on Reset
RC4/SDI/SDA12	PORTA
RC5/SDO12	Associated Registers89
RC6/TX/CK12	LATA Register87
RC7/RX/DT12	PORTA Register
VDD12	TRISA Register
Vss12	PORTB
PIC18F4X2 Pin Functions	Associated Registers92
MCLR/VPP13	LATB Register90
OSC1/CLKI13	PORTB Register
OSC2/CLKO13	RB0/INT Pin, External
RA0/AN013	
RA1/AN113	RB7:RB4 Interrupt-on-Change Flag (RBIF Bit) 90
RA2/AN2/VREF13	TRISB Register
RA3/AN3/VREF+13	PORTC
RA4/T0CKI13	Associated Registers
RA5/AN4/SS/LVDIN13	LATC Register
RB0/INT14	PORTC Register
RB114	RC3/SCK/SCL Pin
RB214	RC7/RX/DT Pin
RB314	TRISC Register93, 165
RB414	PORTD
RB5/PGM14	Associated Registers96
RB6/PGC14	LATD Register95
RB7/PGD14	Parallel Slave Port (PSP) Function95
RC0/T1OSO/T1CKI15	PORTD Register95
RC1/T1OSI/CCP215	TRISD Register95
RC2/CCP115	
RC3/SCK/SCL15	
RC4/SDI/SDA15	
RC5/SDO	
RC6/TX/CK15	
NOU/ I A/ON	

PORTE	Registers	
Analog Port Pins99, 100	ADCON0 (A/D Control 0)	181
Associated Registers99	ADCON1 (A/D Control 1)	182
LATE Register97	CCP1CON and CCP2CON	
PORTE Register97	(Capture/Compare/PWM Control)	117
PSP Mode Select (PSPMODE Bit)95, 100	CONFIG1H (Configuration 1 High)	
RE0/RD/AN5 Pin	CONFIG2H (Configuration 2 High)	
RE1/WR/AN6 Pin	CONFIG2L (Configuration 2 Low)	
RE2/CS/AN7 Pin	CONFIG3H (Configuration 3 High)	
TRISE Register	CONFIG4L (Configuration 4 Low)	
9		
Postscaler, WDT	CONFIG5H (Configuration 5 High)	
Assignment (PSA Bit)	CONFIGSL (Configuration 5 Low)	
Rate Select (T0PS2:T0PS0 Bits)	CONFIG6H (Configuration 6 High)	
Switching Between Timer0 and WDT105	CONFIG6L (Configuration 6 Low)	
Power-down Mode. See SLEEP	CONFIG7H (Configuration 7 High)	
Power-on Reset (POR)26	CONFIG7L (Configuration 7 Low)	
Oscillator Start-up Timer (OST)26	DEVID1 (Device ID Register 1)	
Power-up Timer (PWRT)26	DEVID2 (Device ID Register 2)	202
Prescaler, Capture119	EECON1 (Data EEPROM Control 1)	57, 66
Prescaler, Timer0105	File Summary	46-48
Assignment (PSA Bit)105	INTCON (Interrupt Control)	75
Rate Select (T0PS2:T0PS0 Bits)105	INTCON2 (Interrupt Control 2)	
Switching Between Timer0 and WDT105	INTCON3 (Interrupt Control 3)	
Prescaler, Timer2	IPR1 (Peripheral Interrupt Priority 1)	
PRO MATE II Universal Device Programmer255	IPR2 (Peripheral Interrupt Priority 2)	
Product Identification System	LVDCON (LVD Control)	
Program Counter	OSCCON (Oscillator Control)	
PCL Register	PIE1 (Peripheral Interrupt Enable 1)	
PCLATH Register39	PIE2 (Peripheral Interrupt Enable 2)	
PCLATU Register39	PIR1 (Peripheral Interrupt Request 1)	
Program Memory	PIR2 (Peripheral Interrupt Request 2)	
Interrupt Vector35	RCON (Register Control)	
Map and Stack for PIC18F442/24236	RCON (RESET Control)	
Map and Stack for PIC18F452/25236	RCSTA (Receive Status and Control)	167
RESET Vector35	SSPCON1 (MSSP Control 1)	
Program Verification and Code Protection207	I <sup>2</sup> C Mode	136
Associated Registers207	SPI Mode	127
Programming, Device Instructions211	SSPCON2 (MSSP Control 2)	
PSP. See Parallel Slave Port.	I <sup>2</sup> C Mode	137
Pulse Width Modulation. See PWM (CCP Module).	SSPSTAT (MSSP Status)	
PUSH240	I <sup>2</sup> C Mode	135
PWM (CCP Module)122	SPI Mode	
Associated Registers	STATUS	
CCPR1H:CCPR1L Registers	STKPTR (Stack Pointer)	
Duty Cycle122	T0CON (Timer0 Control)	
	· ·	
Example Frequencies/Resolutions	T1CON (Timer 1 Control)	
Period	T2CON (Timer 2 Control)	
Setup for PWM Operation	T3CON (Timer3 Control)	
TMR2 to PR2 Match111, 122	TRISE	
Q	TXSTA (Transmit Status and Control)	
	WDTCON (Watchdog Timer Control)	
Q Clock122	RESET	, ,
R	Brown-out Reset (BOR)	195
	MCLR Reset (During SLEEP)	
RAM. See Data Memory	MCLR Reset (Normal Operation)	25
RC Oscillator18	Oscillator Start-up Timer (OST)	
RCALL241	Power-on Reset (POR)	
RCSTA Register	Power-up Timer (PWRT)	
SPEN Bit165	Programmable Brown-out Reset (BOR)	
Register File42	RESET Instruction	
	Stack Full Reset	
	Stack Underflow Reset	
	Watchdog Timer (WDT) Reset	
	113.009 (1151) 110001	

RETFIE242	Т	
RETLW242	TABLAT Beginter	E (
RETURN243	TABLAT Register	
Revision History313	Table Pointer Operations (table)	
RLCF243	TBLPTR Register	
RLNCF244	TBLWT	
RRCF244		
RRNCF245	Time-out Sequence Time-out in Various Situations	
~	Time-out in various Situations	
S	16-bit Mode Timer Reads and Writes	
SCI. See USART	Associated Registers	
SCK125	Clock Source Edge Select (T0SE Bit)	
SDI125	Clock Source Select (TOCS Bit)	
SDO125	Operation	
Serial Clock, SCK125	Overflow Interrupt	
Serial Communication Interface. See USART	Prescaler. See Prescaler, Timer0	100
Serial Data In, SDI125	Timer1	107
Serial Data Out, SDO125	16-bit Read/Write Mode	
Serial Peripheral Interface. See SPI	Associated Registers	
SETF245	Operation	
Slave Select Synchronization131	Oscillator107, 1	
Slave Select, SS125	Overflow Interrupt	
SLEEP195, 205, 246	Special Event Trigger (CCP)109, 1	
Software Simulator (MPLAB SIM)254	TMR1H Register	
Special Event Trigger. See Compare	TMR1L Register	
Special Features of the CPU195	Timer2	
Configuration Registers196–201	Associated Registers	
Special Function Registers42	Operation	
Map45	Postscaler. See Postscaler, Timer2	
SPI	PR2 Register111, 1	122
Master Mode130	Prescaler. See Prescaler, Timer2	122
Serial Clock125	SSP Clock Shift111, 1	112
Serial Data In125	TMR2 Register	
Serial Data Out125	TMR2 to PR2 Match Interrupt111, 112, 1	
Slave Select125	Timer3	
SPI Clock130	Associated Registers	
SPI Mode125	Operation	
SPI Master/Slave Connection129	Oscillator113, 1	
SPI Module	Overflow Interrupt113, 1	
Associated Registers133	Special Event Trigger (CCP)	
Bus Mode Compatibility133	TMR3H Register	
Effects of a RESET133	TMR3L Register	
Master/Slave Connection129	Timing Diagrams	
Slave Mode131	Bus Collision	
Slave Select Synchronization131	Transmit and Acknowledge	159
Slave Synch Timing131	A/D Conversion	
SLEEP Operation	Acknowledge Sequence	
<u>SS</u> 125	Baud Rate Generator with Clock Arbitration	
SSP	BRG Reset Due to SDA Arbitration During	
I <sup>2</sup> C Mode. See I <sup>2</sup> C	START Condition	161
SPI Mode125	Brown-out Reset (BOR)2	
SPI Mode. See SPI	Bus Collision	
SSPBUF Register	Start Condition (SDA Only)	160
SSPSR Register130	Bus Collision During a Repeated	
TMR2 Output for Clock Shift	START Condition (Case 1)	162
SSPOV Status Flag	Bus Collision During a Repeated	
SSPSTAT Register	START Condition (Case 2)	162
R/W Bit	Bus Collision During a START Condition	
Status Bits	(SCL = 0)	161
Significance and the Initialization Condition	Bus Collision During a STOP Condition	
for RCON Register	(Case 1)	163
SUBFWB	Bus Collision During a STOP Condition	
SUBLW	(Case 2)	163
SUBWF	Capture/Compare/PWM (CCP1 and CCP2)	
SUBWFB	CLKO and I/O2	272
SWAPF248	Clock Synchronization	

Example SPI Master Mode (CKE = 0)278	USART Synchronous Transmission	
Example SPI Master Mode (CKE = 1)279	(Through TXEN)	
Example SPI Slave Mode (CKE = 0)280	Wake-up from SLEEP via Interrupt	206
Example SPI Slave Mode (CKE = 1)281	Timing Diagrams Requirements	
External Clock (All Modes except PLL)271	Master SSP I <sup>2</sup> C Bus START/STOP Bits	284
First START Bit Timing153	Timing Requirements	
I <sup>2</sup> C Bus Data282	A/D Conversion	
I <sup>2</sup> C Bus START/STOP Bits282	Capture/Compare/PWM (CCP1 and CCP2)	
I <sup>2</sup> C Master Mode (Reception, 7-bit Address) 157	CLKO and I/O	
I <sup>2</sup> C Master Mode (Transmission,	Example SPI Mode (Master Mode, $CKE = 0$ )	
7 or 10-bit Address)	Example SPI Mode (Master Mode, CKE = 1)	
I <sup>2</sup> C Slave Mode Timing (10-bit Reception,	Example SPI Mode (Slave Mode, CKE = 0)	
SEN = 0)	Example SPI Slave Mode (CKE = 1)	
I <sup>2</sup> C Slave Mode Timing (10-bit Transmission) 143	External Clock	
I <sup>2</sup> C Slave Mode Timing (7-bit Reception,	I <sup>2</sup> C Bus Data (Slave Mode)	
SEN = 0)	Master SSP I <sup>2</sup> C Bus Data	
I <sup>2</sup> C Slave Mode Timing (7-bit Reception,	Parallel Slave Port (PIC18F4X2)	277
SEN = 1)	RESET, Watchdog Timer, Oscillator Start-up	
I <sup>2</sup> C Slave Mode Timing (7-bit Transmission)141	Timer, Power-up Timer and	07
Low Voltage Detect	Brown-out Reset Requirements	
Master SSP I <sup>2</sup> C Bus Data	Timer0 and Timer1 External Clock	
Master SSP I <sup>2</sup> C Bus START/STOP Bits	USART Synchronous Receive	
Parallel Slave Port (PIC18F4X2)277	USART Synchronous Transmission	286
Parallel Slave Port (Read)	Timing Specifications PLL Clock	070
Parallel Slave Port (Write)		272
PWM Output	TRISE Register PSPMODE Bit	OF 100
Repeat START Condition	TSTFSZ	
RESET, Watchdog Timer (WDT),	Two-Word Instructions	201
Oscillator Start-up Timer (OST) and	Example Cases	41
Power-up Timer (PWRT)273 Slave Synchronization	TXSTA Register	41
Slave Synchionization	I ASTA REGISTER	
		169
Slaver Mode General Call Address Sequence	BRGH Bit	168
Slaver Mode General Call Address Sequence (7 or 10-bit Address Mode)148		168
Slaver Mode General Call Address Sequence (7 or 10-bit Address Mode)	BRGH Bit	168
Slaver Mode General Call Address Sequence         (7 or 10-bit Address Mode)	BRGH Bit  U Universal Synchronous Asynchronous	168
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)	BRGH Bit  U Universal Synchronous Asynchronous Receiver Transmitter. See USART	
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)	BRGH Bit  U Universal Synchronous Asynchronous Receiver Transmitter. See USART USART	165
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)	BRGH Bit  U Universal Synchronous Asynchronous Receiver Transmitter. See USART USART Asynchronous Mode	165 172
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled	U Universal Synchronous Asynchronous Receiver Transmitter. See USART USART Asynchronous Mode Associated Registers, Receive	165 172 175
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         33	BRGH Bit  U Universal Synchronous Asynchronous Receiver Transmitter. See USART USART Asynchronous Mode	165 172 175
Slaver Mode General Call Address Sequence	U Universal Synchronous Asynchronous Receiver Transmitter. See USART USART Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit	165 172 175 173
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         33	BRGH Bit	165 172 175 173 174
Slaver Mode General Call Address Sequence	U Universal Synchronous Asynchronous Receiver Transmitter. See USART USART Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver	165 172 173 174 172 172
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         Time-out Sequence on Power-up       (MCLR Not Tied to VDD)         Case 1       32         Case 2       32	U Universal Synchronous Asynchronous Receiver Transmitter. See USART USART Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter Baud Rate Generator (BRG)	165 172 175 174 172 172 168
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         (MCLR Not Tied to VDD)       33         Time-out Sequence on Power-up       (MCLR Not Tied to VDD)         Case 1       32         Case 2       32         Time-out Sequence on Power-up       32	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter Baud Rate Generator (BRG) Associated Registers	165 172 175 174 168 168
Slaver Mode General Call Address Sequence	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode  Associated Registers, Receive  Associated Registers, Transmit  Receiver  Transmitter  Baud Rate Generator (BRG)  Associated Registers  Baud Rate Error, Calculating  Baud Rate Formula	165 172 175 174 168 168
Slaver Mode General Call Address Sequence	U Universal Synchronous Asynchronous Receiver Transmitter. See USART USART Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter Baud Rate Generator (BRG) Associated Registers Baud Rate Error, Calculating	165 172 175 174 172 168 168
Slaver Mode General Call Address Sequence	U Universal Synchronous Asynchronous Receiver Transmitter. See USART USART Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter Baud Rate Generator (BRG) Associated Registers Baud Rate Error, Calculating Baud Rate Formula Baud Rates for Asynchronous Mode	165 172 175 174 172 168 168
Slaver Mode General Call Address Sequence	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode  Associated Registers, Receive  Associated Registers, Transmit  Receiver  Transmitter  Baud Rate Generator (BRG)  Associated Registers  Baud Rate Formula  Baud Rates for Asynchronous Mode  (BRGH = 0)	165 172 175 174 172 168 168
Slaver Mode General Call Address Sequence	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode  Associated Registers, Receive  Associated Registers, Transmit  Receiver  Transmitter  Baud Rate Generator (BRG)  Associated Registers  Baud Rate Formula  Baud Rate Formula  Baud Rates for Asynchronous Mode  (BRGH = 0)  Baud Rates for Asynchronous Mode	165 172 173 174 168 168 170
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         Case 1       32         Case 1       32         Case 2       32         Time-out Sequence on Power-up       (MCLR Tied to VDD)         (MCLR Tied to VDD)       32         Timero and Timer1 External Clock       275         Timing for Transition Between Timer1 and       OSC1 (HS with PLL)       23         Transition Between Timer1 and OSC1       (HS, XT, LP)       22	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter  Baud Rate Generator (BRG) Associated Registers Baud Rate Formula Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1)	165 172 175 174 168 168 168 170 171
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         Case 1       32         Case 1       32         Case 2       32         Time-out Sequence on Power-up       (MCLR Tied to VDD)         (MCLR Tied to VDD)       32         Timero and Timer1 External Clock       275         Timing for Transition Between Timer1 and       OSC1 (HS with PLL)       23         Transition Between Timer1 and OSC1	U Universal Synchronous Asynchronous Receiver Transmitter. See USART USART Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter Baud Rate Generator (BRG) Associated Registers Baud Rate Formula Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1) Baud Rates for Synchronous Mode	165 172 173 174 168 168 168 170 171 169 168
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         Case 1 me-out Sequence on Power-up       32         Case 2 meter 32       32         Time-out Sequence on Power-up       32         (MCLR Tied to VDD)       32         Timerout Sequence on Power-up       32         (MCLR Tied to VDD)       32         Timero and Timer1 External Clock       275         Timing for Transition Between Timer1 and OSC1       23         Transition Between Timer1 and OSC1       22         Transition Between Timer1 and OSC1       22          Transition Between Timer1 and OSC1       22          Transition Between Timer1 and OSC1       22          Transition Between Timer1 and OSC1       23          Transition Between Timer1 and OSC1       24	U Universal Synchronous Asynchronous Receiver Transmitter. See USART USART Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter Baud Rate Generator (BRG) Associated Registers Baud Rate Formula Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1) Baud Rates for Synchronous Mode High Baud Rate Select (BRGH Bit)	165 172 173 174 168 168 170 171 169 168
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         Case 1       32         Case 1       32         Case 2       32         Time-out Sequence on Power-up       (MCLR Tied to VDD)         (MCLR Tied to VDD)       32         Timer0 and Timer1 External Clock       275         Timing for Transition Between Timer1 and       OSC1 (HS with PLL)       23         Transition Between Timer1 and OSC1       (HS, XT, LP)       22         Transition Between Timer1 and OSC1       (RC, EC)       23	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter  Baud Rate Generator (BRG) Associated Registers Baud Rate Formula Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1) Baud Rates for Synchronous Mode High Baud Rate Select (BRGH Bit) Sampling	165 172 173 174 168 168 168 170 171 168 168 170 168 168 168
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         (MCLR Not Tied to VDD)       33         Time-out Sequence on Power-up       (MCLR Tied to VDD)         Case 1       32         Case 2       32         Timerout Sequence on Power-up       (MCLR Tied to VDD)         (MCLR Tied to VDD)       32         Timing for Transition Between Timer1 and OSC1       275         Timing for Transition Between Timer1 and OSC1       22         Transition Between Timer1 and OSC1       23         Transition from OSC1 to Timer1 Oscillator       22	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode  Associated Registers, Receive  Associated Registers, Transmit  Receiver  Transmitter  Baud Rate Generator (BRG)  Associated Registers  Baud Rate Formula  Baud Rate Formula  Baud Rates for Asynchronous Mode  (BRGH = 0)  Baud Rates for Asynchronous Mode  (BRGH = 1)  Baud Rates for Synchronous Mode  High Baud Rate Select (BRGH Bit)  Sampling  Serial Port Enable (SPEN Bit)	165 172 173 174 168 168 170 171 168 176 168 176 171 168 176 178 178
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         Case 1       32         Case 1       32         Case 2       32         Time-out Sequence on Power-up       (MCLR Tied to VDD)         (MCLR Tied to VDD)       32         Timer0 and Timer1 External Clock       275         Timing for Transition Between Timer1 and       OSC1 (HS with PLL)       23         Transition Between Timer1 and OSC1       (HS, XT, LP)       22         Transition Between Timer1 and OSC1       (RC, EC)       23         Transition from OSC1 to Timer1 Oscillator       22         USART Asynchronous Master Transmission       173	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter  Baud Rate Generator (BRG) Associated Registers Baud Rate Frorn, Calculating Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1) Baud Rates for Synchronous Mode High Baud Rate Select (BRGH Bit) Sampling Serial Port Enable (SPEN Bit) Synchronous Master Mode	165 172 173 174 168 168 170 171 168 176 176 177 168 178 178 178
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         Case 1       32         Case 1       32         Case 2       32         Time-out Sequence on Power-up       (MCLR Tied to VDD)         (MCLR Tied to VDD)       32         Timer0 and Timer1 External Clock       275         Timing for Transition Between Timer1 and       OSC1 (HS with PLL)       23         Transition Between Timer1 and OSC1       (HS, XT, LP)       22         Transition Between Timer1 and OSC1       23         Transition from OSC1 to Timer1 Oscillator       22         USART Asynchronous Master Transmission       173         USART Asynchronous Master Transmission	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter  Baud Rate Generator (BRG) Associated Registers Baud Rate Frorn, Calculating Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1) Baud Rates for Synchronous Mode High Baud Rate Select (BRGH Bit) Sampling Serial Port Enable (SPEN Bit) Synchronous Master Mode Associated Registers, Reception	165 172 173 174 168 168 170 171 168 176 176 177 168 178 178 178
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         (MCLR Not Tied to VDD)       33         Time-out Sequence on Power-up       32         Case 1       32         Time-out Sequence on Power-up       32         Timer0 and Timer1 External Clock       275         Timing for Transition Between Timer1 and       0SC1 (HS with PLL)       23         Transition Between Timer1 and OSC1       (HS, XT, LP)       22         Transition Between Timer1 and OSC1       (RC, EC)       23         Transition from OSC1 to Timer1 Oscillator       22         USART Asynchronous Master Transmission       173         USART Asynchronous Master Transmission       173	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter  Baud Rate Generator (BRG) Associated Registers Baud Rate Error, Calculating Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1) Baud Rates for Synchronous Mode High Baud Rate Select (BRGH Bit) Sampling Serial Port Enable (SPEN Bit) Synchronous Master Mode Associated Registers, Reception Associated Registers, Transmit	165 172 173 172 168 168 170 171 169 168 176 177 178 178 178
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         Case 1       32         Case 2       32         Time-out Sequence on Power-up       32         Case 2       32         Timerout Sequence on Power-up       32         (MCLR Tied to VDD)       32         Timer0 and Timer1 External Clock       275         Timing for Transition Between Timer1 and       0SC1 (HS with PLL)       23         Transition Between Timer1 and OSC1       (HS, XT, LP)       22         Transition Between Timer1 and OSC1       (RC, EC)       23         Transition from OSC1 to Timer1 Oscillator       22         USART Asynchronous Master Transmission       173         USART Asynchronous Reception       175	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter  Baud Rate Generator (BRG) Associated Registers Baud Rate Error, Calculating Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1) Baud Rates for Synchronous Mode High Baud Rate Select (BRGH Bit) Sampling Serial Port Enable (SPEN Bit) Synchronous Master Mode Associated Registers, Reception Associated Registers, Transmit Reception	165 172 173 174 168 168 170 171 168 176 176 176 176 176 176 176 176
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         (MCLR Not Tied to VDD)       33         Time-out Sequence on Power-up       32         Case 1       32         Case 2       32         Timer0 and Timer1 External Clock       275         Timing for Transition Between Timer1 and       0SC1 (HS with PLL)       23         Transition Between Timer1 and OSC1       (HS, XT, LP)       22         Transition Between Timer1 and OSC1       (RC, EC)       23         Transition from OSC1 to Timer1 Oscillator       22         USART Asynchronous Master Transmission       173         USART Asynchronous Reception       175         USART Synchronous Reception       175         USART Synchronous Reception       286	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter Baud Rate Generator (BRG) Associated Registers Baud Rate Error, Calculating Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1) Baud Rates for Synchronous Mode High Baud Rate Select (BRGH Bit) Sampling Serial Port Enable (SPEN Bit) Synchronous Master Mode Associated Registers, Reception Associated Registers, Transmit Reception Transmission	165 172 173 174 168 168 170 171 168 176 176 176 176 178 176 176 176 176 176 176 176 176 176 176 176 176 176 176 176
Slaver Mode General Call Address Sequence       (7 or 10-bit Address Mode)       148         Slow Rise Time (MCLR Tied to VDD)       33         SPI Mode (Master Mode)       130         SPI Mode (Slave Mode with CKE = 0)       132         SPI Mode (Slave Mode with CKE = 1)       132         Stop Condition Receive or Transmit Mode       158         Time-out Sequence on POR w/PLL Enabled       (MCLR Tied to VDD)         (MCLR Not Tied to VDD)       33         Time-out Sequence on Power-up       32         Case 1       32         Case 2       32         Timerout Sequence on Power-up       32         (MCLR Tied to VDD)       32         Timero and Timer1 External Clock       275         Timing for Transition Between Timer1 and       0SC1 (HS with PLL)         OSC1 (HS with PLL)       23         Transition Between Timer1 and OSC1       22         (HS, XT, LP)       22         Transition From OSC1 to Timer1 Oscillator       22         USART Asynchronous Master Transmission       173         USART Synchronous Reception       175         USART Synchronous Reception       175         USART Synchronous Transmission       178         USART Synchronous Transmission       177 <td>Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter  Baud Rate Generator (BRG) Associated Registers Baud Rate Error, Calculating Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1) Baud Rates for Synchronous Mode (BRGH = 1) Sampling Serial Port Enable (SPEN Bit) Synchronous Master Mode Associated Registers, Reception Associated Registers, Transmit Reception Transmission Synchronous Slave Mode Associated Registers, Receive Associated Registers, Receive Associated Registers, Transmit</td> <td> 165 172 175 176 168 168 170 171 168 176</td>	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter  Baud Rate Generator (BRG) Associated Registers Baud Rate Error, Calculating Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1) Baud Rates for Synchronous Mode (BRGH = 1) Sampling Serial Port Enable (SPEN Bit) Synchronous Master Mode Associated Registers, Reception Associated Registers, Transmit Reception Transmission Synchronous Slave Mode Associated Registers, Receive Associated Registers, Receive Associated Registers, Transmit	165 172 175 176 168 168 170 171 168 176
Slaver Mode General Call Address Sequence	Universal Synchronous Asynchronous Receiver Transmitter. See USART USART  Asynchronous Mode Associated Registers, Receive Associated Registers, Transmit Receiver Transmitter  Baud Rate Generator (BRG) Associated Registers Baud Rate Formula Baud Rate Formula Baud Rates for Asynchronous Mode (BRGH = 0) Baud Rates for Asynchronous Mode (BRGH = 1) Baud Rates for Synchronous Mode High Baud Rate Select (BRGH Bit) Sampling Serial Port Enable (SPEN Bit) Synchronous Master Mode Associated Registers, Reception Associated Registers, Transmit Reception Transmission Synchronous Slave Mode Associated Registers, Receive	165 172 175 172 168 168 170 171 168 176 176 176 178 178 178 178 178 178 178 178 178 178 178 178 178 178 178 178 178

W	
Wake-up from SLEEP	195, 205
Using Interrupts	205
Watchdog Timer (WDT)	195, 203
Associated Registers	204
Control Register	203
Postscaler	203, 204
Programming Considerations	203
RC Oscillator	203
Time-out Period	203
WCOL	153
WCOL Status Flag	153, 155, 158

WWW, On-Line Support ......5

X	
XORLW	
XORWF	

**NOTES:** 

#### ON-LINE SUPPORT

Microchip provides on-line support on the Microchip World Wide Web site.

The web site is used by Microchip as a means to make files and information easily available to customers. To view the site, the user must have access to the Internet and a web browser, such as Netscape<sup>®</sup> or Microsoft<sup>®</sup> Internet Explorer. Files are also available for FTP download from our FTP site.

#### Connecting to the Microchip Internet Web Site

The Microchip web site is available at the following URL:

#### www.microchip.com

The file transfer site is available by using an FTP service to connect to:

#### ftp://ftp.microchip.com

The web site and file transfer site provide a variety of services. Users may download files for the latest Development Tools, Data Sheets, Application Notes, User's Guides, Articles and Sample Programs. A variety of Microchip specific business information is also available, including listings of Microchip sales offices, distributors and factory representatives. Other data available for consideration is:

- · Latest Microchip Press Releases
- Technical Support Section with Frequently Asked Questions
- · Design Tips
- · Device Errata
- Job Postings
- · Microchip Consultant Program Member Listing
- Links to other useful web sites related to Microchip Products
- Conferences for products, Development Systems, technical information and more
- · Listing of seminars and events

## SYSTEMS INFORMATION AND UPGRADE HOT LINE

The Systems Information and Upgrade Line provides system users a listing of the latest versions of all of Microchip's development systems software products. Plus, this line provides information on how customers can receive the most current upgrade kits. The Hot Line Numbers are:

1-800-755-2345 for U.S. and most of Canada, and 1-480-792-7302 for the rest of the world.

092002

#### **READER RESPONSE**

It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter, and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 792-4150.

Please list the following information, and use this outline to provide us with your comments about this document.

To:	Technical Publications Manager	Total Pages Sent
RE:	Reader Response	
Fron	m: Name	
	Telephone: ()	FAX: ()
Appl	lication (optional):	
Wou	ıld you like a reply?YN	
Devi	ice: PIC18FXX2 Literature	Number: DS39564B
Que	estions:	
1.	What are the best features of this documen	1?
2.	How does this document meet your hardwa	re and software development needs?
-		
3.	Do you find the organization of this docume	nt easy to follow? If not, why?
4.	What additions to the document do you thin	k would enhance the structure and subject?
-		
5.	What deletions from the decument could be	made without affecting the overall usefulness?
J.	what deletions from the document could be	made without affecting the overall decidiness:
-		
6.	Is there any incorrect or misleading informa	tion (what and where)?
-		
-		
7.	How would you improve this document?	
-		
-		

#### PIC18FXX2 PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

PART NO.	_	X	<u>/XX</u>	xxx	Exa	amples
Device		Temperature Range	Package	Pattern	a)	PIC1 PDIP QTP
Device	VD PIC18L	XX2 <sup>(1)</sup> , PIC18FXX D range 4.2V to 5. FXX2 <sup>(1)</sup> , PIC18LFX D range 2.5V to 5.	5V XX2T <sup>(2)</sup> ;		b)	PIC1 SOIC PIC1 PDIP
Temperature Range	I = E =	-40°C to +85°C -40°C to +125°C	'			
Package	SO =	Skinny Plastic DI			Not	te 1: F L 2: T
Pattern		QTP, Code or Spec therwise)	cial Requirem	ents		

- 18LF452 I/P 301 = Industrial temp., package, Extended VDD limits, pattern #301.
- 8LF242 I/SO = Industrial temp., C package, Extended VDD limits.
- 8F442 E/P = Extended temp., package, normal VDD limits.

= Standard Voltage range Wide Voltage Range in tape and reel - SOIC, PLCC, and TQFP packages only.

#### **Sales and Support**

Products supported by a preliminary Data Sheet may have an errata sheet describing minor operational differences and recommended workarounds. To determine if an errata sheet exists for a particular device, please contact one of the following:

- Your local Microchip sales office
- The Microchip Corporate Literature Center U.S. FAX: (480) 792-7277 2.
- 3. The Microchip Worldwide Site (www.microchip.com)

Please specify which device, revision of silicon and Data Sheet (include Literature #) you are using.

#### **New Customer Notification System**

Register on our web site (www.microchip.com/cn) to receive the most current information on our products.



### WORLDWIDE SALES AND SERVICE

#### **AMERICAS**

#### **Corporate Office**

2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200 Fax: 480-792-7277 Technical Support: 480-792-7627 Web Address: http://www.microchip.com

#### **Rocky Mountain**

2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7966 Fax: 480-792-4338

#### Atlanta

500 Sugar Mill Road, Suite 200B Atlanta, GA 30350 Tel: 770-640-0034 Fax: 770-640-0307

#### **Boston**

2 Lan Drive, Suite 120 Westford, MA 01886 Tel: 978-692-3848 Fax: 978-692-3821

#### Chicago

333 Pierce Road, Suite 180 Itasca, IL 60143 Tel: 630-285-0071 Fax: 630-285-0075

#### **Dallas**

4570 Westgrove Drive, Suite 160 Addison, TX 75001 Tel: 972-818-7423 Fax: 972-818-2924

#### Detroit

Tri-Atria Office Building 32255 Northwestern Highway, Suite 190 Farmington Hills, MI 48334 Tel: 248-538-2250 Fax: 248-538-2260

#### Kokomo

2767 S. Albright Road Kokomo, Indiana 46902 Tel: 765-864-8360 Fax: 765-864-8387

#### Los Angeles

18201 Von Karman, Suite 1090 Irvine, CA 92612

Tel: 949-263-1888 Fax: 949-263-1338

#### **New York**

150 Motor Parkway, Suite 202 Hauppauge, NY 11788 Tel: 631-273-5305 Fax: 631-273-5335

#### San Jose

Microchip Technology Inc. 2107 North First Street, Suite 590 San Jose, CA 95131 Tel: 408-436-7950 Fax: 408-436-7955

#### **Toronto**

6285 Northam Drive, Suite 108 Mississauga, Ontario L4V 1X5, Canada Tel: 905-673-0699 Fax: 905-673-6509

#### ASIA/PACIFIC

#### **Australia**

Microchip Technology Australia Pty Ltd Suite 22, 41 Rawson Street Epping 2121, NSW Australia

Tel: 61-2-9868-6733 Fax: 61-2-9868-6755

#### China - Beijing

Microchip Technology Consulting (Shanghai) Co., Ltd., Beijing Liaison Office Unit 915 Bei Hai Wan Tai Bldg. No. 6 Chaoyangmen Beidajie

Beijing, 100027, No. China Tel: 86-10-85282100 Fax: 86-10-85282104

#### China - Chengdu

Microchip Technology Consulting (Shanghai) Co., Ltd., Chengdu Liaison Office Rm. 2401, 24th Floor, Ming Xing Financial Tower No. 88 TIDU Street Chenadu 610016, China Tel: 86-28-86766200 Fax: 86-28-86766599

#### China - Fuzhou

Microchip Technology Consulting (Shanghai) Co., Ltd., Fuzhou Liaison Office Unit 28F, World Trade Plaza No. 71 Wusi Road Fuzhou 350001, China Tel: 86-591-7503506 Fax: 86-591-7503521

#### China - Shanghai

Microchip Technology Consulting (Shanghai) Co., Ltd.

Room 701, Bldg. B Far East International Plaza No. 317 Xian Xia Road Shanghai, 200051

Tel: 86-21-6275-5700 Fax: 86-21-6275-5060

#### China - Shenzhen

Microchip Technology Consulting (Shanghai) Co., Ltd., Shenzhen Liaison Office Rm. 1315, 13/F, Shenzhen Kerry Centre, Renminnan Lu Shenzhen 518001, China

Tel: 86-755-82350361 Fax: 86-755-82366086

#### China - Hong Kong SAR

Microchip Technology Hongkong Ltd. Unit 901-6, Tower 2, Metroplaza 223 Hing Fong Road Kwai Fong, N.T., Hong Kong Tel: 852-2401-1200 Fax: 852-2401-3431

#### India

Microchip Technology Inc. India Liaison Office Divyasree Chambers 1 Floor, Wing A (A3/A4) No. 11, O'Shaugnessey Road Bangalore, 560 025, India Tel: 91-80-2290061 Fax: 91-80-2290062

#### Japan

Microchip Technology Japan K.K. Benex S-1 6F 3-18-20, Shinyokohama Kohoku-Ku, Yokohama-shi Kanagawa, 222-0033, Japan Tel: 81-45-471- 6166 Fax: 81-45-471-6122

#### Korea

Microchip Technology Korea 168-1, Youngbo Bldg. 3 Floor Samsung-Dong, Kangnam-Ku Seoul, Korea 135-882 Tel: 82-2-554-7200 Fax: 82-2-558-5934

#### Singapore

Microchip Technology Singapore Pte Ltd. 200 Middle Road #07-02 Prime Centre Singapore, 188980 Tel: 65-6334-8870 Fax: 65-6334-8850

#### Taiwan

Microchip Technology (Barbados) Inc., Taiwan Branch 11F-3, No. 207 Tung Hua North Road Taipei, 105, Taiwan Tel: 886-2-2717-7175 Fax: 886-2-2545-0139

#### **EUROPE**

#### Austria

Microchip Technology Austria GmbH Durisolstrasse 2 A-4600 Wels Austria Tel: 43-7242-2244-399 Fax: 43-7242-2244-393

#### Denmark

Microchip Technology Nordic ApS Regus Business Centre Lautrup hoj 1-3 Ballerup DK-2750 Denmark Tel: 45 4420 9895 Fax: 45 4420 9910

#### **France**

Microchip Technology SARL Parc d'Activite du Moulin de Massy 43 Rue du Saule Trapu Batiment A - ler Etage 91300 Massy, France Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

#### Germany

Microchip Technology GmbH Steinheilstrasse 10 D-85737 Ismaning, Germany Tel: 49-89-627-144 0 Fax: 49-89-627-144-44

#### Italy

Microchip Technology SRL Centro Direzionale Colleoni Palazzo Taurus 1 V. Le Colleoni 1 20041 Agrate Brianza Milan, Italy
Tel: 39-039-65791-1 Fax: 39-039-6899883

#### **United Kingdom**

Microchip Ltd 505 Eskdale Road Winnersh Triangle Wokingham Berkshire, England RG41 5TU Tel: 44 118 921 5869 Fax: 44-118 921-5820

08/01/02